

NOTICE TO WATER WELL CONTRACTOR  
The original and first copy of this report  
are to be filed with the

WATER RESOURCES DEPARTMENT,  
SALEM, OREGON 97310  
within 30 days from the date  
of well completion.

2701  
MARI...

RECEIVED  
STATE OF OREGON  
OCT 1 1978  
WATER RESOURCES DEPT.  
(Do not write above this line)

State Well No. 55/2w-28ca  
State Permit No. G-8520

(1) OWNER:

Name Billy R & Joyce Hammond  
Address Rt 1 Box 16  
GERVAIS, OREGON

(2) TYPE OF WORK (check):

New Well  Deepening  Reconditioning  Abandon   
If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary  Driven   
Cable  Jetted   
Dug  Bored

(4) PROPOSED USE (check):

Domestic  Industrial  Municipal   
Irrigation  Test Well  Other

CASING INSTALLED:

Threaded  Welded   
10" Diam. from 0 ft. to 160 ft. Gage 250  
" Diam. from " ft. to " ft. Gage "  
" Diam. from " ft. to " ft. Gage "

PERFORATIONS:

Perforated?  Yes  No.  
Type of perforator used Mills Knife  
Size of perforations 2 in. by 1/4 in.  
125 perforations from 130 ft. to 148 ft.  
perforations from " ft. to " ft.  
perforations from " ft. to " ft.

(7) SCREENS:

Well screen installed?  Yes  No  
Manufacturer's Name \_\_\_\_\_  
Type \_\_\_\_\_ Model No. \_\_\_\_\_  
Diam. \_\_\_\_\_ Slot size \_\_\_\_\_ Set from \_\_\_\_\_ ft. to \_\_\_\_\_ ft.  
Diam. \_\_\_\_\_ Slot size \_\_\_\_\_ Set from \_\_\_\_\_ ft. to \_\_\_\_\_ ft.

(8) WELL TESTS:

Drawdown is amount water level is lowered below static level STETLER  
Was a pump test made?  Yes  No If yes, by whom? DUMP  
Yield: 570 gal./min. with 95 ft. drawdown after 2 hrs.  
" " " " " "  
" " " " " "  
Bailer test gal./min. with ft. drawdown after hrs.  
Artesian flow g.p.m.  
Temperature of water Depth artesian flow encountered ft.

(9) CONSTRUCTION:

Well seal—Material used Bentonite  
Well sealed from land surface to 25 ft.  
Diameter of well bore to bottom of seal 14 in.  
Diameter of well bore below seal 10 in.  
Number of sacks of cement used in well seal 4 sacks  
How was cement grout placed? \_\_\_\_\_  
Was a drive shoe used?  Yes  No Plugs \_\_\_\_\_ Size: location \_\_\_\_\_ ft.  
Did any strata contain unusable water?  Yes  No  
Type of water? \_\_\_\_\_ depth of strata \_\_\_\_\_  
Method of sealing strata off \_\_\_\_\_  
Was well gravel packed?  Yes  No Size of gravel: \_\_\_\_\_  
Gravel placed from \_\_\_\_\_ ft. to \_\_\_\_\_ ft.

(10) LOCATION OF WELL:

County MARION Driller's well number \_\_\_\_\_  
NE 1/4 SE 1/4 Section 28 T. 55 R. 2W W.M.  
Bearing and distance from section or subdivision corner \_\_\_\_\_

(11) WATER LEVEL: Completed well.

Depth at which water was first found 40 ft.  
Static level 40 ft. below land surface. Date \_\_\_\_\_  
Artesian pressure \_\_\_\_\_ lbs. per square inch. Date \_\_\_\_\_

(12) WELL LOG:

Diameter of well below casing \_\_\_\_\_  
Depth drilled 160 ft. Depth of completed well 160 ft.  
Formation: Describe color, texture, grain size and structure of materials; and show thickness and nature of each stratum and aquifer penetrated, with at least one entry for each change of formation. Report each change in position of Static Water Level and indicate principal water-bearing strata.

MATERIAL	From	To	SWL
Light Brown Clay	0	40	
Blue Silty Clay	40	80	
Blue Silty Sand	80	124	
Sandy Gravel	124	150	
Blue Clay	150	152	
BROWN SAND	152	155	
Blue Clay	155	160	

RECEIVED

NOV 16 1978

WATER RESOURCES DEPT.  
SALEM, OREGON

Work started 8/5 1978 Completed 8/10 1978  
Date well drilling machine moved off of well 8/10 1978

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision. Materials used and information reported above are true to my best knowledge and belief.

[Signed] Eugene Jordan Date 15 Aug, 1978  
(Drilling Machine Operator)

Drilling Machine Operator's License No. 607

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

Name Eugene Jordan  
(Person, firm or corporation) (Type or print)

Address 2026 SE 1st Canyon Rd

[Signed] Eugene Jordan  
(Water Well Contractor)

Contractor's License No. 670 Date 15 Aug, 1978