

NOTICE TO WATER WELL CONTRACTOR

The original and first copy of this report are to be filed with the

RECEIVED
STATE ENGINEER
SALEM, OREGON

WATER WELL REPORT

STATE OF OREGON

(Please type or print)
 Do not write above this line

2738
 MARI.....

State Well No. 5/2W-30

State Permit No.

STATE ENGINEER, SALEM, OREGON 97310
 within 30 days from the date of well completion

(1) OWNER:

Name ROBERT ZIELINSKI
 Address Rt. 1 BOX 59 GERVASIS ORE 97026

(2) TYPE OF WORK (check):

New Well Deepening Reconditioning Abandon

If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary Driven
 Cable Jetted
 Dug Bored

(4) PROPOSED USE (check):

Domestic Industrial Municipal
 Irrigation Test Well Other

CASING INSTALLED:

Threaded Welded
 10" Diam. from 0 ft. to 153 ft. Gage 1/4"
 " Diam. from ft. to ft. Gage
 " Diam. from ft. to ft. Gage

PERFORATIONS:

Perforated? Yes No
 Type of perforator used MILLS
 Size of perforations 3/8 in. by 2 1/2 in.
 100 perforations from 112 ft. to 116'6" ft.
 200 perforations from 125 ft. to 135 ft.
 240 perforations from 140 ft. to 150 ft.
 perforations from ft. to ft.
 perforations from ft. to ft.

(7) SCREENS:

Well screen installed? Yes No
 Manufacturer's Name
 Type Model No.
 Diam. Slot size Set from ft. to ft.
 Diam. Slot size Set from ft. to ft.

(8) WATER LEVEL: Completed well.

Static level 20' ft. below land surface Date 2-9-69
 Artesian pressure lbs. per square inch Date

(9) WELL TESTS:

Drawdown is amount water level is lowered below static level
 Was a pump test made? Yes No If yes, by whom? STETTLER SUPPLY
 Yield: 540 gal./min. with 62 ft. drawdown after 1 hrs.
700 " 85 " 1/2 "
820 " 103 " 1/2 "
 Bailer test gal./min. with ft. drawdown after hrs.
 Artesian flow g.p.m. Date
 Temperature of water 57' Was a chemical analysis made? Yes No

(10) CONSTRUCTION:

Well seal—Material used PUDDLIED CLAY
 Depth of seal 80' ft.
 Diameter of well bore to bottom of seal 14" in.
 Were any loose strata cemented off? Yes No Depth
 Was a drive shoe used? Yes No
 Did any strata contain unusable water? Yes No
 Type of water? SANDY depth of strata 65' TO 78'
 Method of sealing strata off CASED PACKER
 Was well gravel packed? Yes No Size of gravel: 3/4" CRUSHED
 Gravel placed from 90' ft. to 108' ft.

(11) LOCATION OF WELL:

County MARION Driller's well number
 1/4 Section 30 T. 55 R. 2W W.M.
 Bearing and distance from section or subdivision corner

(12) WELL LOG:

Diameter of well below casing 10"
 Depth drilled 153' ft. Depth of completed well 153' ft.

Formation: Describe color, texture, grain size and structure of materials; and show thickness and nature of each stratum and aquifer penetrated, with at least one entry for each change of formation. Report each change in position of Static Water Level as drilling proceeds. Note drilling rates.

MATERIAL	From	To	SWL
TOPSOIL	0	1'6"	
CLAY YELLOW	1'6"	2'9"	
CLAY BLUE SILTY	2'9"	6'5"	
SAND BLACK FINE	6'5"	7'8"	12'
CLAY BLUE STICKY	7'8"	8'3"	
CLAY BLUE SANDY	8'3"	9'9"	
CONGLOMERATE	9'9"	10'4"	
GRAVEL + COARSE SAND	10'4"	11'3"	20'
CONGLOMERATE	11'3"	11'7"	20'
CLAY YELLOW SANDY	11'7"	12'0"	
CONGLOMERATE	12'0"	12'6"	
GRAVEL-COARSE BROWN	12'6"	13'2"	20'
CONGLOMERATE	13'2"	13'6"	
SAND FINE GRAVEL PACKED	13'6"	13'8"	
CONGLOMERATE W.B.	13'8"	14'5"	20'
CLAYSTONE GRAY FIRM	14'5"	15'3"	

PACKER PLACED 90' TO 108' TO STOP FEED DOWN OF FINE SAND. 6" HOLE USED AS A CONDUCTOR HOLE. 6" PIPE REMOVED AND 6" HOLE REFILLED TO CODE

Work started 2-9 1969 Completed 2-19 1969
 Date well drilling machine moved off of well 2-19- 1969

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision. Materials used and information reported above are true to my best knowledge and belief.

[Signed] B. F. Sneed Date 2-20- 1969
 (Drilling Machine Operator)

Drilling Machine Operator's License No. 187

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

NAME J. A. SNEED & SONS
 (Person, firm or corporation) (Type or print)

Address 3910 SILVERTON RD. N.E. SALEM ORE 97303

[Signed] B. F. Sneed
 (Water Well Contractor)

Contractor's License No. 6 Date 2-20- 1969