

NOTICE TO WATER WELL CONTRACTOR
The original and first copy of this report are to be filed with the

RECEIVED WATER WELL REPORT

MAR 29 1981
6-10845
State Well No. 65/W-2cc
State Permit No. _____

WATER RESOURCES DEPARTMENT, SALEM, OREGON 97310
within 30 days from the date of well completion.
STATE OF OREGON (Please type or print)
WATER RESOURCES DEPT SALEM, OREGON (Do not write above this line)

MAR 2 1981

(1) OWNER:

Name Alfred Berning
Address 13573 Marquam rd. N.E. Mt. Angel, Oregon 97136

(2) TYPE OF WORK (check):

New Well Deepening Reconditioning Abandon
If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary Driven
 Jetted
 Bored

(4) PROPOSED USE (check):

Domestic Industrial Municipal
Irrigation Test Well Other

(5) CASING INSTALLED:

Threaded Welded
10" Diam. from 1 ft. to 218 ft. Gage 1279
" Diam. from _____ ft. to _____ ft. Gage _____
" Diam. from _____ ft. to _____ ft. Gage _____

(6) PERFORATIONS:

Perforated? Yes No.

Type of perforator used _____
Size of perforations _____ in. by _____ in.
_____ perforations from _____ ft. to _____ ft.
_____ perforations from _____ ft. to _____ ft.
_____ perforations from _____ ft. to _____ ft.

(7) SCREENS:

Well screen installed? Yes No

Manufacturer's Name _____
Type _____ Model No. _____
Diam. _____ Slot size _____ Set from _____ ft. to _____ ft.
Diam. _____ Slot size _____ Set from _____ ft. to _____ ft.

(8) WELL TESTS:

Drawdown is amount water level is lowered below static level

Was a pump test made? Yes No If yes, by whom? driller
Yield: 660 gal./min. with 45 ft. drawdown after 6 1/2 hrs.
" " " " " "
" " " " " "
Boiler test _____ gal./min. with _____ ft. drawdown after _____ hrs.
Artesian flow _____ g.p.m.
Temperature of water _____ Depth artesian flow encountered _____ ft.

(9) CONSTRUCTION:

Well seal—Material used Portland Cement Grout
Well sealed from land surface to 18 ft.
Diameter of well bore to bottom of seal 14 in.
Diameter of well bore below seal 10 in.
Number of sacks of cement used in well seal 16 sacks
How was cement grout placed? pressure grouted

Was a drive shoe used? Yes No Plugs _____ Size: location _____ ft.
Did any strata contain unusable water? Yes No
Type of water? _____ Depth of strata _____
Method of sealing strata off _____
Was well gravel packed? Yes No Size of gravel: _____
Gravel placed from _____ ft. to _____ ft.

(10) LOCATION OF WELL:

County Marion Driller's well number 8
SW 1/4 SW 1/4 Section 2 T. 65 R. 14 W.M.
Bearing and distance from section or subdivision corner _____

(11) WATER LEVEL: Completed well.

Depth at which water was first found 135 ft.
Static level 70 ft. below land surface. Date 1/23/81
Artesian pressure _____ lbs. per square inch. Date _____

(12) WELL LOG:

Diameter of well below casing 8"
Depth drilled 315 ft. Depth of completed well 315 ft.

Formation: Describe color, texture, grain size and structure of materials; and show thickness and nature of each stratum and aquifer penetrated, with at least one entry for each change of formation. Report each change in position of Static Water Level and indicate principal water-bearing strata.

MATERIAL	From	To	SWL
Top Soil	0	1	
Clay Brown	1	28	
Gravel	28	31	
Clay Brown	31	48	
Clay gray	48	63	
Clay Brown	63	76	
Clay gray	76	135	
Sand, black, coarse	135	141	
Clay gray	141	168	
Clay Brown	168	212	
Clay red	212	218	
Basalt Black	218	249	
Basalt weathered	249	255	70
Basalt	255	295	
Basalt fractured	295	298	70
Basalt Hard	298	306	
Basalt fractured	306	312	70
Basalt Hard	312	315	

Work started 12/20 1981 Completed 1/30 1981
Date well drilling machine moved off of well 2/7 1981

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision. Materials used and information reported above are true to my best knowledge and belief.

[Signed] Ivan Grossen Date 2/7, 1981
(Drilling Machine Operator)

Drilling Machine Operator's License No. 1306

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

Name Grossen's Well Drilling
(Person, firm or corporation) (Type or print)

Address 555 Brown St. Woodburn

[Signed] Ivan Grossen
(Water Well Contractor)

Contractor's License No. 783 Date 2/7, 1981