

Marion 65/1w-4ad

Original hole for MARI 3021

J. A. SNEED & SONS

WELL DRILLING CONTRACTORS
2505 Brocks Street Phone 3-6809
SALEM, OREGON

Lo-Norbert Schmitz

Date Started JULY 24 - 1953

Date Finished JULY 31 - 1953

Customer MR. RAYMOND HASSING

Address

MOUNT ANGEL

SIZE	DEPTH	PER FT.	PIPE FT.	REMARKS	FUEL	TOTAL AMT.
8"	145'		129'			
				128' @ 8.00 - CHSED		
				5' @ 10.00 - ROCK		
				26' @ 5.50 - UNCHSED		
				26' @ 10.00 - ROCK		
PERFORATIONS BETWEEN @ 60-70'						
NO ADVISABLE TO PERFORATE ANY OTHER AREA						

WELL LOG

Original hole for MARI 3021

JOB NO. _____

20-Norbert

Date

JULY 31 - 1953

Operator

Snead Brothers

Schmitz

Maion 65/lw-4ad

Hours _____

FORMATION	FEET	DEPTH
SUBSOIL	20'	20'
BLUE CLAY	5'	25'
MUCKY SAND	17'	42'
CEMENTED GRAVEL	3'	45'
GRAVEL - WATER BEARING	2'	47'
BROWN SAND	10'	57'
CEMENTED GRAVEL WATER BEARING	13'	70'
WATER GRAVEL	1'	71'
RED CLAY	30'	101'
VOLCANIC ASH	27'	128'
CAP ROCK BASALT	5'	133'
VOLCANIC ASH	16'	149'
GRAY BASALT ROCK	26'	175'

Water Static

98'

Gallons per Minute

100

Draw Down

To 105'