

MAR 31 1965

6/1W-10c

NOTICE TO WATER WELL CONTRACTOR

The original and first copy of this report are to be filed with the

STATE ENGINEER, SALEM 10, OREGON within 30 days from the date of well completion.

RECEIVED MAY 29 1962 STATE ENGINEER SALEM, OREGON

WATER WELL REPORT

(Please type or print)

State Well No. G2380

State Permit No.

(1) OWNER: SALEM, OREGON Name: CITY OF MOUNT ANGEL Address: MOUNT ANGEL ORE

(11) WELL TESTS: Drawdown is amount water level is lowered below static level. Was a pump test made? Yes X No. Yield: 650 gal./min. with 208 ft. drawdown after 8 hrs.

(2) LOCATION OF WELL: County: Marion Driller's well number: Bearing and distance from section or subdivision corner

(12) WELL LOG: Diameter of well below casing 12. Depth drilled 631 ft. Depth of completed well 631 ft. Formation: Describe by color, character, size of material and structure, and show thickness of aquifers and the kind and nature of the material in each stratum penetrated, with at least one entry for each change of formation.

(3) TYPE OF WORK (check): Well X Deepening Reconditioning Abandonment

(4) PROPOSED USE (check): Domestic Industrial Municipal Irrigation Test Well Other. (5) TYPE OF WELL: Rotary Cable Dug Driven Jetted Bored

Table with 3 columns: MATERIAL, FROM, TO. Lists geological layers like BROWN CLAY, BLUE CLAY, BROWN CLAY AND GRAVEL, etc.

(6) CASING INSTALLED: Threaded Welded. 12" Diam. from 0 ft. to 296 ft. Gage 331. 10" Diam. from 290 ft. to 631 ft. Gage 279.

(7) PERFORATIONS: Perforated? Yes X No. Type of perforator used: TORCH. Size of perforations 3/8 in. by 4 in. 448 perforations from 601 ft. to 629 ft.

(8) SCREENS: Well screen installed? Yes No X. Manufacturer's Name, Model No., Diam., Slot size, Set from ft. to ft.

(9) CONSTRUCTION: Well seal—Material used in seal: CEMENT AND BENTONITE. Depth of seal: 50 ft. Diameter of well bore to bottom of seal: 16 in.

(13) PUMP: Manufacturer's Name, Type, H.P., Water Well Contractor's Certification.

(10) WATER LEVELS: Static level: 9 ft. below land surface Date: 5/1/62. Artesian pressure: lbs. per square inch Date.

NAME: RJ STRASSER DRILLING CO. Address: 8110 SE SUNSET LANE PORTLAND ORE. Drilling Machine Operator's License No. [Signed] Paulo Pylman. Contractor's License No. 101 Date: MAY 28, 1962