

NOTICE TO WATER WELL CONTRACTOR

The original and first copy of this report are to be filed with the

STATE ENGINEER, SALEM, OREGON 97310
within 30 days from the date of well completion.

RECEIVED

OCT 19 1966

WATER WELL REPORT

3/53
MAR 1967

State Well No. 6/1w-12 M

State Permit No.

(1) OWNER:

Name Mr. John Kloft
Address P.O. Box 551
Mt. Angel, Oregon

(2) LOCATION OF WELL:

County Marion Driller's well number
1/4 1/4 Section T. R. W.M.
Bearing and distance from section or subdivision corner
2600 ft. north & 450 ft. east of S.W.
corner of section 12, T.6 S., R.1 W.

(3) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐
Abandonment, describe material and procedure in Item 12.

(4) PROPOSED USE (check):

Domestic ☐ Industrial ☐ Municipal ☐ Rotary ☐ Driven ☐
Irrigation ☒ Test Well ☐ Other ☐ Cable ☒ Jetted ☐
Dug ☐ Bored ☐

(5) TYPE OF WELL:

(6) CASING INSTALLED:

8" Diam. from 1' above ft. to 179 ft. Gage .250
" Diam. from ft. to ft. Gage
" Diam. from ft. to ft. Gage

(7) PERFORATIONS:

Perforated? ☐ Yes ☒ No
Type of perforator used
Size of perforations in. by in.
perforations from ft. to ft.
perforations from ft. to ft.
perforations from ft. to ft.
perforations from ft. to ft.
perforations from ft. to ft.

(8) SCREENS:

Well screen installed? ☐ Yes ☒ No
Manufacturer's Name
Model No.
Diam. Slot size Set from ft. to ft.
Diam. Slot size Set from ft. to ft.

(9) CONSTRUCTION:

Well seal—Material used in seal Bentonite & puddled clay
Depth of seal 19 ft. Was a packer used? no
Diameter of well bore to bottom of seal 13 in.
Were any loose strata cemented off? ☐ Yes ☒ No Depth
Was a drive shoe used? ☒ Yes ☐ No
Was well gravel packed? ☐ Yes ☒ No Size of gravel:
Gravel placed from ft. to ft.
Did any strata contain unusable water? ☐ Yes ☒ No
Type of water? XX depth of strata
Method of sealing strata off

(10) WATER LEVELS:

Static level 92 ft. below land surface Date 5/28/66
Artesian pressure lbs. per square inch Date

(11) WELL TESTS:

Drawdown is amount water level is lowered below static level
Was a pump test made? ☒ Yes ☐ No If yes, by whom? Drillers
Yield: 400 gal./min. with 11 ft. drawdown after 7 hrs.
" " " "
" " " "
Bailer test XX gal./min. with ft. drawdown after hrs.
Artesian flow g.p.m. Date
Temperature of water XX Was a chemical analysis made? ☐ Yes ☒ No

(12) WELL LOG:

Diameter of well below casing 8
Depth drilled 260 ft. Depth of completed well 260 ft.
Formation: Describe by color, character, size of material and structure, and show thickness of aquifers and the kind and nature of the material in each stratum penetrated, with at least one entry for each change of formation.

MATERIAL	FROM	TO
Top soil- brown	0	1
Clay- brown	1	19
Clay with med. gravel- brown	19	57
Clay- grey & sandy	57	64
Med. conglom. grey- (Water bearing)	64	67
Clay with med. sand- grey	67	85
Clay with med. sand- rust red	85	107
Clay with med. sand- light grey	107	127
Clay grey & sandy	127	135
Clay- brown	135	145
Clay- brownish green	145	147
Clay- yellow	147	177
Rock- brown soft-	177	180
Basalt- grey- med. hd., (water)	180	184
Basalt- decayed- brown, soft-	184	187
Basalt- grey- hard	187	197
Claystone- grey- soft (water)	197	199
Basalt- black- med. hard-	199	203
Basalt- grey- hard-	203	215
Basalt- grey- med. hard-	215	218
Claystone- yellow- soft-	218	219
Basalt- grey- med. hard (water)	219	227
Basalt- black- med. hard-	227	243
Basalt- black- med. hd. porous (w. b)	243	260
Work started May 17, 1966 Completed May 28, 1966		
Date well drilling machine moved off of well June 7, 1966		

(13) PUMP:

Manufacturer's Name Jacuzzi
Type: Turbine H.P. 25

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

NAME R. Stadel & Sons
(Person, firm or corporation) (Type or print)
Address Rte. 3, Box 169, Silverton, Oregon

Drilling Machine Operator's License No. 322

[Signed] Paul R. Stadel
(Water Well Contractor)

Contractor's License No. 296 Date 10/17/66, 19

(USE ADDITIONAL SHEETS IF NECESSARY)