

**NOTICE TO WATER WELL CONTRACTOR**

The original and first copy of this report are to be filed with the

STATE ENGINEER, SALEM, OREGON 97310 within 30 days from the date of well completion.

**WATER WELL REPORT**

STATE OF OREGON

(Please type or print) (Do not write above this line)

STATE ENGINEER

SALEM, OREGON

3174  
MARION

State Well No. 6/1w-14 R

State Permit No.

**(1) OWNER:**

Name CLAUSSIE AMMON  
Address P.O. Box 52, JEFFERSON, ORE.

**(2) TYPE OF WORK (check):**

New Well  Deepening  Reconditioning  Abandon

If abandonment, describe material and procedure in Item 12.

**(3) TYPE OF WELL:**

Rotary  Cable  Dug   
Driven  Jetted  Bored

**(4) PROPOSED USE (check):**

Domestic  Industrial  Municipal   
Irrigation  Test Well  Other

**CASING INSTALLED:**

Threaded  Welded   
12" Diam. from 0 ft. to 26.6 ft. Gage 330  
" Diam. from " ft. to " ft. Gage  
" Diam. from " ft. to " ft. Gage

**PERFORATIONS:**

Perforated?  Yes  No.

Type of perforator used

Size of perforations in. by in.  
perforations from " ft. to " ft.  
perforations from " ft. to " ft.  
perforations from " ft. to " ft.  
perforations from " ft. to " ft.  
perforations from " ft. to " ft.

**(7) SCREENS:**

Well screen installed?  Yes  No

Manufacturer's Name  
Type Model No.  
Diam. Slot size Set from " ft. to " ft.  
Diam. Slot size Set from " ft. to " ft.

**(8) WATER LEVEL: Completed well.**

Static level 42 ft. below land surface Date 1/9/68  
Artesian pressure lbs. per square inch Date

**(9) WELL TESTS:**

Drawdown is amount water level is lowered below static level.

Was a pump test made?  Yes  No If yes, by whom? STRASSER  
Yield: 800 gal./min. with 120 ft. drawdown after 10 hrs.  
700 " " 99 " " 1 "  
500 " " 72 " " 1 "

Bailer test gal./min. with " ft. drawdown after " hrs.

Artesian flow g.p.m. Date

Temperature of water 55° Was a chemical analysis made?  Yes  No

**(10) CONSTRUCTION:**

Well seal—Material used CEMENT GROUT  
Depth of seal 30 FT. ft.  
Diameter of well bore to bottom of seal 16 in.  
Were any loose strata cemented off?  Yes  No Depth  
Was a drive shoe used?  Yes  No  
Did any strata contain unusable water?  Yes  No  
Type of water? depth of strata  
Method of sealing strata off  
Was well gravel packed?  Yes  No Size of gravel:  
Gravel placed from " ft. to " ft.

**(11) LOCATION OF WELL:**

County MARION Driller's well number 4766  
SE 1/4 SE 1/4 Section 14 T. 65 R. 1W W.M.  
Bearing and distance from section or subdivision corner

**(12) WELL LOG:**

Diameter of well below casing 12

Depth drilled 419 ft. Depth of completed well 419 ft.

Formation: Describe color, texture, grain size and structure of materials; and show thickness and nature of each stratum and aquifer penetrated, with at least one entry for each change of formation. Report each change in position of Static Water Level as drilling proceeds. Note drilling rates.

MATERIAL	From	To	SWL
BROWN SANDY CLAY	0	5	
CLAY GRAVEL AND BOULDERS	5	17	
CEMENTED GRAVEL	17	27	
BROWN CLAY	27	29	
CLAY AND GRAVEL	29	85	
RED AND YELLOW CLAY	85	180	
CLAY AND ROCK LAYERS	180	225	
WHITE CLAY	225	250	
RED ROCK	250	266	
BROKEN ROCK	266	281	
SOFT BLACK ROCK	281	318	
HARD BLACK ROCK	318	364	
BROWN SOFT ROCK	364	367	
SOFT BLACK ROCK	367	382	
BROKEN ROCK	382	407	
SOFT BLACK ROCK	407	414	
HARD BLACK BASALT	414	419	

Work started OCT 16 1967 Completed JAN 14 1968

Date well drilling machine moved off of well JAN 15 1968

**Drilling Machine Operator's Certification:**

This well was constructed under my direct supervision. Materials used and information reported above are true to my best knowledge and belief.

[Signed] Earn V Baker Date FEB 6 1968  
(Drilling Machine Operator)

Drilling Machine Operator's License No.

**Water Well Contractor's Certification:**

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

NAME R J STRASSER DRILLING CO  
(Person, firm or corporation) (Type or print)

Address 8110 SE SUNSET LANE PORTLAND, ORE

[Signed] Robert J. Strasser  
(Water Well Contractor)

Contractor's License No. 10 Date FEB 6 1968