

WATER RESOURCES DEPARTMENT,
SALEM, OREGON 97310
within 30 days from the date
of well completion.

WATER WELL REPORT

STATE OF OREGON

(Please type or print)

(Do not write above this line)

State Well No. 65/1w-17

State Permit No. _____

(1) OWNER:

Name Leonard Seifer

Address 10542 Saratoga Dr.

Salem, Oregon 97305

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐

If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Drilled ☒
Jetted ☐
Bored ☐

(4) PROPOSED USE (check):

Domestic ☒ Industrial ☐ Municipal ☐
Irrigation ☐ Test Well ☐ Other ☐

(5) CASING INSTALLED:

6" Diam. from +1 ft. to 160 ft. Gage 250
" Diam. from ft. to ft. Gage
" Diam. from ft. to ft. Gage

(6) PERFORATIONS:

Perforated? ☒ Yes ☐ No.

Type of perforator used Air Perforator

Size of perforations .156 in. by .625 in.
100 perforations from 120 ft. to 126 ft.
400 perforations from 140 ft. to 160 ft.
perforations from ft. to ft.

(7) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name _____

Type _____ Model No. _____

Diam. _____ Slot size _____ Set from _____ ft. to _____ ft.

Diam. _____ Slot size _____ Set from _____ ft. to _____ ft.

(8) WELL TESTS:

Drawdown is amount water level is
lowered below static level

a pump test made? ☐ Yes ☒ No If yes, by whom?

Yield: gal./min. with ft. drawdown after hrs.

" " " "

" Air Test May Fluctuate " "

Test 180 gal./min. with 122 ft. drawdown after 1 hrs.

Artesian flow g.p.m.

Temperature of water Depth artesian flow encountered ft.

(9) CONSTRUCTION:

Well seal—Material used Cement

Well sealed from land surface to 20 ft.

Diameter of well bore to bottom of seal 10 in.

Diameter of well bore below seal 6 in.

Number of sacks of cement used in well seal 10 sacks

How was cement grout placed? Air Grout Pump

Was a drive shoe used? ☒ Yes ☐ No Plug Size: location ft.

Did any strata contain unusable water? ☐ Yes ☒ No

Type of water? depth of strata

Method of sealing strata off

Was well gravel packed? ☐ Yes ☒ No Size of gravel:

Gravel placed from ft. to ft.

(10) LOCATION OF WELL:

County Marion

Driller's well number

1/4 1/4 Section 17 T. 6S R. 1W W.M.

Bearing and distance from section or subdivision corner

(11) WATER LEVEL: Completed well.

Depth at which water was first found 96 ft.

Static level 38 ft. below land surface. Date 5-15-80

Artesian pressure lbs. per square inch. Date

(12) WELL LOG:

Diameter of well below casing

Depth drilled 160 ft. Depth of completed well 160 ft.

Formation: Describe color, texture, grain size and structure of materials;
and show thickness and nature of each stratum and aquifer penetrated,
with at least one entry for each change of formation. Report each change in
position of Static Water Level and indicate principal water-bearing strata.

MATERIAL	From	To	SWL
Brown Clay	0	6	
Tan Clay	6	15	
Dark Brown Clay Sandy	15	35	
Gray Clay Sandy	35	42	
Brown Clay Sandy	42	60	
Gray Clay Sticky	60	86	
Gray Clay Sandy	86	96	
Large Gravel	96	107	
Gray Clay Sandy	107	112	
Medium Gravel	112	130	
Gray Clay	130	136	
Medium Gravel/Black Sand	136	160	38Ft.

RECEIVED

JUN 25 1980

WATER RESOURCES DEPT
SALEM, OREGON

Work started 5-14 1980 Completed 5-16 1980

Date well drilling machine moved off of well 5-15 1980

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision.
Materials used and information reported above are true to my
best knowledge and belief.

[Signed] J.D. Manders Date 5-16, 1980
(Drilling Machine Operator)

Drilling Machine Operator's License No. 1195

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is
true to the best of my knowledge and belief.

Name Miller, West Well Drilling
(Person, firm or corporation) (Type or print)

Address 5875 Gaffin Rd. Salem, Oregon 97301

[Signed] Say Moran
(Water Well Contractor)

Contractor's License No. 722 Date 5-16 1980