

NOTICE TO WATER WELL CONTRACTOR
The original and first copy
of this report are to be
filed with the

3490
MARI

WATER WELL REPORT
MAR 14 1974

RECEIVED

FEB 19 1974

STATE ENGINEER, SALEM, OREGON 97331
within 30 days from the date
of well completion.

STATE OF OREGON
(Please type or print)
(Do not write above this line)

STATE ENGINEER
SALEM, OREGON

State Well No. 65/1W-29

State Permit No.

(1) OWNER:

Name Mr. James H. Beyer
Address Route 2, Box 152
Sylverton, Oregon 97381

(2) TYPE OF WORK (check):

New Well Deepening Reconditioning Abandon
If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary Driven
Cable Jetted
Dug Bored

(4) PROPOSED USE (check):

Domestic Industrial Municipal
Irrigation Test Well Other

CASING INSTALLED:

Threaded Welded

8" Diam. from 1 ft. to 228 ft. above surface
1 1/4" Gage

PERFORATIONS:

Perforated Yes No

Type of perforator used Mills Knife perforator
Size of perforations 1/2 in. by 2 in.
190 perforations from 40 ft. to 142 ft.

(7) SCREENS:

Well screen installed? Yes No

Manufacturer's Name
Type Model No.
Diam. Slot size Set from ft. to ft.
Diam. Slot size Set from ft. to ft.

(8) WELL TESTS:

Drawdown is amount water level is lowered below static level

Was a pump test made? Yes No If yes, by whom?
Yield: gal./min. with ft. drawdown after hrs.
Bailer test 40 gal./min. with 25 ft. drawdown after 1 hrs.
Artesian flow g.p.m.
Temperature of water 52° Depth artesian flow encountered ft.

(9) CONSTRUCTION:

Well seal—Material used Concrete
Well sealed from land surface to 20 ft.
Diameter of well bore to bottom of seal 12 in.
Diameter of well bore below seal 12 in.
Number of sacks of cement used in well seal 2 sacks
Number of sacks of bentonite used in well seal -0- sacks
Brand name of bentonite
Number of pounds of bentonite per 100 gallons of water -0- lbs./100 gals.
Was a drive shoe used? Yes No Plugs Size: location ft.
Did any strata contain unusable water? Yes No
Type of water? depth of strata
Method of sealing strata off
Was well gravel packed? Yes No Size of gravel: #2
Gravel placed from 20 ft. to 228 ft.

(10) LOCATION OF WELL:

County Marion Driller's well number
1/4 Section 29 T. 6S R. 1 W W.M.
Bearing and distance from section or subdivision corner

(11) WATER LEVEL: Completed well.

Depth at which water was first found 33 ft.
Static level 16 ft. below land surface. Date 12-3-73
Artesian pressure lbs. per square inch. Date

(12) WELL LOG:

Diameter of well below casing 8"

Depth drilled 300 ft. Depth of completed well 300 ft.

Formation: Describe color, texture, grain size and structure of materials; and show thickness and nature of each stratum and aquifer penetrated, with at least one entry for each change of formation. Report each change in position of Static Water Level and indicate principal water-bearing strata.

MATERIAL	From	To	SWL
Top Soil	0	2'	
Blue Clay	2'	33'	
Blue Clay and Gravel (Water bearing)	33'	104'	
Red Clay	104'	174'	
Blue Clay	174'	245'	
Brown Clay	245'	270'	
Blue Clay	270'	300'	

Work started Dec. 3, 1973 Completed Feb. 1, 1974
Date well drilling machine moved off of well Feb. 1, 1974

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision. Materials used and information reported above are true to my best knowledge and belief.

[Signed] Art Clinton Date Feb. 14 1974
(Drilling Machine Operator)

Drilling Machine Operator's License No. 34

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

Name ART CLINTON WELL DRILLING Co.
(Person, firm or corporation) (Type or print)
Address Rt. 1, Box 2, Independence, Oregon 97351

[Signed] Art Clinton
(Water Well Contractor)

Contractor's License No. 14 Date February 18, 1974

(USE ADDITIONAL SHEETS IF NECESSARY)

MARI 3490

For Official Use Only:

Received Date:

10-7-97

County Well Log ID No.

MARI 3490

Well Identification Tag No.

19552

WELL IDENTIFICATION APPLICATION FORM

BUYER/CURRENT WELL OWNER:

Name: J Beyer

Mailing Address: 11263 Dahl Rd NE

City: Silverton State: OR Zip: 97138 Phone: 873-4505

WELL LOCATION:

County: Marion Owner's Well Number: B

Township: 6 N or (S) Range: 1 E or (W) Section: 29 NE 1/4 NE 1/4

Tax Lot #: 145982000 Type of Well: water supply monitoring

Street Address of Well (if different from above): N/A

WELL INFORMATION: (do not complete remainder of application if well log is available)

Start Card Number: _____ Approx. Construction Date: _____

Well Constructor: _____

Name of Owner at Time of Construction: _____

Well Depth (in feet): _____ Static Water Level (in feet): _____

Diameter of Exposed Well Casing (in inches): _____

Does this well have a formal water right associated with it? Yes: No:

If Yes: Application #: _____ Permit #: _____ Certificate #: _____

Please Return Completed Form to:

Lisa Juul
Well Identification Program
Oregon Water Resources Department
158 12th Street NE
Salem, OR 97310