

STATE OF OREGON
WATER WELL REPORT
(as required by ORS 537.785)

MARI 036 85/3w/30bd
(START CARD) # 12992

(1) OWNER: Well Number:
Name HARRY VANDERPOOL
Address 3-17 BROWNING
City SALEM State ORE Zip

(2) TYPE OF WORK:
☒ New Well ☐ Deepen ☐ Recondition ☐ Abandon

(3) DRILL METHOD
☒ Rotary Air ☐ Rotary Mud ☐ Cable
☐ Other

(4) PROPOSED USE:
☒ Domestic ☐ Community ☐ Industrial ☐ Irrigation
☐ Thermal ☐ Injection ☐ Other

(5) BORE HOLE CONSTRUCTION:
Special Construction approval Yes ☐ No ☒ Depth of Completed Well 271 ft.
Explosives used ☐ Yes ☒ No ☐ Type Amount

HOLE			SEAL			Amount sacks or pounds
Diameter	From	To	Material	From	To	
10"	0'	60'	CEMENT	0'	60'	19 SACKS
6"	60'	271'				

How was seal placed: Method ☐ A ☐ B ☒ C ☐ D ☐ E
☐ Other
Backfill placed from ft. to ft. Material
Gravel placed from ft. to ft. Size of gravel

(6) CASING/LINER:

Diameter	From	To	Gauge	Steel	Plastic	Welded	Threaded
Casing: 6"	+1'	60'	250	☒	☐	☒	☐
				☐	☐	☐	☐
				☐	☐	☐	☐
				☐	☐	☐	☐
Liner:				☐	☐	☐	☐
				☐	☐	☐	☐

Final location of shoe(s)

(7) PERFORATIONS/SCREENS: N/A
☐ Perforations Method
☐ Screens Type Material

From	To	Slot size	Number	Diameter	Tele/pipe size	Casing	Liner
						☐	☐
						☐	☐
						☐	☐
						☐	☐
						☐	☐

(8) WELL TESTS: Minimum testing time is 1 hour
☐ Pump ☐ Bailer ☒ Air ☐ Flowing
Yield gal/min 17.5 Drawdown 101' Drill stem at 271' Time 4 hr.
Temperature of water 51° Depth Artesian Flow Found
Was a water analysis done? ☒ NO ☐ Yes By whom
Did any strata contain water not suitable for intended use? ☐ Too little
☐ Salty ☐ Muddy ☐ Odor ☐ Colored ☐ Other NO
Depth of strata:

(9) LOCATION OF WELL by legal description:
County MARIQU Latitude Longitude
Township 8S N or S, Range 3W E or W, WM.
Section 30 SE 1/4 NW 1/4
Tax Lot 2200 Lot Block Subdivision
Street Address of Well (or nearest address) 7128 SKYLINE RD
SALEM, ORE. 97306

(10) STATIC WATER LEVEL:
120' ft. below land surface. Date 5-16-90
Artesian pressure lb. per square inch. Date

(11) WATER BEARING ZONES:

Depth at which water was first found 100'

From	To	Estimated Flow Rate	SWL
100'	102'	9.5	94'
249'	267'	8	170'
		TOTAL 17.5 gpm	

(12) WELL LOG: Ground elevation

Material	From	To	SWL
TOP SOIL	0'	2'	
BASALT WEATH	2'	22'	
" BROKEN	22'	54'	
" DENSE	54'	94'	
" SEAMY	94'	100'	
" WEATH (WHITE)	100'	121'	94'
" DENSE	121'	236'	
" SEAMY	236'	239'	
" WEATH	239'	249'	
" SEAMY	249'	267'	170'
" DENSE	267'	271'	

RECEIVED

MAY 17 1990

WATER RESOURCES DEPT
SALEM, OREGON

Date started 5-10-90 Completed 5-16-90

(unbonded) Water Well Constructor Certification:
I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon well construction standards. Materials used and information reported above are true to my best knowledge and belief.
Signed WWC Number
Date

(bonded) Water Well Constructor Certification:
I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon well construction standards. This report is true to the best of my knowledge and belief.
Signed James L. Sneed WWC Number 1274
Date 5-16-90