

NOTICE TO WATER WELL CONTRACTOR

The original and first copy
of this report are to be
filed with the

OCT 19 1966

STATE ENGINEER, SALEM, OREGON 97310

WATER WELL REPORT
STATE OF OREGON
within 30 days from the date
of well completion.

SALEM OREGON

(Please type or print)

G-4123

State Well No. 6/1w-35 H

State Permit No.

(1) OWNER:

Name Leonard Duncan
Address Rte. 1, Box 169
Silverton, Oregon

(2) LOCATION OF WELL:

County Marion Driller's well number
1/4 1/4 Section T. R. W.M.
Bearing and distance from section or subdivision corner
2275 ft. south & 50 ft. west of N.E.
corner of section 35, T6 S., R. 1 W.

(3) TYPE OF WORK (check):

New Well ☐ Deepening ☒ Reconditioning ☐ Abandon ☐
Abandonment, describe material and procedure in Item 12.

(4) PROPOSED USE (check):

Domestic ☒ Industrial ☐ Municipal ☐ Rotary ☒ Driven ☐
Irrigation ☐ Test Well ☐ Other ☐ Cable ☐ Jetted ☐
Dug ☐ Bored ☐

(6) CASING INSTALLED:

Threaded ☐ Welded ☒
Diam. from 6" above surface ft. to 15'-8" ft. Gage 250
original casing - 15'-8" ft. Gage 250

(7) PERFORATIONS:

Perforated? ☐ Yes ☒ No

Type of perforator used

Size of perforations in. by in.
perforations from ft. to ft.
perforations from ft. to ft.
perforations from ft. to ft.
perforations from ft. to ft.
perforations from ft. to ft.

(8) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name Model No.
Diam. Slot size Set from ft. to ft.
Diam. Slot size Set from ft. to ft.

(9) CONSTRUCTION:

Well seal—Material used in seal Cement
Depth of seal 15'-8" ft. Was a packer used? no
Diameter of well bore to bottom of seal 10 in.
Were any loose strata cemented off? ☐ Yes ☒ No Depth
Was a drive shoe used? ☐ Yes ☒ No
Was well gravel packed? ☐ Yes ☒ No Size of gravel:
Gravel placed from ft. to ft.
Did any strata contain unusable water? ☐ Yes ☒ No
Type of water? depth of strata
Method of sealing strata off

(10) WATER LEVELS:

Static level 225 ft. below land surface Date 8-19-66
Artesian pressure lbs. per square inch Date

(11) WELL TESTS:

Drawdown is amount water level is lowered below static level

Was a pump test made? ☐ Yes ☒ No If yes, by whom?Yield: 15 gal./min. with 45 ft. drawdown after 1 hrs." air " " " "Ballor test 15 gal./min. with 25 ft. drawdown after 1 hrs.

Artesian flow g.p.m. Date

Temperature of water Was a chemical analysis made? ☐ Yes ☒ No

(12) WELL LOG:

Diameter of well below casing 6Depth drilled 110 ft. Depth of completed well 270 ft.

Formation: Describe by color, character, size of material and structure, and show thickness of aquifers and the kind and nature of the material in each stratum penetrated, with at least one entry for each change of formation.

MATERIAL	FROM	TO
<u>Original depth</u>	<u>160</u>	
<u>Basalt grey hard</u>	<u>160</u>	<u>225</u>
<u>Basalt, seamy, grey hard</u>	<u>225</u>	<u>265</u>
<u>Claystone dark grey, mud</u>	<u>265</u>	<u>270</u>
<u>Water coming into well between 250-265</u>		

Work started 8-12 19 66 Completed 8-19 19 66
Date well drilling machine moved off of well 8-19 19 66

(13) PUMP:

Manufacturer's Name Jacuzzi
Type: Submersible H.P. 1 1/2

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

NAME R. Stadel & Sons
(Person, firm or corporation) (Type or print)

Address Route 3, Box 169, Silverton

Drilling Machine Operator's License No. 84

[Signed] Paul R. Stadel
(Water Well Contractor)

Contractor's License No. 296 Date 10-12, 19 66

(USE ADDITIONAL SHEETS IF NECESSARY)