

STATE OF OREGON
WATER WELL REPORT
(as required by ORS 537.765)

MARI 037 85/3w/2006
(START CARD) # 17991

(1) OWNER: Well Number: _____
Name GERALD MARTIN
Address 6254 SKYLINE RD. S.
City SALEM State ORE Zip 97306

(2) TYPE OF WORK:
☒ New Well ☐ Deepen ☐ Recondition ☐ Abandon

(3) DRILL METHOD
☒ Rotary Air ☐ Rotary Mud ☐ Cable
☐ Other _____

(4) PROPOSED USE:
☒ Domestic ☐ Community ☐ Industrial ☐ Irrigation
☐ Thermal ☐ Injection ☐ Other _____

(5) BORE HOLE CONSTRUCTION:
Special Construction approval Yes ☐ No ☒ Depth of Completed Well 200 ft.
Explosives used ☐ Yes ☒ No ☐ Type _____ Amount _____

HOLE			SEAL			Amount sacks or pounds
Diameter	From	To	Material	From	To	
10"	0'	58'	CEMENT	0'	58'	18 SACKS
6"	58'	200'				

How was seal placed: Method ☐ A ☐ B ☒ C ☐ D ☐ E
☐ Other _____
Backfill placed from _____ ft. to _____ ft. Material _____
Gravel placed from _____ ft. to _____ ft. Size of gravel _____

(6) CASING/LINER:

	Diameter	From	To	Gauge	Steel	Plastic	Welded	Threaded
Casing:	6"	0'	58'	250	☒	☐	☒	☐
					☐	☐	☐	☐
					☐	☐	☐	☐
					☐	☐	☐	☐
Liner:					☐	☐	☐	☐
					☐	☐	☐	☐

Final location of shoe(s) _____

(7) PERFORATIONS/SCREENS: NO
☐ Perforations Method _____
☐ Screens Type _____ Material _____

From	To	Slot size	Number	Diameter	Tele/pipe size	Casing	Liner
						☐	☐
						☐	☐
						☐	☐
						☐	☐
						☐	☐
						☐	☐

(8) WELL TESTS: Minimum testing time is 1 hour
☐ Pump ☐ Bailer ☒ Air ☐ Flowing Artesian
Yield gal/min 16.5 Drawdown 156' Drill stem at 200' Time 4 hr.

Temperature of water 51° Depth Artesian Flow Found _____
Was a water analysis done? ☒ No ☐ Yes By whom _____
Did any strata contain water not suitable for intended use? ☐ Too little NO
☐ Salty ☐ Muddy ☐ Odor ☐ Colored ☐ Other _____
Depth of strata: _____

(9) LOCATION OF WELL by legal description:
County MARION Latitude _____ Longitude _____
Township 8S N or S, Range 3W E or W, WM.
Section 20 NW 1/4 NW 1/4
Tax Lot 2090-128 Lot _____ Block _____ Subdivision _____
Street Address of Well (or nearest address) 6252 SKYLINE RD. S.
SALEM, ORE. 97306

(10) STATIC WATER LEVEL:
44 ft. below land surface. Date 5-9-90
Artesian pressure _____ lb. per square inch. Date _____

(11) WATER BEARING ZONES:

Depth at which water was first found 128-151

From	To	Estimated Flow Rate	SWL
128'	151'	10 gpm	44'
186'	188'	6.5 gpm	44'
		TOTAL	16.5 gpm

(12) WELL LOG: Ground elevation _____

Material	From	To	SWL
TOP SOIL	0	2	
BASALT WEATH.	2	35	
BASALT SEAMY	35	51	
BASALT DENSE	51	119	
BASALT SEAMY	119	124	
BASALT WEATH.	124	134	44'
BASALT SEAMY	134	151	
BASALT DENSE	151	186	
BASALT SEAMY	186	188	44'
BASALT DENSE	188	200	

RECEIVED

MAY 17 1990

WATER RESOURCES DEPT
SALEM, OREGON

Date started 5-3-90 Completed 5-9-90

(unbonded) Water Well Constructor Certification:
I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon well construction standards. Materials used and information reported above are true to my best knowledge and belief.
Signed _____ Date _____ WWC Number _____

(bonded) Water Well Constructor Certification:
I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. all work performed during this time is in compliance with Oregon well construction standards. This report is true to the best of my knowledge and belief.
Signed James L. Sweet WWC Number 1274
Date 5-10-90