

STATE OF OREGON
WATER WELL REPORT
(as required by ORS 537.765)

MAY 17 1990

MARI 038 85/1W 5 ab
SC # 17173 (917173)

(1) OWNER:

Name Oak Lane Farms, Inc.
Address 8167 Oak Lane ~~Ruckus~~ NE
City Mt. Angel State OR Zip 97362

(2) TYPE OF WORK:

☒ New Well ☐ Deepen ☐ Recondition ☐ Abandon

(3) DRILL METHOD

☒ Rotary Air ☐ Rotary Mud ☐ Cable
☐ Other

(4) PROPOSED USE:

☐ Domestic ☐ Community ☐ Industrial ☒ Irrigation
☐ Thermal ☐ Injection ☐ Other

(5) BORE HOLE CONSTRUCTION:

Special Construction approval Yes No Depth of Completed Well 575 ft.
Yes No ☐ ☒
Explosives used ☐ ☒ Type Amount

HOLE			SEAL			Amount
Diameter	From	To	Material	From	To	sacks or pounds
17	0	40	cement	0	40	37 sacks
13	40	48				
12	48	480				
8	480	575				

How was seal placed: Method ☐ A ☐ B ☒ C ☐ D ☐ E

☐ Other

Backfill placed from ft. to ft. Material

Gravel placed from ft. to ft. Size of gravel

(6) CASING/LINER:

	Diameter	From	To	Gauge	Steel	Plastic	Welded	Threaded
Casing:	12"	+1	48	.250	☒	☐	☒	☐
					☐	☐	☐	☐
					☐	☐	☐	☐
					☐	☐	☐	☐
Liner:					☐	☐	☐	☐
					☐	☐	☐	☐

Final location of shoe(s)

(7) PERFORATIONS/SCREENS:

☐ Perforations Method
☐ Screens Type Material

From	To	Slot size	Number	Diameter	Tele/pipe size	Casing	Liner
						☐	☐
						☐	☐
						☐	☐
						☐	☐
						☐	☐
						☐	☐
						☐	☐

(8) WELL TESTS: Minimum testing time is 1 hour

☐ Pump ☐ Bailer ☒ Air ☐ Flowing
☐ Artesian

Yield gal/min	Drawdown	Drill stem at	Time
300-400		575	1 hr.

Temperature of water Depth Artesian Flow Found

Was a water analysis done? ☐ Yes By whom

Did any strata contain water not suitable for intended use? ☐ Too little

☐ Salty ☐ Muddy ☐ Odor ☐ Colored ☐ Other

(9) LOCATION OF WELL by legal description:

County Marion Latitude Longitude
Township 8 N or S, Range 1W E or W, WM.
Section 5 NW 1/4 NE 1/4
Tax Lot 00100 Lot Block Subdivision
Street Address of Well (or nearest address) 11555 Waldo Hills SE
Salem, OR 97301

(10) STATIC WATER LEVEL:

265 ft. below land surface. Date 5-9-90
Artesian pressure lb. per square inch. Date

(11) WATER BEARING ZONES:

Depth at which water was first found 282			
From	To	Estimated Flow Rate	SWL
282	300	15 gpm	265
455	480	300 gpm	265

(12) WELL LOG:

Ground elevation

Material	From	To	SWL
Topsoil	0	2	
Soil and broken rock	2	4	
Basaltic rubble	4	12	
Basalt frac	12	23	
Decomposed rock	23	32	
Basalt grey frac & hard	32	95	
Basalt grey pourous hard	95	105	
Claystone brwon hard	105	108	
Claystone green	108	119	
Basalt grey med hard	119	189	
Basalt black pourous	189	194	
Basalt grey hard	194	205	
Basalt grey weathered	205	209	
Basalt grey hard	209	234	
Basalt grey pourous	234	246	
Basalt grey hard	246	282	
Basalt frac & broken	282	300	265
Basalt grey hard	300	455	
Basalt frac	455	465	265
Basalt broken & visic	465	480	265
Basalt grey Hard w/ visic	480	490	
Basalt grey hard	490	570	
Clay brown	570	575	

Date started 4-30-90 Completed 5-9-90

(unbonded) Water Well Constructor Certification:

I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon well construction standards. Materials used and information reported above are true to my best knowledge and belief.

Signed Devin B. Hudec WWC Number 1358
Date 5-16-90

(bonded) Water Well Constructor Certification:

I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. all work performed during this time is in compliance with Oregon well construction standards. This report is true to the best of my knowledge and belief.

WWC Number 723