

NOTICE TO WATER WELL CONTRACTOR:
The original and first copy of this report are to be filed with the STATE ENGINEER, SALEM, OREGON within 30 days from the date of well completion.

RECEIVED
JUN 4 1968
3875
WATER WELL REPORT

STATE ENGINEER STATE OF OREGON
SALEM, OREGON (Please type or print)
(Do not write above this line)

State Well No. 6/2W-8P
State Permit No. _____

(1) OWNER:

Name Mainline Foods Inc. *not in use*
Address P.O. Box 2165
Salem, Ore. Well # 2

(2) TYPE OF WORK (check):

New Well Deepening Reconditioning Abandon

If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary Driven
Cable Jetted
Dug Bored

(4) PROPOSED USE (check):

Domestic Industrial Municipal
Irrigation Test Well Other

(5) CASING INSTALLED:

Threaded Welded
123/4" Diam. from 1340 ft. to 142 ft. Gage .250
" Diam. from _____ ft. to _____ ft. Gage _____
" Diam. from _____ ft. to _____ ft. Gage _____

(6) PERFORATIONS:

Perforated Yes No.

Type of perforator used Mills
Size of perforations 3/8 in. by 2 in.
972 perforations from 100 ft. to 140 ft.
_____ perforations from _____ ft. to _____ ft.
_____ perforations from _____ ft. to _____ ft.
_____ perforations from _____ ft. to _____ ft.
_____ perforations from _____ ft. to _____ ft.

(7) SCREENS:

Well screen installed? Yes No

Manufacturer's Name _____ Model No. _____
Type _____
Diam. _____ Slot size _____ Set from _____ ft. to _____ ft.
Diam. _____ Slot size _____ Set from _____ ft. to _____ ft.

(8) WATER LEVEL: Completed well.

Static level 15 ft. below land surface Date May 3
Artesian pressure _____ lbs. per square inch Date _____

(9) WELL TESTS:

Drawdown is amount water level is lowered below static level

Was a pump test made? Yes No If yes, by whom? Stettler
800 gal./min. with 55 ft. drawdown after 8 hrs.
" " " " " "
" " " " " "
Bailer test _____ gal./min. with _____ ft. drawdown after _____ hrs.
Artesian flow _____ g.p.m. Date _____
Temperature of water _____ Was a chemical analysis made? Yes No

(10) CONSTRUCTION:

Well seal—Material used Clay
Depth of seal 24 ft.
Diameter of well bore to bottom of seal 16 in.
Were any loose strata cemented off? Yes No Depth _____
Was a drive shoe used? Yes No
Did any strata contain unusable water? Yes No
Type of water? _____ depth of strata _____
Method of sealing strata off _____
Was well gravel packed? Yes No Size of gravel: 1/2" #20
Gravel placed from 50 ft. to 170 ft.

(11) LOCATION OF WELL:

County Marion Driller's well number 6/2W8P2
1/4 1/4 Section T. R. W.M.
Bearing and distance from section or subdivision corner _____

(12) WELL LOG:

Diameter of well below casing 12

Depth drilled 144 ft. Depth of completed well 142 ft.

Formation: Describe color, texture, grain size and structure of materials; and show thickness and nature of each stratum and aquifer penetrated, with at least one entry for each change of formation. Report each change in position of Static Water Level as drilling proceeds. Note drilling rates.

MATERIAL	From	To	SWL
Top soil	0	2	
Yellow clay	2	8	
Yellow silty clay	8	35	
Blue silty clay	35	60	
Muddy blk sand	60	70	
Clean blk sand	70	90	
Clean blk sand & gravel	90	105	
Clean gravel with sand	105	110	
Brwn gravel & sand	110	137	
Coarse gravel with clay	137	141	
Silty clay & wood	141	143	
Fine grey sand	143	144	

Drilled 6" conductor pipe down to 98' and attempted to place gravel pack, hole would not take gravel. Cemented bottom of hole. 6 sacks of cement used
WELL

Work started April 5 1968 Completed May 2 1968

Date well drilling machine moved off of well May 3 1968

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision. Materials used and information reported above are true to my best knowledge and belief.

[Signed] Harry A. Robinson Date June 1, 1968
(Drilling Machine Operator)

Drilling Machine Operator's License No. 63

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

NAME Harry A. Robinson
(Person, firm or corporation) (Type or print)

Address 2214 Front St. NE Salem, Ore.

[Signed] Harry A. Robinson
(Water Well Contractor)

Contractor's License No. 22 Date June 1, 1968