

NOTICE TO WATER WELL CONTRACTOR  
The original and first copy of this report are to be filed with the

**RECEIVED** MAR 24 1968  
WATER WELL REPORT  
STATE OF OREGON  
STATE ENGINEER  
SALEM, OREGON  
376 well #3  
G-4705

STATE ENGINEER, SALEM, OREGON (Please type or print)  
within 30 days from the date of well completion. (Do not write above this line)

State Well No. 6/2w-8P  
State Permit No. \_\_\_\_\_

(1) OWNER: Well # 4  
Name Mainline Foods Inc.  
Address P.O. Box 2165  
Salem, Ore.

(2) TYPE OF WORK (check):  
New Well  Deepening  Reconditioning  Abandon   
If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL: (4) PROPOSED USE (check):  
Rotary  Driven  Domestic  Industrial  Municipal   
Cable  Jetted  Irrigation  Test Well  Other   
Dug  Bored

(5) CASING INSTALLED: Threaded  Welded   
12 3/4" Diam. from 140 ft. to 99 ft. Gage .250  
" Diam. from \_\_\_\_\_ ft. to \_\_\_\_\_ ft. Gage \_\_\_\_\_  
" Diam. from \_\_\_\_\_ ft. to \_\_\_\_\_ ft. Gage \_\_\_\_\_

PERFORATIONS: Perforated?  Yes  No.  
Johnson Stainless Steel  
Size of perforations in. by in.  
50 slot size perforations from 122 ft. to 127 ft.  
103/4" pipe perforations from 127 ft. to 131 1/2 ft.  
20 slot perforations from 131 1/2 ft. to 132 1/2 ft.  
40 " perforations from 132 1/2 ft. to 133 1/2 ft.  
80 " perforations from 133 1/2 ft. to 137 ft.

(7) SCREENS: Well screen installed?  Yes  No  
Manufacturer's Name Johnson  
Type 10" std pipe size Model No. Stainless  
Diam. 103/4" Slot size 80 Set from 97 ft. to 107 ft.  
Diam. " Slot size 150 Set from 107 ft. to 122 ft.

(8) WATER LEVEL: Completed well.  
Static level 16 1/2 ft. below land surface Date \_\_\_\_\_  
Artesian pressure \_\_\_\_\_ lbs. per square inch Date \_\_\_\_\_

(9) WELL TESTS: Drawdown is amount water level is lowered below static level  
Was a pump test made?  Yes  No If yes, by whom? Stettler  
Flow: \_\_\_\_\_ gal./min. with \_\_\_\_\_ ft. drawdown after \_\_\_\_\_ hrs.

\* Consult with Stettler Supply, Salem  
Bailer test \_\_\_\_\_ gal./min. with \_\_\_\_\_ ft. drawdown after \_\_\_\_\_ hrs.  
Artesian flow \_\_\_\_\_ g.p.m. Date \_\_\_\_\_  
Temperature of water \_\_\_\_\_ Was a chemical analysis made?  Yes  No

(10) CONSTRUCTION:  
Well seal—Material used Puddled clay  
Depth of seal 22 ft.  
Diameter of well bore to bottom of seal 16 in.  
Were any loose strata cemented off?  Yes  No Depth \_\_\_\_\_  
Was a drive shoe used?  Yes  No  
Did any strata contain unusable water?  Yes  No  
Type of water? \_\_\_\_\_ depth of strata \_\_\_\_\_  
Method of sealing strata off \_\_\_\_\_  
Was well gravel packed?  Yes  No Size of gravel: \_\_\_\_\_  
Gravel placed from \_\_\_\_\_ ft. to \_\_\_\_\_ ft.

(11) LOCATION OF WELL:  
County Marion Driller's well number 6/2W8P4  
1/4 1/4 Section T. R. W.M.  
Bearing and distance from section or subdivision corner \_\_\_\_\_

(12) WELL LOG: Diameter of well below casing 10  
Depth drilled 137 ft. Depth of completed well 137 ft.  
Formation: Describe color, texture, grain size and structure of materials; and show thickness and nature of each stratum and aquifer penetrated, with at least one entry for each change of formation. Report each change in position of Static Water Level as drilling proceeds. Note drilling rates.

MATERIAL	From	To	SWL
Top soil	0	2	
Yellow clay	2	8	
Yellow silty clay	8	35	
Blue silty clay	35	60	
Muddy blk sand	60	70	
Clean blk sand	70	89	
Blk sand & gravel	89	97	
Brwn sand & gravel	97	98	
Heavy grvl clay binder	98	100	
Clean gravel	100	101	
Green sand & gravel	101	102	
Coarse gravel little sand	102	112	
Small gravel	112	128	
Brown sand	128	130	
Loose brwn sand & grvl	130	133	
Coarse gravel	133	137	

Work started 5/20 1968 Completed 6/1/68 19\_\_\_\_  
Date well drilling machine moved off of well 6/3/68 19\_\_\_\_

Drilling Machine Operator's Certification:  
This well was constructed under my direct supervision. Materials used and information reported above are true to my best knowledge and belief.  
[Signed] Harry A. Robinson Date 6/21, 1968  
(Drilling Machine Operator)  
Drilling Machine Operator's License No. 63

Water Well Contractor's Certification:  
This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.  
NAME Harry A. Robinson (Type or print)  
(Person, firm or corporation)  
Address 2214 Front NE Salem, Ore.  
[Signed] Harry A. Robinson  
(Water Well Contractor)  
Contractor's License No. 22 Date 6/21/68, 19\_\_\_\_