

NOTICE TO WATER WELL CONTRACTOR  
The original and first copy  
of this report are to be  
filed with the

STATE ENGINEER, SALEM, OREGON 97310  
within 30 days from the date  
of well completion.

MARI... 3877  
**RECEIVED**  
AUG 12 1968  
STATE ENGINEER  
SALM OREGON

Well # 2  
**RECEIVED**  
AUG 1 1968  
STATE ENGINEER  
SALM OREGON  
cd  
6/2w-8P

**(1) OWNER:**

Name Mainline Foods Inc.  
Address P.O. Box 2165  
Salem, Ore. 97308

**(2) TYPE OF WORK (check):**

New Well  Deepening  Reconditioning  Abandon   
If abandonment, describe material and procedure in Item 12.

**(3) TYPE OF WELL:**

Rotary  Driven   
Cable  Jetted   
Dug  Bored

**(4) PROPOSED USE (check):**

Domestic  Industrial  Municipal   
Irrigation  Test Well  Other

**CASING INSTALLED:**

Threaded  Welded   
123/4" Diam. from 140 ft. to 99 1/2 ft. Gage .250  
103/4" Diam. from 96 ft. to 100 ft. Gage .250  
103/4" Diam. from 130 ft. to 185 ft. Gage .250  
103/4" Diam. from 201 ft. to 205 ft. Gage .250

**PERFORATIONS:**

Perforated?  Yes  No.

Type of perforator used Johnson Stainless Steel  
Screen  
Size of perforations in. by in.  
125 slot perforations from 125 ft. to 130 ft.  
90 " perforations from 185 ft. to 198 ft.  
30 " perforations from 198 ft. to 200 ft.  
perforations from ft. to ft.  
perforations from ft. to ft.

**(7) SCREENS:**

Well screen installed?  Yes  No

Manufacturer's Name Johnson  
Type 10" std size Model No. Stainless  
Diam. 103/4 Slot size 125 Set from 100 ft. to 105 ft.  
Diam. 103/4 Slot size 80 Set from 105 ft. to 125 ft.

**(8) WATER LEVEL: Completed well.**

Static level 140 ft. below land surface Date 7/29/68  
Artesian pressure lbs. per square inch Date

**(9) WELL TESTS:**

Drawdown is amount water level is lowered below static level

Was a pump test made?  Yes  No If yes, by whom? Stettler  
Yield: 700 gal./min. with 57 ft. drawdown after 1 hrs.  
Consult Stettler Supply  
Salem, Ore. 2  
" 620 " 42 " 2 "  
Ballor test gal./min. with ft. drawdown after hrs.  
Artesian flow g.p.m. Date  
Temperature of water Was a chemical analysis made?  Yes  No

**(10) CONSTRUCTION:**

Well seal—Material used Puddled clay  
Depth of seal 22 ft.  
Diameter of well bore to bottom of seal 16 in.  
Were any loose strata cemented off?  Yes  No Depth  
Was a drive shoe used?  Yes  No  
Did any strata contain unusable water?  Yes  No  
Type of water? depth of strata  
Method of sealing strata off  
Was well gravel packed?  Yes  No Size of gravel:  
Gravel placed from ft. to ft.

**(11) LOCATION OF WELL:**

County Marion Driller's well number 6/2W-8P5  
1/4 1/4 Section T. R. W.M.  
Bearing and distance from section or subdivision corner

**(12) WELL LOG:**

Diameter of well below casing 12  
Depth drilled 205 ft. Depth of completed well 205 ft.

Formation: Describe color, texture, grain size and structure of materials; and show thickness and nature of each stratum and aquifer penetrated, with at least one entry for each change of formation. Report each change in position of Static Water Level as drilling proceeds. Note drilling rates.

MATERIAL	From	To	SWL
Top soil	0	2	
Yellow clay	2	8	
Yellow silty clay	8	35	
Blue silty clay	35	55	
Fine muddy sand	55	70	
Clean blk sand	70	89	
Blk sand & coarse gravel	89	94	
Smal gravel & less sand	94	99	
Brwn sand & gravel	99	129	
Packed sand & gravel	129	135	
Gray silt	135	137	
Muddy gray sand	137	158	
<del>Sticky gray clay</del>	<del>158</del>	<del>162</del>	
Sticky gray clay	158	162	
Muddy gray sand	162	172	
Cemented gravels	172	184	
Clean C gravel & gray sand	184	202	
Brwn silty clay	202	205	

Work started 6/18/68 19 Completed 7/26/68 19  
Date well drilling machine moved off of well 7/26/68 19

**Drilling Machine Operator's Certification:**

This well was constructed under my direct supervision. Materials used and information reported above are true to my best knowledge and belief.

[Signed] Harry A. Robinson Date 7/31, 1968  
(Drilling Machine Operator)

Drilling Machine Operator's License No. 63

**Water Well Contractor's Certification:**

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

NAME Harry A. Robinson  
(Person, firm or corporation) (Type or print)

Address 2214 Front St. NE Salem, Ore.

[Signed] Harry A. Robinson  
(Water Well Contractor)

Contractor's License No. 22 Date 7/31/68 19