

STATE OF OREGON
WATER WELL REPORT
(as required by ORS 537.745)

MARI 4111

RECEIVED

(START CARD) # 20585

(1) OWNER:

Name PETER DINSDALE
Address 4290 Barrett Street South
City Salem State Oregon

Well Number: Two
AUG 0 8 1990

(2) TYPE OF WORK:

☒ New Well ☐ Deepen ☐ Recondition ☐ Abandon

(3) DRILL METHOD

☒ Rotary Air ☐ Rotary Mud ☐ Cable

☐ Other

(4) PROPOSED USE:

☒ Domestic ☐ Community ☐ Industrial ☐ Irrigation

☐ Thermal ☐ Injection ☐ Other

(5) BORE HOLE CONSTRUCTION:

Special Construction approval Yes No ☒ Depth of Completed Well 315 ft.

Explosives used ☐ ☒ Type Amount

HOLE			SEAL			Amount sacks or pounds
Diameter	From	To	Material	From	To	
10"	0'	79'	Cement	0'	79'	29
6"	79'	315'				

How was seal placed: Method ☐ A ☐ B ☒ C ☐ D ☐ E
☐ Other 5% Bentonite Used To Seal Well.

Backfill placed from ft. to ft. Material

Gravel placed from ft. to ft. Size of gravel

(6) CASING/LINER:

	Diameter	From	To	Gauge	Steel	Plastic	Welded	Threaded
Casing:	6"	+1	79'	250	☒	☐	☒	☐
					☐	☐	☐	☐
					☐	☐	☐	☐
					☐	☐	☐	☐
Liner:	4"	0'	315'	PVC	☐	☒	☒	☐
			SDR	26	☐	☐	☐	☐

Final location of shoe(s) 79 Ft.

(7) PERFORATIONS/SCREENS:

☒ Perforations Method Electric Saw

☐ Screens Type Material

From	To	Slot size	Number	Diameter	Tele/pipe size	Casing	Liner
255'	313'		144	1/8	x 5 Inch	☐	☒
						☐	☐
						☐	☐
						☐	☐
						☐	☐
						☐	☐

(8) WELL TESTS: Minimum testing time is 1 hour

☒ Pump ☐ Bailer ☐ Air ☐ Flowing

Yield gal/min Drawdown Drill stem at Time

35	48 Ft		1 hr. 2 Hrs.
----	-------	--	-----------------

Temperature of water Depth Artesian Flow Found

Was a water analysis done? ☐ Yes By whom

Did any strata contain water not suitable for intended use? ☐ Too little

☐ Salty ☐ Muddy ☐ Odor ☐ Colored ☐ Other

Depth of strata:

(9) LOCATION OF WELL by legal description:

County Marion Latitude Longitude
Township 8 South N or S, Range 4 West E or W, WM.
Section 25 SE 1/4 NE 1/4
Tax Lot Lot Block Subdivision

Street Address of Well (or nearest address)
7445 Skyline Road South, Salem, Oregon

(10) STATIC WATER LEVEL:

155 ft. below land surface. Date 7-16-90

Artesian pressure lb. per square inch. Date

(11) WATER BEARING ZONES:

Depth at which water was first found 98 Feet

From	To	Estimated Flow Rate	SWL
98 Ft	313 Ft	35 GPM	155'

(12) WELL LOG:

Ground elevation

Material	From	To	SWL
Soil	0	1	
Brown Clay	1	6	
Reddish Brown Clay	6	47	
Multi-Colored Broken Claystone	47	67	
Weathered Basalt	67	71	
Black Basalt	71	92	
Weathered Basalt	92	98	
Black Basalt	98	179	
Multi-Colored Clays, And			
Claystones	179	196	
Weathered Basalt, With Multi-			
Colored Clays & Claystones	196	216	
Weathered Basalt	216	258	
Badly Weathered Rock, With			
Multi-Colored Claystones	258	313	
Gray Sticky Clay	313	315	155'

Date started 7-13-90 Completed 7-16-90

(unbonded) Water Well Constructor Certification:

I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon well construction standards. Materials used and information reported above are true to my best knowledge and belief.

WWC Number

Signed Date

(bonded) Water Well Constructor Certification:

I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. all work performed during this time is in compliance with Oregon well construction standards. This report is true to the best of my knowledge and belief. MONDERS DRILLING, INC.

WWC Number 1325

Signed J. D. Monders Date 7-18-90



Oregon Water Resources Department
725 Summer Street NE, Suite A
Salem Oregon 97301
(503) 986-0900
www.wrd.state.or.us

Application for Well ID Number

RECEIVED

APR 19 2017

WATER RESOURCES DEPT
SALEM, OREGON

Do not complete if the well already has a Well Identification Number.

I. OWNER INFORMATION

Current Owner Name (please print): Willy Dinsdale ; BH Land LLC
Mailing Address: P.O. Box 357
City, State, Zip: Independence, OR 97351
Mail Well ID Tag to: ☒ SAME AS ABOVE ☐ In Care Of (C/O)
Name & Address: _____
City, State, Zip: _____

II. WELL LOCATION INFORMATION (Please fill out as completely as possible)

Township: 8 (North South) Range: 4 (East West) Section: 25
Tax Lot: 100 County Marion 1/4 _____ 1/4 _____
GPS Coordinates: 44.84830, -123.11448 WGS 84 from iPAD
Street Address of Well, City: 7445 Skyline Road South, Salem, OR
If the property had a different street address in the past: _____

III. GENERAL WELL INFORMATION (Please fill out as completely as possible)

Use of Well (domestic, irrigation, commercial, industrial, monitoring): domestic & irrigation
Date Well Constructed (or property built): 7/16/1990 Total Well Depth: 315 Casing Diameter: 6"
Owner at time the well was constructed (if known): Peter Dinsdale
Other Information: _____

SUBMITTED BY (please print): Justin Iverson
PHONE: 503-986-0933 EMAIL &/or FAX: justin.iverson@oregon.gov

Send application to: Oregon Water Resources Department 725 Summer St NE, Suite A, Salem, Oregon 97301; or fax to (503) 986-0902. Applications are processed in the order they are received, and Well ID Numbers are mailed within 4-5 business days.

For Official Use Only by the Oregon Water Resources Department:

Received Date:

4-19-17

Well Log Number:

MARI 4111

Well Identification #:

120597