

MARION 4535

NOTICE TO WATER WELL CONTRACTOR

The original and first copy of this report are to be filed with the

RECEIVED

RECEIVED

OCT 25 1965

WATER WELL REPORT NOV 18 1965

State Well No. 6/2w-29 H

STATE ENGINEER, SALEM, OREGON 97310

STATE OF OREGON

STATE ENGINEER

State Permit No.

(1) OWNER:

Name JOHN L. LESHER

Address RT. 2 BOX 317 SALEM, OREGON

(2) LOCATION OF WELL:

County MARION Driller's well number I099

1/4 1/4 Section 29 T. 6 S R. 2 W W.M.

Bearing and distance from section or subdivision corner

(3) TYPE OF WORK (check):

New Well [X] Deepening [ ] Reconditioning [ ] Abandon [ ]

(4) PROPOSED USE (check):

Domestic [ ] Industrial [ ] Municipal [ ] Irrigation [X] Test Well [ ] Other [ ]

(5) TYPE OF WELL:

Rotary [ ] Driven [ ] Cable [X] Jetted [ ] Dug [ ] Bored [ ]

(6) CASING INSTALLED:

10" Diam. from TOP ft. to 60 ft. Gage 250

(7) PERFORATIONS:

Perforated? [X] Yes [ ] No Type of perforator used MILLS Size of perforations 2 in. by 3/8 in.

(8) SCREENS:

Well screen installed? [ ] Yes [X] No Manufacturer's Name Model No.

(9) CONSTRUCTION:

Well seal—Material used in seal CEMENT & PUDDLE CLAY Depth of seal 18 ft. Was a packer used? Diameter of well bore to bottom of seal 12 in.

(10) WATER LEVELS:

Static level 2 ft. below land surface Date 10/12/65 Artesian pressure lbs. per square inch Date

(11) WELL TESTS:

Drawdown is amount water level is lowered below static level Was a pump test made? [X] Yes [ ] No If yes, by whom? DRILLER Yield: 200 gal./min. with 19 ft. drawdown after 4 hrs.

(12) WELL LOG:

Diameter of well below casing Depth drilled 60 ft. Depth of completed well 60 ft. Formation: Describe by color, character, size of material and structure, and show thickness of aquifers and the kind and nature of the material in each stratum penetrated, with at least one entry for each change of formation.

Table with columns MATERIAL, FROM, TO. Rows: BEAVER DAM (0-6), BROWN DIRT (6-18), BLUE CLAY (18-32), BROWN SAND & GRAVEL (32-60)

Work started OCT. 8 1965 Completed OCT 12 1965 Date well drilling machine moved off of well OCT 12 1965 19

(13) PUMP:

Manufacturer's Name Type: H.P.

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

NAME WILLAMETTE DRILLING CO (Person, firm or corporation) (Type or print)

Address RT. 2 BOX 276 SALEM, OREGON

Drilling Machine Operator's License No. 141

[Signed] Emiel O. Beyer (Water Well Contractor)

Contractor's License No. 2 Date OCT. 12 1965 19