

NOTICE TO WATER WELL CONTRACTOR

The original and first copy of this report are to be filed with the

RECEIVED JUN 4 - 1971

STATE OF OREGON

STATE ENGINEER, SALEM, OREGON 97310

within 30 days from the date of well completion.

(Please type or print)

STATE ENGINEER SALEM, OREGON

(Do not write above this line)

State Well No. 6/2W-2536bt

State Permit No. G-5548

(1) OWNER:

Name ANDREW SMITH Address Rte 2 SILVERTON ORE.

(2) TYPE OF WORK (check):

New Well [x] Deepening [] Reconditioning [] Abandon []

(3) TYPE OF WELL:

Rotary [] Driven [] Cable [x] Jetted [] Dug [] Bored []

(4) PROPOSED USE (check):

Domestic [] Industrial [] Municipal [] Irrigation [x] Test Well [] Other []

CASING INSTALLED:

12" Diam. from 0 ft. to 190 ft. Gage 250

PERFORATIONS:

Type of perforator used Mills Perforated? [x] Yes [] No Size of perforations 2 1/2 in. by 5/8 in.

(7) SCREENS:

Well screen installed? [] Yes [x] No Manufacturer's Name Type Model No.

(8) WELL TESTS:

Drawdown is amount water level is lowered below static level Was a pump test made? [x] Yes [] No Yield: 500 gal./min. with 4 ft. drawdown after 3 hrs.

(9) CONSTRUCTION:

Well seal-Material used DRILLING CLAY Well sealed from land surface to 40 ft. Diameter of well bore to bottom of seal 10 in.

(10) LOCATION OF WELL:

County Marion Driller's well number 1/4 1/4 Section 25 T. 4, S. R. 2, W W.M. Bearing and distance from section or subdivision corner

(11) WATER LEVEL: Completed well.

Depth at which water was first found 70 ft. Static level 47 ft. below land surface. Date 5-25-71 Artesian pressure lbs. per square inch. Date

(12) WELL LOG:

Diameter of well below casing 12 Depth drilled 190 ft. Depth of completed well 190 ft.

Formation: Describe color, texture, grain size and structure of materials; and show thickness and nature of each stratum and aquifer penetrated, with at least one entry for each change of formation.

Table with columns: MATERIAL, From, To, SWL. Rows include: BROWN - CLAY (0-22), BLUE - (22-57), BROWN - 11" SANDY (57-80), BROWN - UNCONSOLIDATED SAND + GRAVEL + SILT (80-110), BROWN - CEMENTED SAND + GRAVEL (110-140), BROWN - UNCONSOLIDATED SAND + GRAVEL (140-181), BLUE - CLAY (181-189), BLACK - BASALT ROCK (189-190).

Work started 5-10-1971 Completed 5-25-1971 Date well drilling machine moved off of well 5-25-1971

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision. Materials used and information reported above are true to my best knowledge and belief.

[Signed] Miller West Date 5-26, 1971 (Drilling Machine Operator)

Drilling Machine Operator's License No. 188

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

Name Miller West (Person, firm or corporation) (Type or print)

Address 5545 Jorie Rd SE S.E. Salem

[Signed] Andrew R. Miller (Water Well Contractor)

Contractor's License No. 317 Date 5-26-1971