

RECEIVED

DEC 31 1984

MAR 4.883

65/3W-13

STATE OF OREGON
WATER WELL REPORT
(as required by ORS 537.765)

WATER RESOURCES DEPARTMENT
SALEM, OREGON

(for official use only)

(1) OWNER:

Name JEAN Mossbrucker
Address 2050 Brooklake Rd. NE
City Salem State Ore

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐
If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary Air ☐ Driven ☐
Rotary Mud ☐ Dug ☐
Cable ☒ Bored ☐

(4) PROPOSED USE (check):

Domestic ☒ Industrial ☐ Municipal ☐
Thermal: ☐
Irrigation ☐ Withdrawal ☐ Reinjection ☐
Other: ☐
Piezometric ☐ Grounding ☐ Test ☐

(5) CASING INSTALLED:

Steel ☒ Plastic ☐
Threaded ☐ Welded ☒

6" Diam. from +1 ft. to 130 ft. Gauge .250
" Diam. from _____ ft. to _____ ft. Gauge _____

(6) LINER INSTALLED:

Steel ☐ Plastic ☐
Threaded ☐ Welded ☐

" Diam. from _____ ft. to _____ ft. Gauge _____

(6) PERFORATIONS:

Perforated? ☐ Yes ☒ No
Size of perforations in. by _____

_____ perforations from _____ ft. to _____ ft.
_____ perforations from _____ ft. to _____ ft.
_____ perforations from _____ ft. to _____ ft.

(7) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name _____
Type _____ Model No. _____
Diam. _____ Slot Size _____ Set from _____ ft. to _____ ft.
Diam. _____ Slot Size _____ Set from _____ ft. to _____ ft.

(8) WELL TESTS:

Drawdown is amount water level is lowered below static level

Was a pump test made? ☐ Yes ☒ No If yes, by whom?

_____ gal./min. with _____ ft. drawdown after _____ hrs.
Air test _____ gal./min. with drill stem at _____ ft. _____ hrs.
Bailer test 15 gal./min. with 20 ft. drawdown after 1 hrs.
Artesian flow _____ g.p.m.

Temperature of water 52° Depth artesian flow encountered _____ ft.

(9) CONSTRUCTION:

Special standards: Yes ☐ No ☒

Well seal—Material used Cement
Well sealed from land surface to 18 ft.
Diameter of well bore to bottom of seal 10 in.
Diameter of well bore below seal 6 in.
Amount of sealing material 10 sacks ☒ pounds ☐
How was cement grout placed? press grouted

Was pump installed? _____ Type _____ HP _____ Depth _____ ft.
Was a drive shoe used? ☒ Yes ☐ No Plugs _____ Size: location _____ ft.
Did any strata contain unusable water? ☐ Yes ☒ No
Type of Water? _____ depth of strata _____

Method of sealing strata off _____
Was well gravel packed? ☐ Yes ☒ No Size of gravel: _____
Gravel placed from _____ ft. to _____ ft.

(10) LOCATION OF WELL by legal description:

County Marion 1/4 1/4 of Section 13 of
Township 6 S Range 3 W WM.
(Township is North or South) (Range is East or West)
Tax Lot _____ Lot _____ Block _____ Subdivision _____
MAILING ADDRESS OF WELL (or nearest address) _____

(11) WATER LEVEL of COMPLETED WELL:

Depth at which water was first found 105 ft.
Static level 45 ft. below land surface. Date 12-16-84
Artesian pressure _____ lbs. per square inch. Date _____

(12) WELL LOG:

Diameter of well below casing _____

Depth drilled 130 ft. Depth of completed well 130 ft.
Formation: Describe color, texture, grain size and structure of materials; and show thickness and nature of each stratum and aquifer penetrated, with at least one entry for each change of formation. Report each change in position of Static Water Level and indicate principal water-bearing strata.

MATERIAL	From	To	SWL
Top Soil	0	2	
Brown Clay	2	45	
Light Brown Clay	45	58	
Light Brown Clay & Sand	58	64	
Dark Gray Clay	64	85	
Gray Clay & Gravel	85	105	60
Brown Clay Sand & Gravel	105	120	
Brown Sand & Gravel	120	130	45

Date work started 12-5-84 /completed 12-16-84
Date well drilling machine moved off of well 12-17 19 84

(unbonded) Water Well Constructor Certification (if applicable):

This well was constructed under my direct supervision. Materials used and information reported above are true to my best knowledge and belief.

[Signed] Thomas D Flores Date 12-29, 19 84

(bonded) Water Well Constructor Certification:

Bond 2241032 Issued by: Western Surety Company
(number) (Surety Company Name)
On behalf of Thomas D Flores
(type or print name of Water Well Constructor)

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief:

(Signed) Thomas D Flores
(Water Well Constructor)

(Dated) 12-29-84

NOTICE TO WATER WELL CONSTRUCTOR
The original and first copy of this report
are to be filed with the

WATER RESOURCES DEPARTMENT,
SALEM, OREGON 97310
within 30 days from the date of well completion.

SP*46866-690