

92 30 24 AB

(START CARD) # 69875

(1) OWNER: Well Number 2
Name MILDRED WRIGHT
Address 3075 EDGEWOOD DR. S.
City JEFFERSON State ORE Zip 97352

(2) TYPE OF WORK: ☒ New Well ☐ Deepen ☐ Recondition ☐ Abandon

(3) DRILL METHOD:
☒ Rotary Air ☐ Rotary Mud ☐ Cable
☐ Other _____

(4) PROPOSED USE:
☒ Domestic ☐ Community ☐ Industrial ☐ Irrigation
☐ Thermal ☐ Injection ☐ Other _____

(5) BORE HOLE CONSTRUCTION: 536'
Special Construction approval ☐ Yes ☒ No Depth of Completed Well _____ ft
Explosives used ☐ Yes ☒ No Type _____ Amount _____

HOLE			SEAL			Amount
Diameter	From	To	Material	From	To	sacks or pounds
10"	0	22'	CEMENT	0'	37 1/2	9 sacks
8 7/8"	22'	37 1/2'				+ 50 lb
6"	37 1/2'	536				BEATONITE

How was seal placed: Method ☐ A ☐ B ☒ C ☐ D ☐ E
☐ Other _____

Backfill placed from _____ ft. to _____ ft. Material _____
Gravel placed from _____ ft. to _____ ft. Size of gravel _____

	Diameter	From	To	Gauge	Steel	Plastic	Welded	Threaded
Casing:	6"	+1 1/2'	37 1/2'	1/4"	☒	☐	☒	☐
					☐	☐	☐	☐
					☐	☐	☐	☐
					☐	☐	☐	☐
					☐	☐	☐	☐
Liner:					☐	☐	☐	☐
					☐	☐	☐	☐

Final location of shoe(s)

(7) PERFORATIONS/SCREENS: *N/A*

☐ Perforations Method _____

☐ Screens Type _____ Material _____

From	To	Slot size	Number	Diameter	Tele/pipe size	Casing	Liner
						☐	☐
						☐	☐
						☐	☐
						☐	☐
						☐	☐

(8) WELL TESTS: Minimum testing time is 1 hour

☐ Pump ☐ Bailer ☒ Air ☐ Flowing Artesian

Yield gal/min	Drawdown	Drill stem at	Time
15 gpm	216'	536'	4 hr.

Temperature of Water 50 Depth Artesian Flow Found _____

Was a water analysis done? ☒ Yes By whom JFK

Did any strata contain water not suitable for intended use? ☐ Too little YES

☐ Salty ☐ Muddy ☐ Odor ☐ Colored ☐ Other _____
Depth of strata: 16 TO 18' (CASE) & CEMENT

(9) LOCATION OF WELL by legal description:

County MARION Latitude _____ Longitude _____
Township 9S N or S. Range 3W E or W. WM. _____
Section 24 NW $\frac{1}{4}$ SE $\frac{1}{4}$ _____
Tax Lot 62570 Lot 626 Block _____ Subdivision _____
Street Address of Well (or nearest address) SAME AS #1

(10) STATIC WATER LEVEL:

220' ft. below land surface. Date 12-11-95
Artesian pressure _____ lb. per square inch. Date _____

(11) WATER BEARING ZONES:

Depth at which water was first found 515'

From	To	Estimated Flow Rate	SWL
515'	516'	156 gpm.	220'

(12) WELL LOG:

Ground elevation

Material	From	To	SWL
TOP SOIL	0'	1'	
WEATHERED BASALT STICKY	1'	16'	
BASALT BULDERS 5"-6"	16'	18'	
CLAY GRAY SOFT STICKY	18'	25'	
CLAYSTONE GRAY FIRM	25'	31'	
CLAYSTONE BLUE FIRM	31'	490'	
SANDSTONE GRAY	490'	530'	220
SANDY CLAYSTONE GRAY	530'		

RECEIVED

~~EO 201995~~

SALEM, ORE.

Date started 9-18-95 Completed 12-20-95

(unbonded) Water Well Constructor Certification:

I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon well construction standards. Material used and information reported above are true to my best knowledge and belief.

Signed _____ WWC Number _____
Date _____

(bonded) Water Well Constructor Certification:

I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon well construction standards. This report is true to the best of my knowledge and belief.

is true to the best of my knowledge and belief.

Signed James R. Sneed WWC Number 1279
Date 12-20-95