

STATE ENGINEER
Salem, Oregon

5214
MARION

Well Record

STATE WELL NO. 6/3W-250
COUNTY Marion
APPLICATION NO. GR-4166

OWNER: Bonneville Power Administration Mailing Address: P.O. Box 3537

LOCATION OF WELL: Owner's No. CITY AND STATE: Portland 8, Oregon

SW 1/4 SE 1/4 Sec. 25 T. 6 S, R. 3 W., W.M.

Bearing and distance from section or subdivision corner Approx. 40' W. & 160' N. of SE Cor. of Sec. 25

			X

Section 25

Altitude at well

TYPE OF WELL: Drilled Date Constructed 3/14/53

Depth drilled 146 ft. Depth cased 146 ft.

CASING RECORD:

10 in. standard pipe casing set to 146 feet

FINISH:

1 1/4" x 3/8" 18 per foot from 75 to 80 ft.; 86 to 91 ft.; 99 to 109 ft.; 133 to 143 ft.;

AQUIFERS:

WATER LEVEL:

26 ft. below surface

PUMPING EQUIPMENT: Type Layne & Bowler 6 stage turbine H.P. 15
Capacity 200 G.P.M.

WELL TESTS:

Drawdown 22 ft. after hours 250 G.P.M.
Drawdown 50 ft. after hours 410 G.P.M.

USE OF WATER Domestic Temp. °F. 19

SOURCE OF INFORMATION Well Registration Statement Cert. # GR-3731

DRILLER or DIGGER Force Account, Martin Jansen

ADDITIONAL DATA:

Log X Water Level Measurements Chemical Analysis Aquifer Test

REMARKS:

