

Material	From	To
Top soil, brown	0	5
Clay, brown, fine, sandy	5	35
Clay, brown, fine sandy w/ some pea gravel	35	40
Clay, brown, fine, sandy w/ gravel up to 1"	40	46
Clay, brown	46	49
Clay, dark brown	49	65
Clay, dark brown, fine, sandy	65	70
Sand, cemented, rusty brown	70	74
Gravel, pea up to 1" w/ sand, mud, rusty brown w/ some 4"	74	77
Gravel, up to 6" w/ some sand, brown, medium	77	107
Gravel up to 4" w/ some sand, brown, medium, loosely cemented	107	115
Gravel up to 6" w/ some sand, brown, medium, loosely cemented	115	125
Gravel up to 6" w/ some sand, black, medium	125	128
Gravel up to 6", rusty, w/ some sand, brown, loosely cemented	128	145
Clay, brown to blue	145	146
Clay, blue	146	150
Clay, blue-green	150	153
Clay, dark green, fine, sandy	153	159
Gravel, w/ clay, green, w/ sand, med-coarse	159	160
Gravel w/ sand, med-coarse	160	164
Gravel & sand w/ some clay, green	164	168
Gravel & sand, med-coarse	168	176
Gravel & sand, med-coarse, cemented	176	189
Sand, cemented	189	190
Gravel, w/ some sand & some clay, gray	190	195
Gravel & sand, med-coarse, loosely cemented	195	210
Gravel & sand, med-coarse, w/ some clay, gray up to 6"	210	221
Gravel, cemented w/ some sand, med. up to 6"	221	238
Gravel, cemented w/ some clay, blue-green up to 6"	238	248
Gravel w/ clay, brown	248	250
Gravel w/ some sand & some clay, gray, cemented	250	255
Clay, gray, hard	255	256
Clay, brown, w/ some stray gravel	256	261
Clay, light brown	261	264
Gravel w/ some sand, brown, loosely cemented up to 6"	264	279
Gravel w/ sand, med-coarse, brown w/some clay, blue gray	279	288
Gravel w/ sand, med-coarse brown, some cemented	288	318
Gravel w/ sand, med-coarse, brown, w/ some clay, brown	318	323
Clay, brown & gray	323	326
Clay, gray, sandy	326	330
Clay & gravel, black, sandy	330	333

RECEIVED

FEB 23 1981

WATER RESOURCES DEPT

SALEM, OREGON

(5) Casing Installed:

30" Diameter from +1'10"	to 25'	Gauge .375
16" Diameter from +2'	to 159'2"	Gauge .375
16" Diameter from 259'5"	to 264'5"	Gauge .375
16" Diameter fro 324'6"	to 329'6"	Gauge .375

$\frac{1}{4}$ " thick steel plate welded on bottom

OREGON HEALTH DIVISION ONLY:

Received Date:

County Well Log ID #

9/18/00

MARI 5224

WELL IDENTIFICATION LABEL ATTACHMENT FORM (OREGON HEALTH DIVISION)

COMPANY /CURRENT WELL OWNER:

OWNER (S) WELL NO: #8

Name: City of Keizer

Mailing Address: P.O. Box 21000

City: Keizer State: OR Zip: 97307 Phone: (503) 390-3700

CONTACT PERSON:

NAME: Joe Edgell PHONE # (503) 390-3700

THIS FORM IS ONLY TO BE USED FOR WELLS WITH POSITIVELY IDENTIFIED WATER SUPPLY WELL REPORTS.

O.H.D. OFFICIAL USE ONLY

TOWNSHIP: 6 N RANGE: 3 SECTION: 26 TAX-LOT: 4000

Well Identification Label : L- 32105

LABEL ATTACHED BY: Tom Pattee DATE: 8/18/00 (O.H.D. OFFICIAL)

(WATER SUPPLY WELL REPORT MUST BE ATTACHED!)

Please Return Completed Form to:

Larry D. McQueen Well Identification Program Oregon Water Resources Department 158 12th Street NE Salem, OR 97310