

STATE ENGINEER
Salem, Oregon

M 171.5.304
Well Record

STATE WELL NO. 6/3W-27A
COUNTY MARION
APPLICATION NO. GR-2943

OWNER: Vernon M. Wilson

MAILING ADDRESS: Rt. 2, Box 477

LOCATION OF WELL: Owner's No. _____

CITY AND STATE: Salem, Oregon

NE 1/4 NE 1/4 Sec. 27 T. 6 N. S. R. 3 E. W., W.M.

Bearing and distance from section or subdivision corner 695' S. and 1880' E.

Section _____

Altitude at well _____

TYPE OF WELL: drilled Date Constructed 1954

Depth drilled 123 Depth cased 120

CASING RECORD:

8-inch

FINISH:

Perforations from 82' to 120'

AQUIFERS:

Subsoil, silt, sand, gravel and shale

WATER LEVEL:

46-feet

PUMPING EQUIPMENT: Type Fairbanks Morse Turbine H.P. 10

Capacity 200 G.P.M.

WELL TESTS:

Drawdown 98 ft. after _____ hours Pumping 450 G.P.M.

Drawdown _____ ft. after _____ hours _____ G.P.M.

USE OF WATER Irrigation Temp. _____ °F., 19 _____

SOURCE OF INFORMATION GR-2767

DRILLER or DIGGER _____

ADDITIONAL DATA:

Log Water Level Measurements _____ Chemical Analysis _____ Aquifer Test _____

REMARKS:

Subsoil	3	3
Yellow silt	76	79
Sand	2	81
Cemented gravel	12	93
Water-bearing gravel	1	94
Cemented gravel	27	121
Water Gravel and sand	1	123
Blue shale	2	125