

RECEIVED

WELL I.D.# 15078

JUL 24 1998

STATE OF OREGON WATER SUPPLY WELL REPORT

(START CARD) # 111429

WATER RESOURCES SALEM, OREGON

Instructions for completing this report are on the last page of this form.

(1) OWNER: Well Number Name ROBERT KUENZI Address 1973 HIBBARD RD. City SILVERTON State OR Zip 97381

(2) TYPE OF WORK [] New Well [] Deepening [X] Alteration (repair/recondition) [] Abandonment

(3) DRILL METHOD: [] Rotary Air [] Rotary Mud [] Cable [] Auger [X] Other NO DRILLING

(4) PROPOSED USE: [] Domestic [] Community [] Industrial [X] Irrigation [] Thermal [] Injection [] Livestock [] Other

(5) BORE HOLE CONSTRUCTION: Special Construction approval [] Yes [X] No Depth of Completed Well 193 ft. Explosives used [] Yes [X] No Type Amount

Table with columns for HOLE Diameter, From, To, Material, SEAL From, To, Sacks or pounds. Entry: SEE #12

How was seal placed: Method [] A [] B [] C [] D [] E [] Other Backfill placed from ft. to ft. Material Gravel placed from ft. to ft. Size of gravel

(6) CASING/LINER: Table with columns for Diameter, From, To, Gauge, Steel, Plastic, Welded, Threaded. Includes Casing and Liner rows.

(7) PERFORATIONS/SCREENS: Table with columns for From, To, Slot size, Number, Diameter, Tele/pipe size, Casing, Liner. Includes Perforations and Screens rows.

(8) WELL TESTS: Minimum testing time is 1 hour. [X] Pump [] Bailer [] Air [] Flowing Artesian. Yield gal/min 70, Drawdown 42, Drill stem at 4, Time 1 hr.

Temperature of water 56° Depth Artesian Flow Found Was a water analysis done? [X] Yes By whom WATER LAB Did any strata contain water not suitable for intended use? [] Too little [] Salty [] Muddy [] Odor [] Colored [] Other Depth of strata:

(9) LOCATION OF WELL by legal description: County MARION Latitude Longitude Township 7S N or S Range 1W E or W. WM. Section 18 SW 1/4 SE 1/4 Tax Lot 800 Lot Block Subdivision Street Address of Well (or nearest address) 10004 Kaufman Rd. N.E. SILVERTON, OR 97381

(10) STATIC WATER LEVEL: 43 ft. below land surface. Date 4-21-98 Artesian pressure lb. per square inch. Date

(11) WATER BEARING ZONES: Depth at which water was first found ORIGINAL

Table with columns: From, To, Estimated Flow Rate, SWL. Row: ORIGINAL

(12) WELL LOG: Ground Elevation

Table with columns: Material, From, To, SWL. Content: THIS WELL WAS BACKFILLED WITH CEMENT PLUGS TO ELIMINATE SOME HIGH CONDUCTIVITY WATER. ORIGINAL WELL LOG DATED 12-9-97 START CARD # 104229. GRAVEL BACKFILL 343 325 CEMENT GROUT 325 269 GRAVEL 269 248 CEMENT GROUT 248 193. Westerberg Drilling, Inc. 36728 S. Kropf Rd. Molalla, OR 97038 829-2526

Date started 4-4-98 Completed 4-21-98

(unbonded) Water Well Constructor Certification: I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief. WWC Number Signed Date

(bonded) Water Well Constructor Certification: I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief. WWC Number 688 Signed Steve N. Stahl Date 6-5-98