

(1) OWNER: Well No: 1862
Name LARRY/DANN MONAGON
Address 1585 CHEMAMA RD. N.
City KEIZER St OR Zip 97303

(2) TYPE OF WORK: NEW WELL
(3) DRILL METHOD: CABLE
(4) PROPOSED USE: IRRIGATION

(5) BORE HOLE CONSTRUCTION:

Special Construction	Approval NO	Depth of Compl.	Well	80 ft		
Explosives used NO	Type	Amount				
HOLE SEAL						
Diam.	From	To	Material	From	To	Amount
12	0	22	BENTONITE CHIP	0	22	28 SAX
8	22	80				

Seal placement method POURED/PROBED
Backfill: from ___ ft to ___ ft Material
Gravel: from ___ ft to ___ ft Size

(6) CASING/LINER:

Casing	Diam.	From	To	Gauge	Material	Connection
8		+1.5	78.5	.25	STEEL	WELDED

Liner

Final Location of shoe(s) 79

(7) PERFORATIONS/SCREENS:

Perf. Method TORCH
 Screens Type

From	To	Slot Size	Number	Diam.	Material	Tele/pipe Size	Casing/liner
70	78.5	.2X6"	120				CASING

(8) WELL TESTS: Minimum testing time is 1 hour
Test type AIR

Yield GPM	Draw-down	Drill stem at	Time
300		78	1 hr.
300		62	3

Temperature of water 54
Was water analysis done? NO
Reason for water not suitable for use
Depth of strata

Depth Artesian Flow Found
By whom

(9) LOCATION OF WELL by legal description:
County MARION Lat. ' ' ' ' Long. ' ' ' '
Township 7 S Range 3 W W.M.
Section 4 NE 1/4 NE 1/4
Tax Lot 300 Lot Block Subdivision
Street Address of Well (or nearest Address)
1585 N CHEMAMA ROAD KEIZER, OR

(10) STATIC WATER LEVEL:
28 ft. below land surface. Date 07/06/99
Artesian pressure ___ lb per square in. Date

(11) WATER BEARING ZONES:

Depth at which water was first found	21	Est Flow Rate	SWL
From	To		
30	80	300+	28

(12) WELL LOG:

Material	Ground elevation		SWL
	From	To	
TOP SOIL, LOAMY	0	4	
BROWN CLAY	4	14	
BROWN CLAY, DENSE/FIRM	14	22	
SAND, FINE TO COARSE W/OCC FINE GRAVEL	22	61	
MED/COARSE SAND AND OCC FINE GRAVEL	61	80	28

DAVE PAYSINGER, BLUE WATER DRILLING CO.
(503) 209-8989

Date started 06/25/99 Completed 07/06/99

(unbonded) Water Well Constructor Certification: I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to my best knowledge and belief.

Signed _____ WWC Number _____
Date _____

(bonded) Water Well Constructor Certification: I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

Signed *David G. Paysinger* WWC Number 1438
Date 07/06/99

RECEIVED
 JUL 08 1999
 WATER RESOURCES DEPT.
 SALEM, OREGON