

MARI
54685

STATE OF OREGON
WATER SUPPLY WELL REPORT
(as required by ORS 537.765)

WELL I.D. # L 27629
START CARD # 129258

Instructions for completing this report are on the last page of this form.

(1) OWNER: Well Number
Name church of god 7 th day
Address po BOX 248
City marion State ore Zip 97359

(2) TYPE OF WORK
 New Well Deepening Alteration (repair/recondition) Abandonment

(3) DRILL METHOD:
 Rotary Air Rotary Mud Cable Auger
 Other

(4) PROPOSED USE:
 Domestic Community Industrial Irrigation
 Thermal Injection Livestock Other

(5) BORE HOLE CONSTRUCTION:
Special Construction approval Yes No Depth of Completed Well 50 ft.
Explosives used Yes No Type Amount

HOLE SEAL

Diameter	From	To	Material	From	To	Sacks or pounds
10	0	20	bentonite	0	20	19 sak
6	+1	50				

How was seal placed: Method A B C D E
 Other filled to top w/dry bentonite
Backfill placed from ___ ft. to ___ ft. Material
Gravel placed from ___ ft. to ___ ft. Size of gravel

(6) CASING/LINER:

Diameter	From	To	Gauge	Steel	Plastic	Welded	Threaded
Casing: 6	+1	50	250	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
Liner:				<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>

(7) PERFORATIONS/SCREENS:

Perforations Method torch cut
 Screens Type Material

From	To	Slot size	Number	Diameter	Tele/pipe size	Casing	Liner
44	49	1/8	16	6 long		<input checked="" type="checkbox"/>	<input type="checkbox"/>

(8) WELL TESTS: Minimum testing time is 1 hour

Yield gal/min	Drawdown	Drill stem at	Flowing Time
50 GPM		44	1 hr.

Temperature of water 55° Depth Artesian Flow Found
Was a water analysis done? Yes By whom
Did any strata contain water not suitable for intended use? Too little
 Salty Muddy Odor Colored Other
Depth of strata:

(9) LOCATION OF WELL by legal description:
County marion Latitude Longitude
Township 9 S N or S Range 2 W E or W. WM.
Section 27 SE 1/4 SE 1/4
Tax Lot 700 Lot Block Subdivision
Street Address of Well (or nearest address) 7478 stayton rd

(10) STATIC WATER LEVEL:
9' ft. below land surface. Date 2/11/00
Artesian pressure lb. per square inch. Date

(11) WATER BEARING ZONES:

Depth at which water was first found

From	To	Estimated Flow Rate	SWL
18	50	50 gpm	

(12) WELL LOG:

Ground Elevation

Material	From	To	SWL
soil	0	1	
sand gravel w/brown clay	1	20	
gravel brown sand	20	36	
gray sand gralel	36	38	
brown sand gravel	38	50	

Date started 2/4/00 Completed 2/19/00
(unbonded) Water Well Constructor Certification:
I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.
Signed _____ WWC Number _____ Date _____

(bonded) Water Well Constructor Certification:
I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.
Signed _____ WWC Number 1585 Date 2/20/00