

NOTICE TO WATER WELL CONTRACTOR
The original and first copy of this report
are to be filed with the

WATER RESOURCES DEPARTMENT
SALEM, OREGON 97310
within 30 days from the date
of well completion.

WATER WELL REPORT

STATE OF OREGON

(Please type or print)

(Do not write above this line)

State Well No. 65/1E-7ad

State Permit No. _____

RECEIVED
JAN 24 1980
WATER RESOURCES DEPT
SALEM, OREGON

MAR 25 1980
Per survey
Crew
Large is 16"
Crew

(1) OWNER:

Name LEONARD HEIDT
Address 14563 OTTER LN N.E.
MT ANGEL, OR.

(2) TYPE OF WORK (check):

New Well Deepening Reconditioning Abandon
If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Primary Driven
Cased Jetted
 dug Bored

(4) PROPOSED USE (check):

Domestic Industrial Municipal
Irrigation Test Well Other

(5) CASING INSTALLED:

Threaded Welded

8" Diam. from 0 ft. to 183 ft. Gage .250
8" Diam. from 113 ft. to 273 ft. Gage .188
" Diam. from _____ ft. to _____ ft. Gage _____

(6) PERFORATIONS:

Perforated? Yes No.

Type of perforator used Torch
Size of perforations 3/16" in. by 6" in.
65' perforations from 63 ft. to 125 ft.
80 perforations from 120 ft. to 273 ft.
perforations from _____ ft. to _____ ft.

(7) SCREENS:

Well screen installed? Yes No

Manufacturer's Name _____
Type _____ Model No. _____
Diam. _____ Slot size _____ Set from _____ ft. to _____ ft.
Diam. _____ Slot size _____ Set from _____ ft. to _____ ft.

(8) WELL TESTS:

Drawdown is amount water level is lowered below static level

a pump test made? Yes No If yes, by whom? DRILLER
Yield: 145 gal./min. with 55 ft. drawdown after 2 hrs.
" 160 " 87 " 4 "
" " " " "
" " " " "
Artesian flow _____ gal./min. with _____ ft. drawdown after _____ hrs.

Temperature of water 51 Depth artesian flow encountered _____ ft.

(9) CONSTRUCTION:

Well seal—Material used CEMENT
Well sealed from land surface to 29 ft.
Diameter of well bore to bottom of seal 12 + in.
Diameter of well bore below seal 8 in.
Number of sacks of cement used in well seal 19 sacks
How was cement grout placed? PUMP

Was a drive shoe used? Yes No Plugs _____ Size: location _____ ft.
Did any strata contain unusable water? Yes No
Type of water? _____ depth of strata _____
Method of sealing strata off _____
Was well gravel packed? Yes No Size of gravel: _____
Gravel placed from _____ ft. to _____ ft.

(10) LOCATION OF WELL:

County MARION Driller's well number _____
NE 1/4 SE 1/4 Section 7 T. 6S R. 1W W.M.
Bearing and distance from section or subdivision corner _____

(11) WATER LEVEL: Completed well.

Depth at which water was first found 12 ft.
Static level 19 ft. below land surface. Date JAN 16, 1980
Artesian pressure _____ lbs. per square inch. Date _____

(12) WELL LOG:

Diameter of well below casing 6 1/2"

Depth drilled 300 ft. Depth of completed well 300 ft.

Formation: Describe color, texture, grain size and structure of materials; and show thickness and nature of each stratum and aquifer penetrated, with at least one entry for each change of formation. Report each change in position of Static Water Level and indicate principal water-bearing strata.

MATERIAL	From	To	SWL
TOPSOIL	0	2	
SILTY CLAY, BROWN	2	10	
CEMENT GRAVEL & BOULDERS	10	23	13
ROCK	23	63	
CLAY GREY & CEMENT GRAVEL	63	81	19
CLAY	81	128	
CEMENT GRAVEL BROWN	128	130	
CEMENT GRAVEL GREY	130	135	
CEMENT GRAVEL BROWN	135	155	19
SILT DARK GREY	155	185	
CLAY GREY	185	207	
CLAY & CEMENT GRAVEL	207	213	19
CLAY STICKEY GREY	213	226	
SHALE BLUE	226	300	

Work started Nov 11, 1979 Completed JAN 17, 1980
Date well drilling machine moved off of well JAN 17, 1980

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision. Materials used and information reported above are true to my best knowledge and belief.

[Signed] Richard J Beck Date JAN 18, 1980
(Drilling Machine Operator)

Drilling Machine Operator's License No. 1200

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

Name J W Beck Well Drilling (Type or print)
(Person, firm or corporation)

Address 24137 S Skyline Dr Conby Ore

[Signed] John W Beck (Water Well Contractor)

Contractor's License No. 449 Date 1-18-1980