

WATER SUPPLY WELL REPORT

(as required by ORS 537.765)

Instructions for completing this report are on the last page of this form

Mari 56548

(1) OWNER: Well Number: Name: Holden Wholesale Growers Address: 10374 Hazelgreen Rd. City: Silverton State: OR Zip: 97381

(2) TYPE OF WORK: [X] New Well [] Deepening [] Alteration (repair/recondition) [] Abandonment

(3) DRILL METHOD: [] Rotary Air [] Rotary Mud [X] Cable [] Auger [] Other

(4) PROPOSED USE: [] Domestic [] Community [] Industrial [X] Irrigation [] Thermal [] Injection [] Livestock [] Other

(5) BORE HOLE CONSTRUCTION: Special Construction approval [] Yes [X] No Depth of Completed Well 184 ft. Explosives used [] Yes [X] No Type Amount

Table with columns: HOLE Diameter, From, To, SEAL Material, From, To, Amount sacks or pounds. Rows include Bentonite and cement seals.

How was seal placed: Method [] A [] B [X] C [] D [] E Backfill placed from 195 ft. to 184 ft. Material CEMENT

(6) CASING/LINER: Casing: 10in. From +1' To 143' Gauge .250 Steel [X] Plastic [] Welded [X] Threaded [] Liner: 6in. 129' 144' .25 Steel [X] Plastic [] Welded [X] Threaded []

(7) PERFORATIONS/SCREENS: [X] Perforations Method Mills Knife [X] Screens Type v-slot Material 304SS

(8) WELL TESTS: Minimum testing time is 1 hour [X] Pump [] Bailer [] Air [] Flowing Artesian Yield gal/min 150 220 Drawdown 32.75' 45.91' Drill stem at 3hrs. 3hrs.

Temperature of Water 57° Depth Artesian Flow found Was a water analysis done? [] Yes [] No By whom Did any strata contain water not suitable for intended use? [] Too little [] Salty [] Muddy [] Odor [] Colored [] Other

(9) LOCATION OF WELL by legal description: County Marion Latitude Longitude Township 6S N or S. Range 1W E or W. of WM. Section 28 SE 1/4 NW 1/4 Tax lot 1300 Lot Block NW Subdivision Street Address of Well (or nearest address) 6822 Old Mt. Angel Hwy.

(10) STATIC WATER LEVEL: 42.08 ft. below land surface. Date 4/12/2002 Artesian pressure lb. per square inch. Date

(11) WATER BEARING ZONES: Table with columns: From, To, Estimated Flow Rate, SWL. Rows show 85' to 120' at 100gpm and 144' to 164' at 50gpm.

(12) WELL LOG: Table with columns: Material, From, To, SWL. Lists layers like topsoil, Brown clay, Blue/gray clay, etc. Includes a RECEIVED stamp dated MAY 16 2002.

Date started 1/7/2002 Completed 4/12/2002

(unbonded) Water Well Constructor Certification: I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Signature: Marc Mader WWC Number 749 Date 5-15-02

(bonded) Water Well Constructor Certification: I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. Signature: Michael Waldroop WWC Number 633 Date 5/15/2002