

MARI  
Mari  
57858

57858

STATE OF OREGON  
WATER SUPPLY WELL REPORT  
(as required by ORS 537.765)

WELL ID # L6843  
START CARD # 162566

(1) OWNER:

Well Number: \_\_\_\_\_  
Name: Mark Weissenfels - Bill Warner  
Address: 295 Lincoln St P.O. Box 255  
City: ML Angel State: OR Zip: 97362

(2) TYPE OF WORK:

New Well  Deepening  Alteration (repair/recondition)  Abandonment

(3) DRILL METHOD:

Rotary Air  Rotary Mud  Cable  Auger  
 Other: \_\_\_\_\_

(4) PROPOSED USE:

Domestic  Community  Industrial  Irrigation  
 Thermal  Injection  Livestock  Other \_\_\_\_\_

(5) BORE HOLE CONSTRUCTION:

Special Construction approval  Yes  No  
Depth of Completed Well 447  
Explosives Used  Yes  No Type \_\_\_\_\_ Amount \_\_\_\_\_

HOLE			SEAL			socks or pounds
Diameter	From	To	Material	From	To	
10	0	104	Cement	50	104	22 SKS
10	0	50	Bent	0	50	19 SKS
6"	104	447	—	—	—	—

How was seal placed: Method  A  B  C  D  E  
 Other Chips Installed Dry  
Backfill placed from \_\_\_\_\_ to \_\_\_\_\_ Material \_\_\_\_\_  
Gravel placed from \_\_\_\_\_ to \_\_\_\_\_ Size of gravel \_\_\_\_\_

(6) CASING/LINER:

Diameter	From	To	Gauge	Material			
				Steel	Plastic	Welded	Threaded
6	+1.5	104	250	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
LINER:							
4	-1	447	200	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>

Final location of Shoe(s): \_\_\_\_\_

(7) PERFORATIONS/SCREENS:

Perforations Method: Saw  
 Screen Type: \_\_\_\_\_ Material: PVC

From	To	Shot Size	No.	Diameter	Tele/pipe size	Casing	Liner
280	340	1/8x4	108			<input type="checkbox"/>	<input checked="" type="checkbox"/>
400	446	1/8x4	71			<input type="checkbox"/>	<input checked="" type="checkbox"/>

(8) WELL TESTS: Minimum testing time is 1 hour

Pump  Bailer  Air  Flowing Artesian

Yield gpm	Drawdown	Drill Stem at	Time
70		440	1 hr.
			2 hrs

Temperature of water 55 Depth Artesian Flow Found \_\_\_\_\_  
Was a water analysis done? \_\_\_\_\_ By whom: TDS 03  
Did any strata contain water not suitable for intended use? (explain) \_\_\_\_\_  
Depth of Strata: \_\_\_\_\_

(9) LOCATION OF WELL by legal description:

County: Marion Latitude: \_\_\_\_\_ Longitude: \_\_\_\_\_  
Township: 6S Range: 1E  
Section: 31 SE  $\frac{1}{4}$  SW  $\frac{1}{4}$   
Tax Lot: 1100 Lot: N/A Block: N/A Subdivision: N/A  
Street Address of Well (or nearest address) \_\_\_\_\_  
5374 Forrest Ridge Rd

(10) STATIC WATER LEVEL:

57 Ft. below land surface Date 12-10-03  
Artesian pressure \_\_\_\_\_ lb. per sq. in. Date \_\_\_\_\_

(11) WATER BEARING ZONES:

Depth at which water was first found 24

From	To	Est. Flow Rate	SWL
24	25	5	6
90	96	2	42
290	291	15	57
422	431	55	57

(12) WELL LOG:

Material	Ground Elevation:		SWL
	From	To	
Clay Med Brown	0	24	
Sandstone Med Gray	24	90	16
Sandstone Med Hard Brown	90	96	42
Sandstone Med Hard Gray	96	181	
Sandstone Med <u>Gray</u>	181	199	
Sandstone Hard Gray	199	221	
Sandstone Lava Dry <u>MIX</u>	221	229	
Sandstone Hard Brown	229	284	
Sandstone Med Gray	284	326	1120
Sandstone Med Brown	326	408	
Sandstone Fract Green Hard	408	412	
Sandstone Brown Med	412	431	
Sandstone Green Med	431	440	<u>H2O</u>
Sandstone Brown Med	440	447	

RECEIVED RECEIVED  
JAN 14 2004 FEB 17 2004  
WATER RESOURCES DEPT SALEM OREGON WATER RESOURCES DEPT SALEM OREGON

Date Started: 12-1-03 Completed: 12-10-03

(unbonded) Water Well Constructor Certification:  
I certify that the work performed on the construction, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.

Signed \_\_\_\_\_ WWC Number 723  
Date 12/12/03

(bonded) Water Well Constructor Certification:  
I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

Signed \_\_\_\_\_ WWC Number 723  
Date 12/12/03