

STATE OF OREGON WATER SUPPLY WELL REPORT

(as required by ORS 537.705)

Instructions for completing this report are on the last page of this form.

(WELL I.D.) = **L 69328**(START CARD) = **157920****(1) OWNER:** Well Number **1**Name **Don Fetter**Address **10162 Liberty Road South**City **Salem**State **OR**Zip **97306****(2) TYPE OF WORK**☒ New Well ☐ Deepening ☐ Alteration (repair/recondition) ☐ Abandonment**(3) DRILL METHOD:**☒ Rotary Air ☐ Rotary Mud ☐ Cable ☐ Auger☐ Other**(4) PROPOSED USE:**☒ Domestic ☐ Community ☐ Industrial ☐ Irrigation☐ Thermal ☐ Injection ☐ Livestock ☐ Other**(5) BORE HOLE CONSTRUCTION:**Special Construction approval ☐ Yes ☒ No Depth of Completed Well **180** ft.Explosives used ☐ Yes ☒ No Type _____ Amount _____

HOLE			SEAL			Sacks or pounds
Diameter	From	To	Material	From	To	
10	0	7	Hole Plug	0	7	4-50 lbs
10	7	100	Cement	7	100	20-94lbs
6	100	180				

How was seal placed: Method ☐ A ☐ B ☒ C ☐ D ☐ E☒ Other **Poured & Probed**

Backfill placed from _____ ft. to _____ ft. Material _____

Gravel placed from _____ ft. to _____ ft. Size of gravel _____

(6) CASING/LINER:

	Diameter	From	To	Gauge	Steel	Plastic	Welded	Threaded
Casing:	6	+1-1/2	100	.250	☒	☐	☒	☐
Liner:	4	0	180	.160	☐	☒	☒	☐

Final location of sheets: **100****(7) PERFORATIONS/SCREENS:**☒ Perforations Method **Saw Cut**☐ Screens

From	To	Slot size	Number	Diameter	Tele/pipe size	Casing	Liner
140	180	1/8x7	30	7		☐	☒

(8) WELL TESTS: Minimum testing time is 1 hour☐ Pump ☐ Bailor ☒ Air ☐ Flowing ☐ ArtesianYield gal/min **30+** Drawdown _____ Drill stem at **175** Time **1 hr.**Temperature of water **57** Depth Artesian Flow Found _____

Was a water analysis done? Yes By whom _____

Did any strata contain water not suitable for intended use? ☐ Too little☐ Salty ☐ Muddy ☐ Odor ☐ Colored ☐ Other _____

Depth of strata: _____

(9) LOCATION OF WELL by legal description:County **Marion** Latitude **44 48.488N** Longitude **123 03.353W**Township **9** S Range **3** W WMSection **9** 14 14Tax Lot **700** Lot _____ Block _____ Subdivision _____Street Address of Well (or nearest address) **10162 Liberty Road South****Salem, OR 97306****(10) STATIC WATER LEVEL:****60** ft. below land surface. Date **4/30/04**

Artesian pressure _____ lb. per square inch. Date _____

(11) WATER BEARING ZONES:Depth at which water was first found **120**

	From	To	Estimated Flow Rate	SWI
120	140	10+	60	
160	180	20	60	

(12) WELL LOG:

Ground Elevation _____

Material	From	To	SWI
Top Soil	0	2	
Clay Brown & Tan Silty	2	75	
Sandstone Gray Firm	75	120	
Sandstone Dark Gray Fractured w/Broken Seams	120	180	

REC

MAY 20 2004

WATER RESOURCES DEPT
SALEM, OREGONDate started **4/27/04**Completed **4/30/04****(unbonded) Water Well Constructor Certification:**

I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.

Signed *Don Fetter* WWC Number **1725** Date **5/5/04****(bonded) Water Well Constructor Certification:**

I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

Signed *Don Fetter* WWC Number **1725** Date **5/5/04**