

STATE OF OREGON
WATER SUPPLY WELL REPORT

(as required by ORS 537.765)

Instructions for completing this report are on the last page of this form.

(WELL I.D.) = L 639329

(START CARD) = 157922

(1) OWNER: Well Number 1
Name **Al Burkoff**
Address **32023 S Shadydell**
City **Molalla** State **OR** Zip **97308**

(2) TYPE OF WORK
☒ New Well ☐ Deepening ☐ Alteration (repair/recondition) ☐ Abandonment

(3) DRILL METHOD:
☒ Rotary Air ☐ Rotary Mud ☐ Cable ☐ Auger
☐ Other

(4) PROPOSED USE:
☒ Domestic ☐ Community ☐ Industrial ☐ Irrigation
☐ Thermal ☐ Injection ☐ Livestock ☐ Other

(5) BORE HOLE CONSTRUCTION:
Special Construction approval ☐ Yes ☒ No Depth of Completed Well **115** ft.
Explosives used ☐ Yes ☒ No Type Amount

HOLE			SEAL			
Diameter	From	To	Material	From	To	Sacks or pounds
10	0	19	Hole Plug	0	19	10-50lb
6	19	130				

How was seal placed: Method ☐ A ☐ B ☐ C ☐ D ☐ E
☒ Other **Poured & Probed**
Backfill placed from _____ ft. to _____ ft. Material _____
Gravel placed from _____ ft. to _____ ft. Size of gravel _____

(6) CASING/LINER:

Diameter	From	To	Gauge	Steel	Plastic	Welded	Threaded
Casing 6	+1-1/2	19	.250	☒	☐	☒	☐
Liner 4	0	115	.160	☐	☒	☒	☐

Final location of sheets: **19**

(7) PERFORATIONS/SCREENS:
☒ Perforations Method **Saw Cut**
☐ Screens Type Material
From To Slot Number Diameter Tele-pipe Casing Liner
85 115 1/8x7 30 7 size size ☒

(8) WELL TESTS: Minimum testing time is 1 hour

	Pump	Butler	☒ Air	Flowing
	Yield gal/min	Drawdown	Drill stem at	Artesian
	40		110	
				Time
				1 hr

Temperature of water **56** Depth Artesian Flow Found _____
Was a water analysis done? ☐ Yes By whom _____
Did any strata contain water not suitable for intended use? ☐ Too little
☐ Salty ☐ Muddy ☐ Odor ☐ Colored ☐ Other _____
Depth of strata: _____

(9) LOCATION OF WELL by legal description:
County **Marion** Latitude **45 00.791N** Longitude **122 41.750W**
Township **6** S Range **1** E WM
Section **33** 14 14
Tax Lot **700** Lot Block Subdivision
Street Address of Well (or nearest address) **5982 Towne Drive NE**
Silverton, OR 97381

(10) STATIC WATER LEVEL:
7 ft below land surface Date **5/5/04**
Artesian pressure lb. per square inch. Date

(11) WATER BEARING ZONES:
Depth at which water was first found **80**

From	To	Estimated Flow Rate	SWL
80	100	20	7
100	120	20	7

(12) WELL LOG:
Ground Elevation _____

Material	From	To	SWL
Top Soil	0	2	
Clay Brown Firm w/Boulders	2	12	
Sandstone Gray Firm	12	80	
Sandstone Gray Fractured & Broken	80	105	7
Sandstone Gray Heaving Broken & Caving	105	130	7

****Well Could Not Be Kept Open From
115 to 130 Due To Heavy Caving**

RECEIVED

MAY 20 2004

**WATER RESOURCES DEPT
SALEM, OREGON**

Date started **5/3/04** Completed **5/5/04**

(unbonded) Water Well Constructor Certification:

I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.

Signed *Tony L. Byrns* WWC Number **1725** Date **5/14/04**

(bonded) Water Well Constructor Certification:

I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

Signed *Tony L. Byrns* WWC Number **1725** Date **5/14/04**

ORIGINAL & FIRST COPY-WATER RESOURCES DEPARTMENT SECOND COPY-CONSTRUCTOR THIRD COPY-CUSTOMER

**RECEIVED
OVER THE COUNTER**