

Westerberg Drilling, Inc  
36728 S. Kropf Rd.  
Molalla, OR 97038

STATE OF OREGON  
WATER SUPPLY WELL REPORT  
(as required by ORS 537.765)

WELL I.D. # L 71446  
START CARD # 170226

Instructions for completing this report are on the last page of this form.

(1) LAND OWNER Well Number \_\_\_\_\_  
Name Paul Dupont  
Address 1112 Knights Bridge Rd.  
City Canby State OR Zip 97013

(2) TYPE OF WORK  
 New Well  Deepening  Alteration (repair/recondition)  Abandonment

(3) DRILL METHOD:  
 Rotary Air  Rotary Mud  Cable  Auger  
 Other \_\_\_\_\_

(4) PROPOSED USE:  
 Domestic  Community  Industrial  Irrigation  
 Thermal  Injection  Livestock  Other \_\_\_\_\_

(5) BORE HOLE CONSTRUCTION:  
Special Construction approval  Yes  No Depth of Completed Well 200 ft.  
Explosives used  Yes  No Type \_\_\_\_\_ Amount \_\_\_\_\_

HOLE		SEAL			
Diameter	From	To	Material	From	To
16"	0	135	Cement	25	135
10"	135	200	Bentonite	0	25

How was seal placed: Method  A  B  C  D  E  
 Other Bentonite placed dry  
Backfill placed from \_\_\_\_\_ ft. to \_\_\_\_\_ ft. Material \_\_\_\_\_  
Gravel placed from 135 ft. to 200 ft. Size of gravel 6x9

(6) CASING/LINER:

Diameter	From	To	Gauge	Steel	Plastic	Welded	Threaded
Casing: 10"	+1.5	154	.250	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
Liner: 6" riser	134'	155'	.250	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
6" tail	186'	200'	.250	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>

Drive Shoe used  Inside  Outside  None  
Final location of shoe(s) 154'

(7) PERFORATIONS/SCREENS:

Perforations Method \_\_\_\_\_  
 Screens Type V-wire Material Stainless

From	To	Slot size	Number	Diameter	Tele/pipe size	Casing	Liner
155	160	.065		6"	PS	<input type="checkbox"/>	<input type="checkbox"/>
160	186	.060		6"	PS	<input type="checkbox"/>	<input type="checkbox"/>

(8) WELL TESTS: Minimum testing time is 1 hour

Pump  Bailer  Air  Flowing Artesian

Yield gal/min	Drawdown	Drill stem at	Time
350	68'		4 hr.

Temperature of water 56° Depth Artesian Flow Found \_\_\_\_\_  
Was water tested?  Yes  No By whom No  
Did any strata contain water not suitable for intended use?  Too little  
 Salty  Murky  Odor  Colored  Other \_\_\_\_\_  
Depth of strata: \_\_\_\_\_

WATER RESOURCES DEPT  
SALEM, OREGON

(9) LOCATION OF WELL by legal description:  
County Marion Latitude \_\_\_\_\_ Longitude \_\_\_\_\_  
Township 4S N or S Range 1W E or W. WM.  
Section 18 SW 1/4 NW 1/4  
Tax Lot 1000 Lot \_\_\_\_\_ Block \_\_\_\_\_ Subdivision \_\_\_\_\_  
Street Address of Well (or nearest address) 21211 Olmstead Rd. NE  
Aurora, OR 97002

(10) STATIC WATER LEVEL:  
46 ft. below land surface. Date 12-8-04  
Artesian pressure \_\_\_\_\_ lb. per square inch Date \_\_\_\_\_

(11) WATER BEARING ZONES:

Depth at which water was first found 77'

From	To	Estimated Flow Rate	SWL
77'	106'	N/A	N/A
157'	184'	350 gpm	46'

(12) WELL LOG:

Ground Elevation \_\_\_\_\_

Material	From	To	SWL
Topsoil brown	0	2	
Clay brown	2	28	
Clay brown silty	28	38	
Clay blue	38	77	
Clay grey w/ silty sand	77	80	
Sand black silty fine	80	92	
Sand black cemntd fine	92	95	
Sand black fine w/ gravel med	95	99	
Sand black silty fine	99	106	
Clay blue silty	106	126	
Clay grey silty	126	136	
Clay grey sticky dense	136	157	
Sand black fine cemntd	157	160	
Gravel med cemented	160	170	
Gravel med w/ sandy clay grey	170	172	
Sand blk med loose w/ grav.	172	175	

continued on page 2

Date started 11-9-04 Completed 12-13-04

(unbonded) Water Well Constructor Certification:  
I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.  
Signed *Arnelma Sura* WWC Number 1768 Date 12-21-04

(bonded) Water Well Constructor Certification:  
I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.  
Signed *Stevan N. Stahle* WWC Number 688 Date 12-21-04

RECEIVED  
DEC 27 2004



36728 S. Kropf Rd., Molalla, OR 97038 • Phone: (503) 829-2526 FAX (503) 829-7514

Page 2

WELL ID# L 71446  
 OWNER: Paul Dupont  
 ADDRESS: 1112 Knights Bridge Rd.  
 CITY/STATE/ZIP: Canby, OR 97013

WELL ADDRESS: 21211 Olmstead Rd. NE Aurora, OR 97002  
 COUNTY Marion TOWNSHIP 4S RANGE 1W  
 SECTION 18 SW 1/4 NW 1/4 TAX LOT 1000

(12) WELL LOG INFO. CONT'D FROM PREVIOUS PAGE:

MATERIAL	FROM	TO	SWL
Gravel med w/ silty sand binder	175	182	
Gravel med w/ silty clay matrix wood	182	184	
Clay green brown wood dense	184	193	
Clay grey dense	193	200	

Westerberg Drilling, Inc.  
 36728 S. Kropf Rd.  
 Molalla, OR 97038

**RECEIVED**

DEC 27 2004

WATER RESOURCES DEPT  
 SALEM, OREGON