

Dairy Farm Ltd. Partnership
 C/O Marlin Rassmussen
 23231 River Rd. NE
 St. Paul, OR 97137

Well I.D.# L75903

Start Card # 163484

Marion County Township: 4S Range: 2W Sec: 4 SE1/4, NW1/4
 23231 River Rd. NE St.Paul, OR Tax Lot: 800

WELL LOG

Material	From	To	SWL
Topsoil	0	1	
Clay brown	1	29	
Clay silty brown	29	31	
Clay silty gray & fine sand	31	37	
Clay silty gray	37	45	
Clay silty dark gray & fine sand	45	84	
Clay green	84	103	
Clay green sandy	103	106	
Clay green silty	106	118	
Clay gray sticky	118	128	
Clay green sandy	128	137	
Clay green sandy, some gravel	137	141	
Clay blue & gray, sticky	141	149	
Clay green sticky	149	154	
Clay brown sticky	154	159	
Clay brown sandy	159	171	
Sand brown & silt	171	173	
Clay gray & brown, sticky	173	191	
Sand fine & silt	191	193	
Clay light brown & gray	193	206	
Sand & silt brown	206	209	
Clay light brown, sticky	209	213	
Clay gray & brown	213	218	
Clay gray & brown, sticky	218	235	
Clay sandy brown	235	238	
Clay gray & sand	238	259	66'
Gravel & clay gray, cemented	259	269	
Gravel & cemented clay w/seams of loose gravel	269	274	66'
Gravel & clay sandy gray	274	281	66'
Clay gray & brown sticky	281	302	
Clay dark gray	302	304	
Clay sandy dark gray	304	309	66'
Clay gray	309	350	

RECEIVED
 AUG 1 2 2005
 WATER RESOURCES DEPT
 SALEM, OREGON