

NOTICE TO WATER WELL CONTRACTOR
The original and first copy of this report
are to be filed with the

WATER RESOURCES DEPARTMENT
SALEM, OREGON 97310
within 30 days from the date
of well completion.

WATER WELL REPORT

STATE OF OREGON

(Please type or print)

(Do not write above this line)

RECEIVED

MAY 31 1978

Well No. 781W-13CC

State Permit No. G-8282

WATER RESOURCES DEPT

(1) OWNER:

Name Norman Queen
Address 10391 Porta 1 A ve.
Cupertino, California 95014

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐
If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary ☒ Driven ☐
Cable ☐ Jetted ☐
Dug ☐ Bored ☐

(4) PROPOSED USE (check):

Domestic ☒ Industrial ☐ Municipal ☐
Irrigation ☒ Test Well ☐ Other ☐

CASING INSTALLED:

8" Diam. from 1+ ft. to 61 ft. Gage .250
" Diam. from _____ ft. to _____ ft. Gage _____
" Diam. from _____ ft. to _____ ft. Gage _____

PERFORATIONS:

Perforated? ☐ Yes ☒ No.

Type of perforator used _____

Size of perforations in. by in.
_____ perforations from _____ ft. to _____ ft.
_____ perforations from _____ ft. to _____ ft.
_____ perforations from _____ ft. to _____ ft.

(7) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name _____
Type _____ Model No. _____
Diam. _____ Slot size _____ Set from _____ ft. to _____ ft.
Diam. _____ Slot size _____ Set from _____ ft. to _____ ft.

(8) WELL TESTS:

Drawdown is amount water level is lowered below static level

Was a pump test made? ☐ Yes ☒ No If yes, by whom?

Air-
Yield: 75 gal./min. with 57 ft. drawdown after 1 hr.
200 + " 145 " 2 "
300+ " 211 " 1 "
Pump test 300 gal./min. with _____ ft. drawdown after _____ hrs.

Artesian flow _____ g.p.m.

Temperature of water xx Depth artesian flow encountered _____ ft.

(9) CONSTRUCTION:

Well seal—Material used Cement
Well sealed from land surface to 61 ft.
Diameter of well bore to bottom of seal 12" to 18' & 10" to 61'
Diameter of well bore below seal 8 in.
Number of sacks of cement used in well seal 12 sacks
How was cement grout placed? Gravity pressure

Was a drive shoe used? ☐ Yes ☒ No Plugs _____ Size: location _____ ft.

Did any strata contain unusable water? ☐ Yes ☒ No

Type of water? _____ depth of strata _____

Method of sealing strata off _____

Was well gravel packed? ☐ Yes ☒ No Size of gravel: _____

Gravel placed from _____ ft. to _____ ft.

(10) LOCATION OF WELL:

County Marion Driller's well number _____
S.W. $\frac{1}{4}$ S.W. $\frac{1}{4}$ Section 13 T. 7 S. R. 1 W. W.M.
Bearing and distance from section or subdivision corner _____

(11) WATER LEVEL: Completed well.

Depth at which water was first found 145 ft.
Static level 88 ft. below land surface. Date 5/23/78
Artesian pressure _____ lbs. per square inch. Date _____

(12) WELL LOG:

Diameter of well below casing 8"

Depth drilled 302 ft. Depth of completed well 302 ft.

Formation: Describe color, texture, grain size and structure of materials; and show thickness and nature of each stratum and aquifer penetrated, with at least one entry for each change of formation. Report each change in position of Static Water Level and indicate principal water-bearing strata.

MATERIAL	From	To	SWL
Top soil- brn.-	0	1	
Clay-brn. & boulders-	01	3	
Sandstone-brn. & soft-	3	35	
Sandstone-grey-med.hd.-	35	58	
Sandstone- brn.-med.hd.-	58	100	
Claystone-grey-hd.-	100	120	
Sandstone-grey-hd.-	120	145	
Sandstone-grey-hd. & crevicy-	145	160 (W.B.)	
Sandstone-grey-hd.-	160	215	
Sandstone-grey-hd. & crevicy-	215	235 (W.B.)	
Sandstone-grey-hd.-	235	302	

Work started 5/17/78 19 Completed 5/22/78 19
Date well drilling machine moved off of well 5/23/78 19

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision. Materials used and information reported above are true to my best knowledge and belief.

[Signed] Maurice J. Stadel Date 5-24, 1978
(Drilling Machine Operator)

Drilling Machine Operator's License No. 1118

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

Name R. Stadel & Sons, Inc.
(Person, firm or corporation) (Type or print)

Address 11364 Evergn. Rd. N.E., Silvrtn. Or. 97381

[Signed] Paul R. Stadel
(Water Well Contractor)

Contractor's License No. 296 Date 5/25/78, 19____