

MARI 63534

R. Stadel & Sons Well & Pump Inc. 4385 Stadel Lane NE Silverton, OR 97381

STATE OF OREGON WATER SUPPLY WELL REPORT (as required by ORS 537.765)

WELL I.D. # L 101926

START CARD # 205940

Instructions for completing this report are on the last page of this form.

(1) LAND OWNER Well Number Name Bethel Park/Oregon Ministries Network Address PO Box 9178 City Salem State OR Zip 97305

(2) TYPE OF WORK [X] New Well [ ] Deepening [ ] Alteration (repair/recondition) [ ] Abandonment [ ] Conversion

(3) DRILL METHOD [X] Rotary Air [ ] Rotary Mud [X] Cable [ ] Auger [ ] Cable Mud [ ] Other

(4) PROPOSED USE [ ] Domestic [X] Community [ ] Industrial [ ] Irrigation [ ] Thermal [ ] Injection [ ] Livestock [ ] Other

(5) BORE HOLE CONSTRUCTION Special Construction: [ ] Yes [X] No Depth of Completed Well 340 ft. Explosives used: [ ] Yes [X] No Type Amount

Table with columns: BORE HOLE (Diameter, From, To, Material), SEAL (From, To, Sacks or Pounds). Rows include Bentonite and Cement.

How was seal placed: Method [ ] A [ ] B [X] C [ ] D [ ] E [X] Other Bentonite Poured & Probed Backfill placed from 163 ft. to 182 ft. Material Sand Gravel placed from ft. to ft. Size of gravel

(6) CASING/LINER Table with columns: Diameter, From, To, Gauge, Steel, Plastic, Welded, Threaded. Includes Double K-Packer liner.

Drive Shoe used [ ] Inside [X] Outside [ ] None Final location of shoe(s) 10" shoe cut off @ 340', 16" shoe cut off @ 182'

(7) PERFORATIONS/SCREENS [ ] Perforations Method [ ] Screens Type Material SS

Table with columns: From, To, Slot Size, Number, Diameter, Tele/pipe size, Casing, Liner. Lists perforation details.

(8) WELL TESTS: Minimum testing time is 1 hour [X] Pump [ ] Bailer [ ] Air [ ] Flowing Artesian

Table with columns: Yield gal/min, Drawdown, Drill stem at, Time. Shows 500 gal/min, 19' drawdown, 8 hr time.

Temperature of water 55 Depth Artesian Flow Found Was a water analysis done? [ ] Yes By whom Did any strata contain water not suitable for intended use? [ ] Too little [ ] Salty [ ] Muddy [ ] Odor [ ] Colored [ ] Other Depth of strata:

(9) LOCATION OF WELL (legal description) County Marion Tax Lot 300 Lot Township 6 S Range 2 W WM Section 17 NW 1/4 NE 1/4

Lat Long Street Address of Well (or nearest address) 9255 Portland Rd. Salem, OR 97305

(10) STATIC WATER LEVEL 33 ft. below land surface. Date 02-22-2011 Artesian pressure lb. per square inch Date

(11) WATER BEARING ZONES Table with columns: From, To, Estimated Flow Rate, SWL. Shows zones from 80' to 297'.

(12) WELL LOG Table with columns: Material, From, To, SWL. Lists soil types and elevations.

Date Started 12/14/2010 Completed 02/24/2011

(unbonded) Water Well Constructor Certification I certify that the work I performed on the construction, deepening, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards.

WWC Number 1358 Date 02/25/2011


Signed [Signature]

(bonded) Water Well Constructor Certification I accept responsibility for the construction, deepening, alteration, or abandonment work performed on this well during the construction dates reported above.

WWC Number 688 Date 02/28/2011

Signed [Signature]

RECEIVED MAR 02 2011



4385 Stadel Lane N.E. • Silverton, Oregon 97381  
Phone: 503.873.5245 • Fax: 503.873.2275  
Email: rstadeli.sons@verizon.net

WELL ID#	OWNER/BUSINESS NAME	MAILING ADDRESS	CITY/STATE/ZIP
101926	Bethel Park/Oregon Ministerial Association	PO box 9178	Salem, OR 97305

WELL ADDRESS	COUNTY	TOWNSHIP	RANGE	SECTION	1/4	1/4	TAX LOT
9255 Portland Rd., Salem, OR 97305	Marion	6S	2W	17	NW	NE	300

(12) WELL LOG INFO. CONTINUED FROM PREVIOUS PAGE:

MATERIAL	FROM	TO	SWL
Larger & Looser - More Water	234	252	
Cemented - Less Water	252	254	
Sandy & Gravel Brown Cemented	254	293	
Clay Grey	293	297	
Sand Grey Coarse	297	309	
Sand Grey w/Gravel	309	335	
Clay Medium	335	338	
Silt Grey Fine	338	340	

**RECEIVED**  
MAR 02 2011  
WATER RESOURCES DEPT  
SALEM, OREGON