

NOTICE TO WATER WELL CONTRACTOR

The original and first copy
of this report are to be
filed with the

STATE ENGINEER, SALEM, OREGON 97310

within 30 days from the date
of well completion.

RECEIVED
JAN 6 1970

STATE OF OREGON

(Please type or print)

STATE ENGINEER
SALEM, OREGON

write above this line)

State Well No.

State Permit No.

(1) OWNER:

Name FRANK KOCHAddress 12495 SUNNYVIEW RD., SALEM, ORE.

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐

If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary ☐ Driven ☐
Cable ☒ Jetted ☐
Dug ☐ Bored ☐

(4) PROPOSED USE (check):

Domestic ☒ Industrial ☐ Municipal ☐
Irrigation ☐ Test Well ☐ Other ☒

(5) CASING INSTALLED:

6" Diam. from 0 ft. to 39 ft. Gage 250

" Diam. from ft. to ft. Gage

" Diam. from ft. to ft. Gage

(6) PERFORATIONS:

Perforated? ☐ Yes ☒ No.

Type of perforator used

Size of perforations in. by in.

perforations from ft. to ft.

perforations from ft. to ft.

perforations from ft. to ft.

perforations from ft. to ft.

perforations from ft. to ft.

(7) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name

Type Model No.

Diam. Slot size Set from ft. to ft.

Diam. Slot size Set from ft. to ft.

(8) WATER LEVEL: Completed well.

Static level 117 ft. below land surface Date 11/24/69

Artesian pressure lbs. per square inch Date

(9) WELL TESTS:

Drawdown is amount water level is lowered below static level

Was a pump test made? ☐ Yes ☒ No If yes, by whom?

Yield: gal./min. with ft. drawdown after hrs.

" " " "

" " " "

Bailer test 20 gal./min. with 76 ft. drawdown after 2 hrs.

Artesian flow g.p.m. Date

Temperature of water Was a chemical analysis made? ☐ Yes ☒ No(10) CONSTRUCTION Annular space-crushed rock, bentonite, cement.Well seal—Material used Casing cemented in rock.

Depth of seal 39 ft.

Diameter of well bore to bottom of seal 10 in.

Were any loose strata cemented off? ☐ Yes ☒ No DepthWas a drive shoe used? ☒ Yes ☐ NoDid any strata contain unusable water? ☐ Yes ☒ No

Type of water? depth of strata

Method of sealing strata off

Was well gravel packed? ☐ Yes ☒ No Size of gravel:

Gravel placed from ft. to ft.

(11) LOCATION OF WELL:

County MARION

Driller's well number

NW 1/4 SW 1/4 Section 22 T. 7S R. 1 W W.M.

Bearing and distance from section or subdivision corner

1400' N & 80' E SW Cor. Sec. 22

(12) WELL LOG:

Diameter of well below casing 6"

Depth drilled 213 ft. Depth of completed well 213 ft.

Formation: Describe color, texture, grain size and structure of materials;
and show thickness and nature of each stratum and aquifer penetrated,
with at least one entry for each change of formation. Report each change
in position of Static Water Level as drilling proceeds. Note drilling rates.

MATERIAL	From	To	SWL
Surface soil	0	3	
Clay red	3	10	
Boulders-basaltic	10	18	
Lava-decomposed basalt	18	31	
Lava-decomposed	31	37	
Basalt-gray, very hard	37	96	
Basalt-black	96	102	
Basalt-gray, very hard	102	189	113
Basalt-black	189	211	
Basalt-gray, very hard	211	213	117

Aquifers at 158

176

189

211

Work started 11/7/69 19 Completed 11/24/69 19

Date well drilling machine moved off of well 11/25/69 19

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision. Materials used and information reported above are true to my best knowledge and belief.

[Signed] Howard Ruffield Date 10 Dec., 1969
(Drilling Machine Operator)

Drilling Machine Operator's License No. 46

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

NAME DUFFIELD BROS.

(Person, firm or corporation)

(Type or print)

Address 4123 BLUFF AVE S E, SALEM, ORE.

[Signed] Howard Ruffield
(Water Well Contractor)

Contractor's License No. 15 Date 10 Dec., 1969