

STATE OF OREGON
WATER SUPPLY WELL REPORT
(as required by ORS 537.765)

MARI 64801
Westenberg Drilling, Inc.
36728 S. Kropf Rd.
Molalla, OR 97038

WELL I.D. # L **108271**

START CARD # **209491**

Instructions for completing this report are on the last page of this form.

(1) LAND OWNER Well Number _____
Name **Oak Lane Farms**
Address **7882 Jordan St. SE**
City **Salem** State **OR** Zip **97317**

(2) TYPE OF WORK ☐ New Well
☐ Deepening ☒ Alteration (repair/recondition) ☐ Abandonment ☐ Conversion

(3) DRILL METHOD
☐ Rotary Air ☐ Rotary Mud ☒ Cable ☐ Auger ☐ Cable Mud
☐ Other _____

(4) PROPOSED USE
☐ Domestic ☐ Community ☐ Industrial ☒ Irrigation
☐ Thermal ☐ Injection ☐ Livestock ☐ Other _____

(5) BORE HOLE CONSTRUCTION Special Construction: ☐ Yes ☒ No
Depth of Completed Well **795** ft.
Explosives used: ☐ Yes ☒ No Type _____ Amount _____

BORE HOLE				SEAL			
Diameter	From	To	Material	From	To	Sacks or Pounds	
12	0	385	MARI8602				
10	385	795	MARI8603				
no	drilling	done					

How was seal placed: Method ☐ A ☐ B ☐ C ☐ D ☐ E
☒ Other **original MARI8602**

Backfill placed from _____ ft. to _____ ft. Material _____
Gravel placed from _____ ft. to _____ ft. Size of gravel _____

(6) CASING/LINER

Casing:	Diameter	From	To	Gauge	Steel	Plastic	Welded	Threaded
	MARI	8602			☐	☐	☐	☐
					☐	☐	☐	☐
					☐	☐	☐	☐
Liner:	liner	welded to 12"	casing		☐	☐	☐	☐
	above	grnd			☐	☐	☐	☐
	8	+1	442'7"	.250	☒	☐	☒	☐

Drive Shoe used ☐ Inside ☒ Outside ☐ None

Final location of shoe(s) **442'7"**

(7) PERFORATIONS/SCREENS
☒ Perforations Method **swift factory slotted**
☐ Screens Type _____ Material _____

From	To	Slot Size	Number	Diameter	Tele/pipe size	Casing	Liner
242	442	3/16 x 3	3040			☐	☒
						☐	☐
						☐	☐
						☐	☐

(8) WELL TESTS: Minimum testing time is 1 hour

☒ Pump ☐ Bailer ☐ Air ☐ Flowing Artesian

Yield gal/min **515** Drawdown **4.75 ft** Drill stem at **8 hour** Time

Temperature of water **56** Depth Artesian Flow Found _____

Was a water analysis done? ☐ Yes By whom _____

Did any strata contain water not suitable for intended use? ☐ Too little

☐ Salty ☐ Muddy ☐ Odor ☐ Colored ☐ Other _____

Depth of strata: _____

(9) LOCATION OF WELL (legal description)

County **Marion**
Tax Lot **100** Lot _____
Township **8** S Range **1** W WM
Section **4** NW 1/4 SW 1/4

Lat _____ " or _____ (degrees or decimal)
Long _____ " or _____ (degrees or decimal)

Street Address of Well (or nearest address) _____

11555 Waldo Hills Drive

(10) STATIC WATER LEVEL

242.5 ft. below land surface. Date **6-6-13**

_____ ft. below land surface. Date _____

Artesian pressure _____ lb. per square inch Date _____

(11) WATER BEARING ZONES

Depth at which water was first found **original**

From	To	Estimated Flow Rate	SWL
MARI8602			
MARI8603			

(12) WELL LOG

Ground Elevation _____

Material	From	To	SWL
No drilling.			
See MARI 8602 & 8603 for original well construction.			
We installed a liner, cleaned out well to bottom & test pumped.			

RECEIVED BY OWRD

JUN 18 2013

SALEM, OR

Date Started **5-14-13** Completed **6-6-13**

(unbonded) Water Well Constructor Certification

I certify that the work I performed on the construction, deepening, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.

WWC Number _____ Date _____

Signed _____

(bonded) Water Well Constructor Certification

I accept responsibility for the construction, deepening, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

WWC Number **688** Date **6-14-13**

Signed _____