

JAN REC SUBDIVISION MARI 6707 #3 WELL

RECEIVED MAY 10 1963 WATER WELL REPORT STATE ENGINEER STATE OF OREGON (Please type or print) SALEM, OREGON G3388

NOTICE TO WATER WELL CONTRACTOR The original and first copy of this report are to be filed with the STATE ENGINEER, SALEM 10, OREGON within 30 days from the date of well completion.

State Well No. 7/2W-8 GR(2) State Permit No.

(1) OWNER: Name BERNARD STEWART Address 4374-41ST AVE. N.E. SALEM ORE

(2) LOCATION OF WELL: County MARION Driller's well number 7 T. 7S R. 2W.W.M. Bearing and distance from section or subdivision corner

(3) TYPE OF WORK (check): Well [X] Deepening [ ] Reconditioning [ ] Abandon [ ]

(4) PROPOSED USE (check): Domestic [X] Industrial [ ] Municipal [X] Irrigation [ ] Test Well [ ] Other [ ] (5) TYPE OF WELL: Rotary [ ] Driven [ ] Cable [X] Jetted [ ] Dug [ ] Bored [ ]

(6) CASING INSTALLED: 12" Diam. from 0 ft. to 223 ft. Gage 412"

(7) PERFORATIONS: Perforated? [X] Yes [ ] No Type of perforator used Size of perforations 3/8 in. by 3" in. 142 perforations from 97 ft. to 104 ft. 156 perforations from 118 ft. to 128 ft. 540 perforations from 142 ft. to 192 ft. 80 perforations from 198 ft. to 213 ft.

(8) SCREENS: Well screen installed? [ ] Yes [X] No Manufacturer's Name Model No. Slot size Set from ft. to ft. Diam. Slot size Set from ft. to ft.

(9) CONSTRUCTION: Well seal-Material used in seal BENTONITE Depth of seal 412 ft. Was a packer used? yes Diameter of well bore to bottom of seal 16" in. Were any loose strata cemented off? [ ] Yes [X] No Depth Was a drive shoe used? [X] Yes [ ] No Was well gravel packed? [ ] Yes [X] No Size of gravel: Gravel placed from ft. to ft. Did any strata contain unusable water? [X] Yes [ ] No Type of water? SANDY Depth of strata 62'6" TO 85' Method of sealing strata off CASED

(10) WATER LEVELS: Static level 14' ft. below land surface Date 5-3-63 Artesian pressure lbs. per square inch Date

(11) WELL TESTS: Drawdown is amount water level is lowered below static level. Was a pump test made? [X] Yes [ ] No If yes, by whom? STETTLER SUPPLY Yield: 500 gal./min. with 52 ft. drawdown after 1 hrs. 600 " 57 " 1 " 900 " 71 " 1 1/2 "

(12) WELL LOG: Diameter of well below casing 12" Depth drilled 223 ft. Depth of completed well 223 ft. Formation: Describe by color, character, size of material and structure, and show thickness of aquifers and the kind and nature of the material in each stratum penetrated, with at least one entry for each change of formation.

Table with columns MATERIAL, FROM, TO. Rows include TOPSOIL, CLAY YELLOW COLOR, CLAY BLUE COLOR, CONGLOMERATE 2", CLAY YELLOW COLOR, CLAY + SAND BLUE COLOR, CLAY + SAND BROWN COLOR, CONGLOMERATE 2", GRAVEL 2" - WATER BEARING, CLAY - SANDY - YELLOW, CONGLOMERATE 3", GRAVEL - W. BEARING 1", CONGLOMERATE - 2", CLAY YELLOW COLOR, CLAY BLUE COLOR, CONGLOMERATE 3", GRAVEL W. BEARING 1", CONGLOMERATE 3", GRAVEL 2" - W. BEARING, CONGLOMERATE 3", CLAY YELLOW COLOR, CONGLOMERATE W. BEARING, CONGLOMERATE DR. 3"

Work started 4-12 1963. Completed 5-3 1963 Date well drilling machine moved off of well 5-3 1963

(13) PUMP: Manufacturer's Name BERNLEY Type: TURBINE H.P. 40

Water Well Contractor's Certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. NAME J. A. SPEED & SONS (Person, firm or corporation) (Type or print) Address 3910 SIVERTON RD. N.E. SALEM ORE. Drilling Machine Operator's License No. 187 [Signed] J.A. Speed (Water Well Contractor) Contractor's License No. 6 Date 5-6-63, 1963

MARI 6707

For Official Use Only:

Received Date:

County Well Log ID #

Well Identification Tag #

Mari 6707

50383

WELL IDENTIFICATION APPLICATION FORM

BUYER/CURRENT WELL OWNER:

Name: Jim West, Water Superintendent, City of Salem Public Works
Mailing Address: 1410 20th Street SE, Building No. 2
City: Salem State: OR Zip: 97302 Phone: (503) 588-6063

NOTE: Well Identification Tag will be sent to the above address unless otherwise specified.

WELL LOCATION:

Latitude Longitude

County: Owner's Well Number (1st or 2nd, etc) JANREE #2
Township: 7 N or S Range: 2 E or W Section 06DD 1/4 SE 1/4 SE

Tax Lot Number: 8100 Type of Well: water supply MUNIC monitoring

Address of Well (if different from above): 4500-45th AVENUE, SALEM, OR

Does this well have a formal water right associated with it? Yes: X No:

If Yes: Application #: 63388, 64222, 69224 Permit #: 6-3183, 6841, 8338 Certificate #:

WELL INFORMATION: ( do not complete remainder of application if well log is attached)

Start Card Number: Approx. Construction Date: MARI-6707

Well Constructor:

Name of Land Owner at Time of Construction:

Well Depth (in feet): Static Water Level (in feet):

Diameter of Exposed Well Casing (in inches):

Please Return Completed Form to: Well Identification Program Oregon Water Resources Department 158 12th Street NE Salem, OR 97301-4172

RECEIVED

MAY 21 2001

WATER RESOURCES DEPT. SALEM, OREGON