

NOTICE TO WATER WELL CONTRACTOR

The original and first copy of this report are to be filed with the

STATE ENGINEER, SALEM, OREGON 97310
within 30 days from the date of well completion

WATER WELL REPORT

STATE OF OREGON

(Please type or print)

(Do not write above this line)

State Well No. 7/2w-15 G

State Permit No. G-4941
G-4289

(1) OWNER:

Name E.V. HAMMER
Address 7010 LARDON RD. N.E. SALEM, ORE.

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐
If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary ☐ Driven ☐
Cable ☒ Jetted ☐
Dug ☐ Bored ☐

(4) PROPOSED USE (check):

Domestic ☐ Industrial ☐ Municipal ☐
Irrigation ☒ Test Well ☐ Other ☐

CASING INSTALLED:

Threaded ☐ Welded ☒
8" Diam. from 0 ft. to 159 ft. Gage 2
" Diam. from ft. to ft. Gage
" Diam. from ft. to ft. Gage

PERFORATIONS:

Perforated? ☒ Yes ☐ No.

Type of perforator used HILLS
Size of perforations 5/16 in. by 2 1/2 in.
776 perforations from 73' ft. to 157 ft.
perforations from ft. to ft.
perforations from ft. to ft.
perforations from ft. to ft.
perforations from ft. to ft.

(7) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name
Type Model No.
Diam. Slot size Set from ft. to ft.
Diam. Slot size Set from ft. to ft.

(8) WATER LEVEL: Completed well.

Static level 40' 3" ft. below land surface Date 1-8-67
Pneumatic pressure lbs. per square inch Date

(9) WELL TESTS:

Drawdown is amount water level is lowered below static level

Was a pump test made? ☒ Yes ☐ No If yes, by whom? SPENTLER SUPPLY
Id: 330 gal./min. with 34 ft. drawdown after 1/2 hrs.
500 " 48 " 1/2 "
" 600 " 71 " 1/2 "
Ball test 800 gal./min. with 80 ft. drawdown after 1/2 hrs.
Artesian flow g.p.m. Date
Temperature of water 51° Was a chemical analysis made? ☐ Yes ☒ No

(10) CONSTRUCTION:

Well seal—Material used BENTONITE
Depth of seal 61' ft.
Diameter of well bore to bottom of seal 12" in.
Were any loose strata cemented off? ☐ Yes ☒ No Depth
Was a drive shoe used? ☒ Yes ☐ No
Did any strata contain unusable water? ☒ Yes ☐ No
Type of water SANDY-MUDDY depth of strata 54'-61'
Method of sealing strata off CHASED
Was well gravel packed? ☐ Yes ☒ No Size of gravel:
Gravel placed from ft. to ft.

(11) LOCATION OF WELL:

County MARION Driller's well number
1/4 1/4 Section 15 T. 75 R. 2W W.M.
Bearing and distance from section or subdivision corner

(12) WELL LOG:

Diameter of well below casing 8"

Depth drilled 159' ft. Depth of completed well 159' ft.

Formation: Describe color, texture, grain size and structure of materials; and show thickness and nature of each stratum and aquifer penetrated, with at least one entry for each change of formation. Report each change in position of Static Water Level as drilling proceeds. Note drilling rates.

MATERIAL	From	To	SWL
TOPSOIL	0	3	
CLAY YELLOW COLOR	3	54	
SAND BROWN-FINE GRAIN	54	61	
CONGLOMERATE	61	94	
CLAY YELLOW COLOR	94	97	
CONGLOMERATE - W.B.	97	138	
SAND BROWN MED TO COARSE	138	139	
CONGLOMERATE W.B.	139	148	
GRAVEL 2 1/2"	148	150	
CONGLOMERATE	150	159	

Work started 12-28-1967 Completed 1-8-1968

Date well drilling machine moved off of well 1-8-1968

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision. Materials used and information reported above are true to my best knowledge and belief.

[Signed] R.A. Sneed Date 1-8-1968
(Drilling Machine Operator)

Drilling Machine Operator's License No. 187

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

NAME J.A. SNEED & SONS
(Person, firm or corporation) (Type or print)

Address 3910 SILVERTON RD. SALEM, ORE. 97302

[Signed] R.A. Sneed
(Water Well Contractor)

Contractor's License No. 6 Date 1-28-1968