

Lower seal placed from 365-522ft to prevent co-mingling of water. Then all sections of 8" casing inside 12" casing perforated. Cement pumped in & pressure grouted to ground level. Cement inside 8" settled to 5ft and 16ft inside 12". Both casings cut off 3.5ft below ground level. Bentonite poured between 8" & 12" casings to cut off depth. 8" casing topped with bentonite. 4" gravel tube cut off 3.5ft below ground & cleaned out 1 ft of gravel, filled w/bentonite.

WATER SUPPLY WELL REPORT - Map with location identified must be attached and shall include an approximate scale and north arrow

MARI 71900

11/28/2025

Map of Hole

STATE OF OREGON WELL LOCATION MAP

This map is supplemental to the WATER SUPPLY WELL REPORT

Oregon Water Resources Department

725 Summer St NE, Salem OR 97301
(503)986-0900



LOCATION OF WELL

Latitude: 45.08305843 Datum: WGS84

Longitude: -122.77443378

Township/Range/Section/Quarter-Quarter Section:
WM6.00S1.00W2NENW

Address of Well:

14038 DOMINIC RD MT ANGEL OR 97362

Startcard: 1080113

Printed: November 22, 2025

DISCLAIMER: This map is intended to represent the approximate location the well. It is not intended to be construed as survey accurate in any manner.

Provided by well constructor

