

STATE OF OREGON
WATER SUPPLY WELL REPORT

MARI 71941

WELL I.D. LABEL# L

Page 1 of 4

(as required by ORS 537.545 & 537.765 and OAR 690-205-0210)

12/10/2025

START CARD #
ORIGINAL LOG #

141631

1080175

(1) LAND OWNER

Owner Well I.D.

First Name JOHN

Last Name CATTERSON

Company

Address 1055 S PACIFIC HWY

City WOODBURN

State OR

Zip 970771

(2) TYPE OF WORK

☒ New Well ☐ Deepening ☐ Conversion

☐ Alteration (complete 2a & 10) ☐ Abandonment (complete 5a)

(2a) PRE-ALTERATION

Casing: Dia + From To Gauge Stl Plstc Wld Thrld
Material From To Amt sacks/lbs
Seal: Material From To Amt sacks/lbs

(3) DRILL METHOD

☐ Rotary Air ☐ Rotary Mud ☒ Cable ☐ Auger ☐ Cable Mud
☐ Reverse Rotary ☐ Other

(4) PROPOSED USE

☒ Domestic ☐ Irrigation ☐ Community
☐ Industrial/ Commercial ☐ Livestock ☐ Dewatering
☐ Thermal ☐ Injection ☐ Other

(5) BORE HOLE CONSTRUCTION

Special Standard ☐ (Attach copy)

Depth of Completed Well 130.33 ft.

BORE HOLE				SEAL			
Dia	From	To	Material	From	To	Amt	sacks/lbs
10	0	36	Bentonite Chips	0	36	18	S
6	36	130.33			Calculated	18	
					Calculated		

Seal placement method: ☐ A ☐ B ☐ C ☐ D ☐ E ☒ Other: OAR 690-210-0340

Backfill placed from ft. to ft. Material

Filter pack from ft. to ft. Material Size

Explosives used: ☐ Type Amount

Seal Placement Begin Date 10/23/2025 Begin Time 12 15

(5a) ABANDONMENT USING UNHYDRATED BENTONITE

Proposed Amount Actual Amount

(6) CASING/LINER

C/L	Dia	+	From	To	Gauge	Mat. Type	Wld	Thrd	Shoe	Shoe Location
C	6	☒	2	118.08	0.250	ST	☒		OUT.	118.08
C	5		115	118.66	0.188	ST	☒			
C	5		128.8	130.33	0.188	ST	☒			

Temp casing ☐ Yes Dia From + To

(7) PERFORATIONS/SCREENS

Perforations Method

Screens Type v wire Material stainless steel

Perf/ Screen	Casing/ Liner	Screen Dia	From	To	Scrm/slot width	Slot length	# of slots	Tele/ Pipe size
Screen	Casing	5	118.66	128.8	.015			Telescope

(8) WELL TESTS: Minimum testing time is 1 hour

Type of Test	Yield (gal/min)	Drawdown	Drill Stem/ Pump Depth	Duration (hr)
Air	125		128	1

Temperature 54 °F Lab analysis ☐ Yes By

Water quality concerns? ☐ Yes (describe below) TDS amount 82 ppm
From To Description Amount Units

(9) LOCATION OF WELL (legal description)

County MARION Twp 5.00 S N/S Range 1.00 W E/W WM

Sec 19 SW 1/4 of the NW 1/4 Tax Lot 2000

Tax Map Number Lot

Lat ° ' " or 45.12438242 DMS or DD

Long ° ' " or -122.86330155 DMS or DD

☐ Street address of well ☒ Nearest address

NEAREST ADDRESS IS ACROSS THE STREET, 1200 BELLE PASSI RD, WOODBURN

(10) STATIC WATER LEVEL

	Date	SWL (psi)	+	SWL (ft)
Existing Well / Pre-Alteration				
Completed Well	11/11/2025			21
Flowing Artesian?	☐			
Dry Hole?	☐			

WATER BEARING ZONES

Depth water was first found 69.00

SWL Date From To Est Flow SWL (psi) + SWL (ft)

10/24/2025	69	130	100		21

(11) WELL LOG

Ground Elevation 183.78 FT

Material	From	To
brown clay medium	0	31
grey clay medium hard	31	42
dark grey silt medium	42	58
dark grey silt sandy soft	58	69
fine black sand and grey silt	69	79
black sand fine	79	81
black sand medium heaves	81	91
black sand medium and grey clay	91	92
black sand medium heaves	92	112
black sand and some gravel	112	114
fine black sand and grey clay	114	117
black sand and gravel heaves	117	124
black sand and gravel 70% gravel	124	130.33

Construction

Begin Date 10/22/2025 Begin Time 13 30 End Date 11/11/2025

(unbonded) Water Well Constructor Certification

I certify that the work I performed on the construction, deepening, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.

License Number 2041 Date 11/30/2025

Signed TRAVIS RUSH (E-filed)

(bonded) Water Well Constructor Certification

I accept responsibility for the construction, deepening, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

License Number 783 Date 12/10/2025

Signed IVAN GROSSEN (E-filed)

Drilling Company: grossen well drilling

ORIGINAL - WATER RESOURCES DEPARTMENT

THIS REPORT MUST BE SUBMITTED TO THE WATER RESOURCES DEPARTMENT WITHIN 30 DAYS OF COMPLETION OF WORK Form Version:

New exempt use wells must be submitted with a map and recording fee.

WATER SUPPLY WELL REPORT - Map with location identified must be attached and shall include an approximate scale and north arrow

MARI 71941

12/10/2025

Map of Hole

STATE OF OREGON WELL LOCATION MAP

This map is supplemental to the WATER SUPPLY WELL REPORT

Oregon Water Resources Department

725 Summer St NE, Salem OR 97301
(503)986-0900



LOCATION OF WELL

Latitude: 45.12438242 Datum: WGS84

Longitude: -122.86330155

Township/Range/Section/Quarter-Quarter Section:

WM5.00S1.00W19SWNW

Address of Well:

NEAREST ADDRESS IS ACROSS THE STREET, 1200 BELLE PASS RD, WOODBURN

Well Label: 141631

Printed: December 10, 2025

DISCLAIMER: This map is intended to represent the approximate location the well. It is not intended to be construed as survey accurate in any manner.

Provided by well constructor



12/10/2025

Map of Hole

