

STATE OF OREGON WATER SUPPLY WELL REPORT

MARI 72110

WELL I.D. LABEL# L 158762 START CARD # 1081231 ORIGINAL LOG # MARION 4050

4/24/2026

(as required by ORS 537.545 & 537.765 and OAR 690-205-0210)

(1) LAND OWNER Owner Well I.D. First Name ROBERT Last Name GABRIEL Company Address 8474 HAZELGREEN RD City SILVERTON State OR Zip 97381

(2) TYPE OF WORK New Well Deepening Conversion Alteration (complete 2a & 10) Abandonment (complete 5a)

(2a) PRE-ALTERATION Casing: Dia 10 From 1 To 150 Gauge .279 Stl Plstc Wld Thrd Seal: Material From To Amt sacks/lbs

(3) DRILL METHOD Rotary Air Rotary Mud Cable Auger Reverse Rotary Other

(4) PROPOSED USE Domestic Irrigation Community Industrial/ Commercial Livestock Dewatering Thermal Injection Other

(5) BORE HOLE CONSTRUCTION Special Standard (Attach copy) Depth of Completed Well 299.00 ft.

Table with columns: Dia, From, To, Material, SEAL, Amt, lbs. Rows include Cement and Calculated values.

Seal placement method: A B C D E Other Backfill placed from 175 ft. to 299 ft. Material CSS Size 6/9 Explosives used: Type Amount Seal Placement Begin Date 2/11/2026 Begin Time 14:00

(5a) ABANDONMENT USING UNHYDRATED BENTONITE Proposed Amount Actual Amount

(6) CASING/LINER Table with columns: C/L, Dia, From, To, Gauge, Mat. Type, Wld, Thrd, Shoe, Location. Rows include C, L, L casing types.

Temp casing Yes Dia From To

(7) PERFORATIONS/SCREENS Perforations Method Screens Type V-Wire Material Stainless Steel Perf/ Casing/ Screen Dia From To Scrn/slot width length slots # of Tele/ Pipe size

(8) WELL TESTS: Minimum testing time is 1 hour Table with columns: Type of Test, Yield (gal/min), Drawdown, Drill Stem/ Pump Depth, Duration (hr). Rows include Air and Pump tests.

Temperature 54 °F Lab analysis Yes By Water quality concerns? Yes (describe below) TDS amount 128 ppm From To Description Amount Units

(9) LOCATION OF WELL (legal description) County MARION Twp 6.00 S N/S Range 2.00 W E/W WM Sec 15 SE 1/4 of the NE 1/4 Tax Lot 800 Tax Map Number Lot Lat Long Street address of well 7324 SEQUOIA ST NE, SALEM, OR 97305

(10) STATIC WATER LEVEL Date SWL(psi) + SWL(ft) Existing Well / Pre-Alteration 2/9/2026 27.8 Completed Well 3/25/2026 27.8 Flowing Artesian? Dry Hole?

WATER BEARING ZONES Depth water was first found 154.00 SWL Date From To Est Flow SWL(psi) + SWL(ft) 3/25/2026 154 295 600 27.8

(11) WELL LOG Ground Elevation 169.43 FT Material From To MARI 4050 Gravel 0 154 Clay Grey 155 158 Packed Silt Dirty Grey 158 163 Cemented Gravel Dirty 163 170 Gravel Slightly Cemented with Grey Sand 170 178 Clay with Gravel 178 183 Cemented Gravel with Sand 183 200 Cemented Gravel Large with Brown Sand 200 218 Cemented Sand with Gravel Brown 218 224 Clay Brown 224 227 Cemented Gravel Large 227 264 Clay Grey with Some gravel 264 270 Sand & Gravel Grey 270 295 Clay Blue with Sand Streaks 295 299

Construction Begin Date 2/9/2026 Begin Time 09:00 End Date 3/25/2026

(unbonded) Water Well Constructor Certification I certify that the work I performed on the construction, deepening, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.

License Number 1358 Date 4/7/2026 Signed BYRON STADELI (E-filed)

(bonded) Water Well Constructor Certification I accept responsibility for the construction, deepening, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

License Number 1487 Date 4/24/2026 Signed DANIEL STADELI (E-filed) Drilling Company: Westerberg Drilling, Inc.




WATER SUPPLY WELL REPORT - Map with location identified must be attached and shall include an approximate scale and north arrow

MARI 72110

4/24/2026

### Map of Hole

<b>STATE OF OREGON WELL LOCATION MAP</b>	<b>Oregon Water Resources Department</b> 725 Summer St NE, Salem OR 97301 (503)986-0900	
This map is supplemental to the WATER SUPPLY WELL REPORT		
<b>LOCATION OF WELL</b>	<b>Well Label: 158762</b>	
Latitude: 45.05283000 Datum: WGS84	<b>Printed: April 7, 2026</b>	
Longitude: -122.91075000	<small>DISCLAIMER: This map is intended to represent the approximate location the well. It is not intended to be construed as survey accurate in any manner.</small>	
Township/Range/Section/Quarter-Quarter Section: WM6.00S2.00W15SENE	<small>Provided by well constructor</small>	
Address of Well: 7324 SEQUOIA ST NE, SALEM, OR 97305		



**MARI 72110****4/24/2026****Map of Hole****Well ID Label #: L-158762****Start Card#: 1081231****Original Log #: Marion 4050****Comments/Remarks:**

The only purpose for the special standard was to allow for drill rig absence during well screen selection/construction & shipping delay.

The original 10" well (MARI 4050) was producing unmanageable quantities of sand and silt. OWRD was consulted & provided permission to deepen this well to allow for well screen installation to eliminate the sand and silt production.

We over drilled the original 10" casing to 20' & replaced the original puddled clay seal with cement. The top of the screen has a 6" flush drive shoe (174.2' – 175.2'). The 4' tail pipe has 1 ¼" x 2.5" lift bar 12" above 3/8" thick bottom plate. 8" shoe cutoff at 296' – 299'.