

WATER SUPPLY WELL REPORT - Map with location identified must be attached and shall include an approximate scale and north arrow

MARI 72139

6/12/2026

Map of Hole

STATE OF OREGON WELL LOCATION MAP

This map is supplemental to the WATER SUPPLY WELL REPORT

Oregon Water Resources Department

725 Summer St NE, Salem OR 97301
(503)986-0900



LOCATION OF WELL

Latitude: 44.79372800 Datum: WGS84

Longitude: -122.76366000

Township/Range/Section/Quarter-Quarter Section:
WM9.00S1.00W13NWNW

Address of Well:

2700 E SANTIAM STREET STAYTON, OR 97383

Well Label: 151232

Printed: June 12, 2026

DISCLAIMER: This map is intended to represent the approximate location the well. It is not intended to be construed as survey accurate in any manner.

Provided by well constructor





BOREHOLE ID:

Well B

PROJECT:	City of Salem Supplemental Groundwater	GROUND SURFACE ELEVATION / DATUM: 480 feet amsl (approximate from GE)	
BORING LOCATION:	2700 E Santiam St, Stayton, OR 97383	TOTAL DEPTH (ft): 74	
DRILLING CONTRACTOR:	Holt Services, Inc.	LOGGED BY: G. Deem	
SAMPLING METHOD:	Cuttings/slurry return; grab		
DRILLING METHOD:	Air Rotary (DR-24 rig)		

DEPTH (feet)	SAMPLES		SAMPLE DESCRIPTION Formation/aquifer name; group name (USCS); consistency/density; color; water content/production; percentages, sizes, angularity/shape; cementation; notes/comments	WELL CONSTRUCTION
	Sample ID	Sample Interval		
0			GW Fill: crushed gravel/drain rock	
			GW Fill: Dark grayish brown (10YR 4/2), poorly sorted GRAVEL with SAND and SILT: mostly fine to coarse rounded GRAVEL up to cobbles; some fine to coarse SAND; minor SILT; trace asphalt cobble sized inclusions	
			Color change to very dark gray (10YR 3/1); grades coarser up to 14", BOULDERS	
10			SM Very dark gray (10YR 3/1), SILTY SAND with GRAVEL; mostly fine to coarse SAND; some SILT; minor fine GRAVEL	Bentonite Chip seal 0-18 ft bgs
			SM As above, grades coarser; increase fine to coarse GRAVEL	
			ML Black (10YR 2/1), SILT with SAND: mostly SILT; some fine to medium SAND	
20			GM Very dark brown (10YR 2/2) poorly sorted GRAVEL with SAND and SILT; mostly rounded fine to coarse GRAVEL up to COBBLES, some fine to coarse SAND; minor SILT	
			GW As above, grades coarser to COBBLES up to BOULDERS	
			GW Very dark gray (10YR 3/1), poorly sorted GRAVEL with SAND: mostly fine to coarse rounded GRAVEL up to COBBLES: some fine to coarse SAND; trace SILT	
30			GW As above, grades finer; mostly rounded fine to coarse GRAVEL up to 2.5"; some fine to coarse SAND; trace SILT	
			GW COBBLES and BOULDERS	
			SM Very dark brown (10YR 2/2) SILTY SAND: mostly fine to coarse SAND; some SILT; trace fine rounded GRAVEL	
40			SM Dark brown (10YR 3/3) SILTY SAND with GRAVEL: mostly fine to coarse SAND; some SILT: minor fine rounded GRAVEL	
			GM Dark yellowish brown (10YR 4/4) poorly sorted GRAVEL with SILT and SAND: mostly fine to coarse rounded GRAVEL up to 1"; some SILT; some fine to coarse SAND	
50			SM Very dark brown (10YR 3/3) well sorted GRAVEL with SILT and SAND: mostly fine GRAVEL, some SILT; some medium SAND	
			GP Dark brown (10YR 3/3) well sorted GRAVEL with SILT and SAND: mostly fine GRAVEL; some SILT; some medium SAND	
60			GM Dark yellowish brown (10YR 3/4) poorly sorted GRAVEL with SILT and SAND: mostly fine to coarse GRAVEL up to 3/4"; some SILT; some fine to coarse SAND	
			GW As above, grades coarser; mostly fine to coarse GRAVEL up to 1"; decrease in SILT	
70			GW Black (10YR 2/1) poorly sorted GRAVEL with SAND: mostly fine to coarse rounded GRAVEL up to 1.5"; some fine to coarse SAND; trace SILT	
				Stainless steel wire-wrap screen, 0.210-in slot size 27-67 ft bgs
				Sump, stainless steel blank 67-74 ft bgs