

STATE OF OREGON
WATER SUPPLY WELL REPORT

MARI 72200

WELL I.D. LABEL# L

158764

START CARD #

1081470

ORIGINAL LOG #

(as required by ORS 537.545 & 537.765 and OAR 690-205-0210)

7/22/2026

(1) LAND OWNER

Owner Well I.D. _____

First Name _____ Last Name _____

Company GRASSMAN FARMING LLC

Address 12783 RIVER RD NE

City GERVAIS State OR Zip 97026

(2) TYPE OF WORK

☒ New Well ☐ Deepening ☐ Conversion

☐ Alteration (complete 2a & 10) ☐ Abandonment (complete 5a)

(2a) PRE-ALTERATION

Casing: Dia + From To Gauge Stl Plstc Wld Thrd
Material From To Amt sacks/lbs
Seal: _____

(3) DRILL METHOD

☒ Rotary Air ☐ Rotary Mud ☐ Cable ☐ Auger

☐ Reverse Rotary ☐ Other _____

(4) PROPOSED USE

☐ Domestic ☒ Irrigation ☐ Community

☐ Industrial/ Commercial ☐ Livestock ☐ Dewatering

☐ Thermal ☐ Injection ☐ Other _____

(5) BORE HOLE CONSTRUCTION

Special Standard ☐ (Attach copy)

Depth of Completed Well 326.00 ft.

BORE HOLE				SEAL			
Dia	From	To	Material	From	To	Amt	sacks/lbs
16	0	59	Cement	0	59	177	S
12	59	326			Calculated	25	
					Calculated		

Seal placement method: ☐ A ☐ B ☒ C ☐ D ☐ E ☐ Other: _____

Backfill placed from _____ ft. to _____ ft. Material _____

Filter pack from 174 ft. to 326 ft. Material GRAVEL Size 4/8

Explosives used: ☐ Type _____ Amount _____

Seal Placement Begin Date 6/25/2026 Begin Time 17:00

(5a) ABANDONMENT USING UNHYDRATED BENTONITE

Proposed Amount

Actual Amount

(6) CASING/LINER

C/L	Dia	+	From	To	Gauge	Mat. Type	Wld	Thrd	Shoe	Shoe Location
C	12	☒	1.5	213.75	0.375	ST	☒		OUT.	174
L	10		174	215.75	0.250	ST	☒		OUT.	319.35
L	8		315.75	326	0.250	ST	☒			

Temp casing ☒ Yes Dia 16 From + 0 To 59

(7) PERFORATIONS/SCREENS

Perforations Method _____

Screens Type V-Wire Material Stainless Steel

Perf/ Screen	Casing/ Liner	Screen Dia	From	To	Scrn/slot width	Slot length	# of slots	Tele/ Pipe size
		8	215.75	315.75	.112			Pipe Size

(8) WELL TESTS: Minimum testing time is 1 hour

Type of Test	Yield (gal/min)	Drawdown	Drill Stem/ Pump Depth	Duration (hr)
Pump	1315	21.8	147	8

Temperature 54 °F Lab analysis ☐ Yes By _____

Water quality concerns? ☐ Yes (describe below) TDS amount 128 ppm

From	To	Description	Amount	Units

(9) LOCATION OF WELL (legal description)

County MARION Twp 5.00 S N/S Range 2.00 W E/W WM

Sec 30 NE 1/4 of the SE 1/4 Tax Lot 1400

Tax Map Number _____ Lot _____

Lat _____ ° _____ ' _____ " or 45.10637000 DMS or DD

Long _____ ° _____ ' _____ " or -122.97400000 DMS or DD

☐ Street address of well ☒ Nearest address

ADJACENT TO AND SOUTH OF 12934 RIVER RD, GERVAIS, OR 97026

(10) STATIC WATER LEVEL

	Date	SWL (psi)	+	SWL (ft)
Existing Well / Pre-Alteration				
Completed Well	6/25/2026			65.6
Flowing Artesian?	☐			
Dry Hole?	☐			

WATER BEARING ZONES

Depth water was first found 20.00

SWL Date	From	To	Est Flow	SWL (psi)	+	SWL (ft)
3/16/2026	20	40	10			10.3
3/25/2026	209	320	2500			38.5

(11) WELL LOG

Ground Elevation 181.37 FT

Material	From	To
Soil	0	1
Clay Tan Sandy	1	40
Clay Grey Medium	40	60
Packed Silt Grey	60	68
Sand Black Medium	68	78
Clay Grey Sticky	78	90
Sand & Gravel	90	101
Gravel with Clay	101	105
Sand & Gravel Brown Loose	105	125
Gravel & Sand Loose some Cemented	125	147
Clay Blue	147	165
Sand Black	165	188
Cemented Gravel Dry	188	189
Clay Grey	189	197
Gravel with Sand	197	200
Sand Black	200	209
Sand & Gravel Black & Blue	209	265
Cemented Gravel with Lenses of Loose Gravel	265	275
Large Loose Gravel 3" to 5" Clean	275	282

Construction

Begin Date 3/12/2026 Begin Time 08:00 End Date 6/25/2026

(unbonded) Water Well Constructor Certification

I certify that the work I performed on the construction, deepening, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.

License Number 1358 Date 7/22/2026

Signed BYRON STADELI (E-filed)

(bonded) Water Well Constructor Certification

I accept responsibility for the construction, deepening, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

License Number 1487 Date 7/22/2026

Signed DANIEL STADELI (E-filed)

Drilling Company: Westerberg Drilling, Inc.

ORIGINAL - WATER RESOURCES DEPARTMENT

THIS REPORT MUST BE SUBMITTED TO THE WATER RESOURCES DEPARTMENT WITHIN 30 DAYS OF COMPLETION OF WORK Form Version:

New exempt use wells must be submitted with a map and recording fee.

WATER SUPPLY WELL REPORT - Map with location identified must be attached and shall include an approximate scale and north arrow

MARI 72200

7/22/2026

Map of Hole

