

STATE OF OREGON
WATER SUPPLY WELL REPORT

MARI 72234

WELL I.D. LABEL# L

157719

START CARD #

1083054

ORIGINAL LOG #

(as required by ORS 537.545 & 537.765 and OAR 690-205-0210)

8/11/2026

(1) LAND OWNER

Owner Well I.D. 6805

First Name RANDY

Last Name JACKSON

Company _____

Address 140 N. PIONEER ST.

City SILVERTON State OR Zip 97381

(2) TYPE OF WORK

☒ New Well ☐ Deepening ☐ Conversion

☐ Alteration (complete 2a & 10) ☐ Abandonment (complete 5a)

(2a) PRE-ALTERATION

Casing:

Dia	+	From	To	Gauge	Stl	Plstc	Wld	Thrd

Material From To Amt sacks/lbs
Seal: _____

(3) DRILL METHOD

☒ Rotary Air ☐ Rotary Mud ☐ Cable ☐ Auger

☐ Reverse Rotary ☐ Other _____

(4) PROPOSED USE

☒ Domestic ☐ Irrigation ☐ Community

☐ Industrial/ Commercial ☐ Livestock ☐ Dewatering

☐ Thermal ☐ Injection ☐ Other _____

(5) BORE HOLE CONSTRUCTION

Special Standard ☐ (Attach copy)

Depth of Completed Well 420.00 ft.

BORE HOLE			SEAL			Amt	sacks/ lbs
Dia	From	To	Material	From	To		
10	0	119	Bentonite	0	119	56	S
6	119	420			Calculated	56	
					Calculated		

Seal placement method: ☐ A ☐ B ☐ C ☐ D ☐ E ☒ Other: POURED DRY

Backfill placed from _____ ft. to _____ ft. Material _____

Filter pack from _____ ft. to _____ ft. Material _____ Size _____

Explosives used: ☐ Type _____ Amount _____

Seal Placement Begin Date 7/31/2026 Begin Time 17 00

(5a) ABANDONMENT USING UNHYDRATED BENTONITE

Proposed Amount _____ Actual Amount _____

(6) CASING/LINER

C/L	Dia	+	From	To	Gauge	Mat. Type	Wld	Thrd	Shoe	Shoe Location
C	6	☒	1	119	0.250	ST	☒			
L	4.5		0	420	Sch40	PL	☒			

Temp casing ☐ Yes Dia _____ From + _____ To _____

(7) PERFORATIONS/SCREENS

Perforations Method Drilled 1/4" holes

Screens Type _____ Material _____

Perf/	Casing/	Screen			Scrn/slot	Slot	# of	Tele/
Screen	Liner	Dia	From	To	width	length	slots	Pipe size
Perf	Liner	4.5	200	420	.25	0.25	1000	

(8) WELL TESTS: Minimum testing time is 1 hour

Type of Test	Yield (gal/min)	Drawdown	Drill Stem/ Pump Depth	Duration (hr)
Air	7		419	1

Temperature 53 °F Lab analysis ☐ Yes By _____

Water quality concerns? ☐ Yes (describe below) TDS amount 147 ppm

From	To	Description	Amount	Units

(9) LOCATION OF WELL (legal description)

County MARION Twp 6.00 S N/S Range 1.00 W E/W WM

Sec 36 SW 1/4 of the NW 1/4 Tax Lot 2200

Tax Map Number _____ Lot _____

Lat _____ " or 45.00897000 DMS or DD

Long _____ " or -122.76216100 DMS or DD

☒ Street address of well ☐ Nearest address

140 N. PIONEER ST., SILVERTON, OR 97381

(10) STATIC WATER LEVEL

	Date	SWL (psi)	+	SWL (ft)
Existing Well / Pre-Alteration				
Completed Well	8/5/2026			236
Flowing Artesian?	☐			
Dry Hole?	☐			

WATER BEARING ZONES

Depth water was first found 290.00

SWL Date	From	To	Est Flow	SWL (psi)	+	SWL (ft)
8/4/2026	290	300	1			236
8/5/2026	379	380	6			236

(11) WELL LOG

Ground Elevation 408.47 FT

Material	From	To
Top soil	0	2
Brown clay w/boulders	2	8
Gray basalt	8	18
Brown clay decomposed basalt	18	30
Gray basalt strips	30	45
Hard gray sandstone	45	70
Gray basalt	70	80
Dark gray basalt	80	129
Fractured gray basalt	129	132
Dark gray basalt	132	200
Hard gray basalt	200	270
Fractured gray basalt	270	277
Soft gray sandstone	277	290
Blue sandstone soft	290	300
Gray fractured basalt	300	307
Hard gray sandstone	307	360
Medium gray sandstone	360	385
Gray sandstone basalt mix	385	415
Gray basalt	415	417

Construction

Begin Date 7/28/2026 Begin Time 08 00 End Date 8/5/2026

(unbonded) Water Well Constructor Certification

I certify that the work I performed on the construction, deepening, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.

License Number 1888 Date 8/11/2026

Signed KENNETH GILLET (E-filed)

(bonded) Water Well Constructor Certification

I accept responsibility for the construction, deepening, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

License Number 1684 Date 8/11/2026

Signed BRET JONES (E-filed)

Drilling Company: Jones Drilling Co., Inc.

ORIGINAL - WATER RESOURCES DEPARTMENT

THIS REPORT MUST BE SUBMITTED TO THE WATER RESOURCES DEPARTMENT WITHIN 30 DAYS OF COMPLETION OF WORK Form Version:

New exempt use wells must be submitted with a map and recording fee.

WATER SUPPLY WELL REPORT - Map with location identified must be attached and shall include an approximate scale and north arrow

MARI 72234

8/11/2026

Map of Hole

STATE OF OREGON WELL LOCATION MAP

This map is supplemental to the WATER SUPPLY WELL REPORT

Oregon Water Resources Department

725 Summer St NE, Salem OR 97301
(503)986-0900



LOCATION OF WELL

Latitude: 45.00897000 Datum: WGS84

Longitude: -122.76216100

Township/Range/Section/Quarter-Quarter Section:

WM6.00S1.00W36SWNW

Address of Well:

140 N. PIONEER ST., SILVERTON, OR 97381

Well Label: 157719

Printed: August 11, 2026

DISCLAIMER: This map is intended to represent the approximate location the well. It is not intended to be construed as survey accurate in any manner.

Provided by well constructor

