

STATE OF OREGON
WATER SUPPLY WELL REPORT

MARI 72235

WELL I.D. LABEL# L

157421

START CARD #

1082016

ORIGINAL LOG #

(as required by ORS 537.545 & 537.765 and OAR 690-205-0210)

8/12/2026

(1) LAND OWNER

Owner Well I.D. DR-3848

First Name JED

Last Name BENNETT

Company _____

Address 6578 CONGRESSIONAL CT. SE

City SALEM

State OR

Zip 97306

(2) TYPE OF WORK

☒ New Well ☐ Deepening ☐ Conversion

☐ Alteration (complete 2a & 10) ☐ Abandonment (complete 5a)

(2a) PRE-ALTERATION

Casing:

Dia	+	From	To	Gauge	Stl	Plstc	Wld	Thrd

Material From To Amt sacks/lbs
Seal: _____

(3) DRILL METHOD

☒ Rotary Air ☐ Rotary Mud ☐ Cable ☐ Auger
☐ Reverse Rotary ☐ Other _____

(4) PROPOSED USE

☒ Domestic ☐ Irrigation ☐ Community
☐ Industrial/ Commercial ☐ Livestock ☐ Dewatering
☐ Thermal ☐ Injection ☐ Other _____

(5) BORE HOLE CONSTRUCTION

Special Standard ☐ (Attach copy)

Depth of Completed Well 300.00 ft.

BORE HOLE				SEAL			
Dia	From	To	Material	From	To	Amt	sacks/lbs
10	0	209	Bentonite	0	17	9	S
6	209	300			Calculated	7.76	
			Cement	17	209	52	S
					Calculated	51.54	

Seal placement method: ☐ A ☐ B ☒ C ☐ D ☐ E ☒ Other: POURED DRY

Backfill placed from _____ ft. to _____ ft. Material _____

Filter pack from _____ ft. to _____ ft. Material _____ Size _____

Explosives used: ☐ Type _____ Amount _____

Seal Placement Begin Date 8/7/2026 Begin Time 15 00

(5a) ABANDONMENT USING UNHYDRATED BENTONITE

Proposed Amount _____ Actual Amount _____

(6) CASING/LINER

C/L	Dia	+	From	To	Gauge	Mat. Type	Wld	Thrd	Shoe	Location
C	6	☒	1.4	209	0.250	ST	☒		OUT.	209
L	4.5		0	300	Sch40	PL		☒		

Temp casing ☒ Yes Dia 10 From + ☒ 1 To 17

(7) PERFORATIONS/SCREENS

Perforations Method Saw Cut

Screens Type _____ Material _____

Perf/ Screen	Casing/ Liner	Screen Dia	From	To	Scrm/slot width	Slot length	# of slots	Tele/ Pipe size
Perf	Liner	4.5	264	297	.125	6	72	

(8) WELL TESTS: Minimum testing time is 1 hour

Type of Test	Yield (gal/min)	Drawdown	Drill Stem/ Pump Depth	Duration (hr)
Air	40		295	2

Temperature 53 °F Lab analysis ☐ Yes By _____

Water quality concerns? ☐ Yes (describe below) TDS amount 46 ppm
From To Description Amount Units

(9) LOCATION OF WELL (legal description)

County MARION Twp 8.00 S N/S Range 2.00 W E/W WM

Sec 17 NW 1/4 of the SE 1/4 Tax Lot 4300

Tax Map Number _____ Lot _____

Lat _____ " or 44.87454215 DMS or DD

Long _____ " or -122.95431060 DMS or DD

☒ Street address of well ☐ Nearest address

5350 DESTINY LANE SE.

SALEM OR. 97317

(10) STATIC WATER LEVEL

	Date	SWL(psi)	+	SWL(ft)
Existing Well / Pre-Alteration				
Completed Well	8/11/2026			204
Flowing Artesian?	☐			
Dry Hole?	☐			

WATER BEARING ZONES

Depth water was first found 42.00

SWL Date	From	To	Est Flow	SWL(psi)	+	SWL(ft)
8/11/2026	42	65	10			42
8/11/2026	220	296	40			204

(11) WELL LOG

Ground Elevation 468.68 FT

Material	From	To
Crushed Rock Fill	0	3
Fill Dirt	3	12
Clay Brown	12	16
Shale Decomposed Brown	16	26
Basalt Gray	26	30
Clay Light Brown	30	35
Clay Dark Brown	35	42
Basalt Black/Gray Medium	42	220
Basalt Black/Gray Honeycomb	220	296
Claystone Gray Soft	296	300

Construction

Begin Date 7/28/2026 Begin Time 10 00 End Date 8/11/2026

(unbonded) Water Well Constructor Certification

I certify that the work I performed on the construction, deepening, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.

License Number 2107 Date 8/12/2026

Signed KYLE MOORE (E-filed)

(bonded) Water Well Constructor Certification

I accept responsibility for the construction, deepening, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

License Number 664 Date 8/12/2026

Signed CHARLES NUGENT (E-filed)

Drilling Company: Nugent Drilling Co. Lebanon OR. 541-258-7816

ORIGINAL - WATER RESOURCES DEPARTMENT

THIS REPORT MUST BE SUBMITTED TO THE WATER RESOURCES DEPARTMENT WITHIN 30 DAYS OF COMPLETION OF WORK Form Version:

New exempt use wells must be submitted with a map and recording fee.

WATER SUPPLY WELL REPORT - Map with location identified must be attached and shall include an approximate scale and north arrow

MARI 72235

8/12/2026

Map of Hole

