

STATE OF OREGON
WATER SUPPLY WELL REPORT

MARI 72239

WELL I.D. LABEL# L

141637

START CARD #

1082187

ORIGINAL LOG #

(as required by ORS 537.545 & 537.765 and OAR 690-205-0210)

8/14/2026

(1) LAND OWNER

Owner Well I.D. _____

First Name ROGERLast Name KOWASH

Company _____

Address 4440 MAHONY ROADCity SAINT PAULState ORZip 97137**(2) TYPE OF WORK**☒ New Well ☐ Deepening ☐ Conversion☐ Alteration (complete 2a & 10) ☐ Abandonment (complete 5a)**(2a) PRE-ALTERATION**

Casing:

Dia	+	From	To	Gauge	Stl	Plstc	Wld	Thrd
					☐	☐	☐	☐

Seal:

Material	From	To	Amt	sacks/lbs

(3) DRILL METHOD☐ Rotary Air ☐ Rotary Mud ☒ Cable ☐ Auger☐ Reverse Rotary ☐ Other _____**(4) PROPOSED USE**☒ Domestic ☐ Irrigation ☐ Community☐ Industrial/ Commercial ☐ Livestock ☐ Dewatering☐ Thermal ☐ Injection ☐ Other _____**(5) BORE HOLE CONSTRUCTION**Special Standard ☐ (Attach copy)Depth of Completed Well 135.00 ft.

BORE HOLE				SEAL				sacks/
Dia	From	To	Material	From	To	Amt	lbs	
10	0	35	Bentonite Chips	0	35	18	S	
6	35	135			Calculated	17.5		
					Calculated			

Seal placement method: ☐ A ☐ B ☐ C ☐ D ☐ E ☒ Other: OAR 690-210-0340

Backfill placed from _____ ft. to _____ ft. Material _____

Filter pack from _____ ft. to _____ ft. Material _____ Size _____

Explosives used: ☐ Type _____ Amount _____Seal Placement Begin Date 6/2/2026 Begin Time 23 30**(5a) ABANDONMENT USING UNHYDRATED BENTONITE**

Proposed Amount

Actual Amount

(6) CASING/LINER

C/L	Dia	+	From	To	Gauge	Mat. Type	Wld	Thrd	Shoe	Location
C	6	☒	3	135	0.250	ST	☒		OUT.	135

Temp casing ☐ Yes Dia _____ From + ☐ _____ To _____**(7) PERFORATIONS/SCREENS**

Perforations Method _____

Screens Type _____ Material _____

Perf/ Screen	Casing/ Liner	Screen Dia	From	To	Scrn/slot width	Slot length	# of slots	Tele/ Pipe size

(8) WELL TESTS: Minimum testing time is 1 hour

Type of Test	Yield (gal/min)	Drawdown	Drill Stem/ Pump Depth	Duration (hr)
Pump	60	19.5	105	2

Temperature 53 °F Lab analysis ☐ Yes By _____Water quality concerns? ☐ Yes (describe below) TDS amount 92 ppm

From	To	Description	Amount	Units

(9) LOCATION OF WELL (legal description)County MARION Twp 5.00 S N/S Range 2.00 W E/W WMSec 16 SE 1/4 of the SW 1/4 Tax Lot 1000

Tax Map Number _____ Lot _____

Lat _____ " or 45.13101100 DMS or DD

Long _____ " or -122.94355000 DMS or DD

☒ Street address of well ☐ Nearest address

14563 MANNING ROAD, WOODBURN, OR, 97071

(10) STATIC WATER LEVEL

	Date	SWL (psi)	+	SWL (ft)
Existing Well / Pre-Alteration				
Completed Well	7/16/2026			23.5

Flowing Artesian? ☐ Dry Hole? ☐

WATER BEARING ZONES

Depth water was first found 94.00

SWL Date	From	To	Est Flow	SWL (psi)	+	SWL (ft)
6/4/2026	94	101	50			27
6/15/2026	101	135	100			24

(11) WELL LOGGround Elevation 176.63 FT

Material	From	To
brown clay medium	0	25
grey clay medium	25	43
blue grey clay sandy	43	62
dark grey silt and fine sand	62	73
grey clay sandy	73	84
dark grey silt	84	94
black sand fine	94	103
black sand and gr	103	108
black sand medium heaves	108	115
black sand and gravel 10% gravel	115	126
black sand and gravel 50% gravel	126	130
black sand and gravel cemented	130	132
black sand and gravel 80% gravel	132	135

Construction

Begin Date 5/29/2026 Begin Time 10 00 End Date 7/16/2026**(unbonded) Water Well Constructor Certification**

I certify that the work I performed on the construction, deepening, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.

License Number 2041 Date 8/13/2026Signed TRAVIS RUSH (E-filed)**(bonded) Water Well Constructor Certification**

I accept responsibility for the construction, deepening, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

License Number 783 Date 8/14/2026Signed IVAN GROSSEN (E-filed)Drilling Company: grossen well drilling

ORIGINAL - WATER RESOURCES DEPARTMENT

THIS REPORT MUST BE SUBMITTED TO THE WATER RESOURCES DEPARTMENT WITHIN 30 DAYS OF COMPLETION OF WORK Form Version:

New exempt use wells must be submitted with a map and recording fee.

WATER SUPPLY WELL REPORT - Map with location identified must be attached and shall include an approximate scale and north arrow

MARI 72239

8/14/2026

Map of Hole

STATE OF OREGON WELL LOCATION MAP

This map is supplemental to the WATER SUPPLY WELL REPORT

Oregon Water Resources Department

725 Summer St NE, Salem OR 97301
(503)986-0900



LOCATION OF WELL

Latitude: 45.13101100 Datum: WGS84

Longitude: -122.94355000

Township/Range/Section/Quarter-Quarter Section:
WM5.00S2.00W16SESW

Address of Well:

14563 MANNING ROAD, WOODBURN, OR, 97071

Well Label: 141637

Printed: August 14, 2026

DISCLAIMER: This map is intended to represent the approximate location the well. It is not intended to be construed as survey accurate in any manner.

Provided by well constructor

