

STATE OF OREGON
WATER SUPPLY WELL REPORT

MARI 72258

WELL I.D. LABEL# L

156296

START CARD #

1082949

ORIGINAL LOG #

(as required by ORS 537.545 & 537.765 and OAR 690-205-0210)

8/25/2026

(1) LAND OWNER

Owner Well I.D. _____

First Name CRAIG

Last Name SCHURTER

Company SCHURTER AG SERVICES INC

Address 6541 TORVEND RD NE

City SILVERTON

State OR

Zip 97381

(2) TYPE OF WORK

☒ New Well ☐ Deepening ☐ Conversion

☐ Alteration (complete 2a & 10) ☐ Abandonment (complete 5a)

(2a) PRE-ALTERATION

Casing:

Dia	+	From	To	Gauge	Stl	Plstc	Wld	Thrd

Material From To Amt sacks/lbs
Seal:

--	--	--	--	--	--	--	--	--

(3) DRILL METHOD

☒ Rotary Air ☐ Rotary Mud ☐ Cable ☐ Auger

☐ Reverse Rotary ☐ Other _____

(4) PROPOSED USE

☐ Domestic ☒ Irrigation ☐ Community

☐ Industrial/ Commercial ☐ Livestock ☐ Dewatering

☐ Thermal ☐ Injection ☐ Other _____

(5) BORE HOLE CONSTRUCTION

Special Standard ☐ (Attach copy)

Depth of Completed Well 620.00 ft.

BORE HOLE			SEAL			Amt	sacks/ lbs
Dia	From	To	Material	From	To		
12	0	300	Bentonite	0	9.5	7	S
8	300	525	Calculated			4	
7.88	525	620	Cement	9.5	300	161	S
			Calculated			95	

Seal placement method: ☐ A ☐ B ☒ C ☐ D ☐ E ☒ Other: POURED & PROBED

Backfill placed from _____ ft. to _____ ft. Material _____

Filter pack from _____ ft. to _____ ft. Material _____ Size _____

Explosives used: ☐ Type _____ Amount _____

Seal Placement Begin Date 8/5/2026 Begin Time 18 45

(5a) ABANDONMENT USING UNHYDRATED BENTONITE

Proposed Amount _____ Actual Amount _____

(6) CASING/LINER

C/L	Dia	+	From	To	Gauge	Mat. Type	Wld	Thrd	Shoe	Location
C	8	☒	1.5	300	0.250	ST	☒		OUT.	300

Temp casing ☒ Yes Dia 12 From + ☒ 1 To 177

(7) PERFORATIONS/SCREENS

Perforations Method _____

Screens Type _____ Material _____

Perf/ Screen	Casing/ Liner	Screen Dia	From	To	Scrm/slot width	Slot length	# of slots	Tele/ Pipe size

(8) WELL TESTS: Minimum testing time is 1 hour

Type of Test	Yield (gal/min)	Drawdown	Drill Stem/ Pump Depth	Duration (hr)
Air	600		620	10

Temperature 60 °F Lab analysis ☐ Yes By _____

Water quality concerns? ☐ Yes (describe below) TDS amount 205 ppm

From	To	Description	Amount	Units

(9) LOCATION OF WELL (legal description)

County MARION Twp 6.00 S N/S Range 1.00 W E/W WM

Sec 27 SW 1/4 of the SW 1/4 Tax Lot 1300

Tax Map Number _____ Lot _____

Lat _____ ° _____ ' _____ " or 45.01603000 DMS or DD

Long _____ ° _____ ' _____ " or -122.80068000 DMS or DD

☐ Street address of well ☒ Nearest address

FARM IMMEDIATELY NORTH OF 1502 PINE ST NE, SILVERTON, OR 97381

(10) STATIC WATER LEVEL

	Date	SWL (psi)	+	SWL (ft)
Existing Well / Pre-Alteration				
Completed Well	8/12/2026			122.33
Flowing Artesian? ☐		Dry Hole? ☐		

WATER BEARING ZONES

Depth water was first found 196.00

SWL Date	From	To	Est Flow	SWL (psi)	+	SWL (ft)
8/3/2026	196	265	60			120.5
8/12/2026	312	597	600			122.33

(11) WELL LOG

Ground Elevation 216.58 FT

Material	From	To
Soil	0	1
Clay Brown Hard	1	18
Clay with Gravel Grey	18	30
Cemented Gravel Grey	30	58
Gravel with Blue Claystone	58	64
Gravel with Brown Clay	64	78
Packed Silt Blue	78	85
Gravel	85	93
Clay with Gravel Brown	93	110
Clay Brown Sticky	110	121
Gravel Cemented Grey	121	130
Clay Grey Medium	130	145
Gravel	145	147
Clay Grey	147	151
Gravel & Clay	151	158
Cemented Gravel Weathered	158	180
Cemented Gravel with Clay	180	196
Basalt Black Medium	196	212
Basalt Grey Hard Coarse Grain	212	237

Construction

Begin Date 7/27/2026 Begin Time 13 00 End Date 8/12/2026

(unbonded) Water Well Constructor Certification

I certify that the work I performed on the construction, deepening, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.

License Number 1358 Date 8/25/2026

Signed BYRON STADELI (E-filed)

(bonded) Water Well Constructor Certification

I accept responsibility for the construction, deepening, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

License Number 1487 Date 8/25/2026

Signed DANIEL STADELI (E-filed)

Drilling Company: R. Stadel & Sons, Well & Pump, Inc.

ORIGINAL - WATER RESOURCES DEPARTMENT

THIS REPORT MUST BE SUBMITTED TO THE WATER RESOURCES DEPARTMENT WITHIN 30 DAYS OF COMPLETION OF WORK Form Version:

New exempt use wells must be submitted with a map and recording fee.

12" drive shoe cut off at 175' - 177'.

WATER SUPPLY WELL REPORT - Map with location identified must be attached and shall include an approximate scale and north arrow

MARI 72258

8/25/2026

Map of Hole

STATE OF OREGON WELL LOCATION MAP

This map is supplemental to the WATER SUPPLY WELL REPORT

Oregon Water Resources Department

725 Summer St NE, Salem OR 97301
(503)986-0900



LOCATION OF WELL

Latitude: 45.01603000 Datum: WGS84

Longitude: -122.80068000

Township/Range/Section/Quarter-Quarter Section:

WM6.00S1.00W27SWSW

Address of Well:

FARM IMMEDIATELY NORTH OF 1502 PINE ST NE, SILVERTON, OR 97381

Well Label: 156296

Printed: August 21, 2026

DISCLAIMER: This map is intended to represent the approximate location the well. It is not intended to be construed as survey accurate in any manner.

Provided by well constructor

