

STATE OF OREGON
WATER SUPPLY WELL REPORT

MARI 72289

WELL I.D. LABEL# L

Page 1 of 3

162114

START CARD #

1083333

ORIGINAL LOG #

(as required by ORS 537.545 & 537.765 and OAR 690-205-0210)

9/16/2026

(1) LAND OWNER

Owner Well I.D.

First Name MIKE

Last Name EVERITT

Company

Address 3894 RIDGEWAY DR SE

City TURNER

State OR

Zip 97392

(2) TYPE OF WORK

☒ New Well

☐ Deepening

☐ Conversion

☐ Alteration (complete 2a & 10)

☐ Abandonment (complete 5a)

(2a) PRE-ALTERATION

Casing: Dia + From To Gauge Std Plstc Wld Thrd
Material From To Amt sacks/lbs
Seal: Material From To Amt sacks/lbs

(3) DRILL METHOD

☒ Rotary Air ☐ Rotary Mud ☐ Cable ☐ Auger

☐ Reverse Rotary ☐ Other

(4) PROPOSED USE

☒ Domestic

☐ Irrigation

☐ Community

☐ Industrial/ Commercial

☐ Livestock

☐ Dewatering

☐ Thermal ☐ Injection ☐ Other

(5) BORE HOLE CONSTRUCTION

Special Standard ☐ (Attach copy)

Depth of Completed Well 204.00 ft.

BORE HOLE				SEAL			
Dia	From	To	Material	From	To	Amt	sacks/lbs
10	0	78.5	Bentonite Chips	0	4	2	S
6.25	78.5	204	Calculated			2	
			Cement with 5% Bently	4	55	15	S
			Calculated			12.75	

Seal placement method: ☐ A ☒ B ☒ C ☐ D ☐ E ☒ Other: POURED AND PROBED

Backfill placed from ft. to ft. Material

Filter pack from ft. to ft. Material Size

Explosives used: ☐ Type Amount

Seal Placement Begin Date 9/11/2026 Begin Time 15 00

(5a) ABANDONMENT USING UNHYDRATED BENTONITE

Proposed Amount Actual Amount

(6) CASING/LINER

C/L	Dia	+ From To Gauge	Mat. Type	Wld	Thrd	Shoe	Location
C	6	☒ 1.5 78.5 0.250	ST	☒		IN.	78.5
L	4	☐ 4 204 Sch40	PL		☒		

Temp casing ☒ Yes Dia 10 From + 0 To 20

(7) PERFORATIONS/SCREENS

Perforations Method Electric saw

Screens Type Material

Perf/ Screen	Casing/ Liner	Screen Dia	From	To	Scrn/slot width	Slot length	# of slots	Tele/ Pipe size
		4	164	204	.125	6	60	

(8) WELL TESTS: Minimum testing time is 1 hour

Type of Test	Yield (gal/min)	Drawdown	Drill Stem/ Pump Depth	Duration (hr)
Air	10		200	1

Temperature 54 °F Lab analysis ☐ Yes By

Water quality concerns? ☐ Yes (describe below) TDS amount 50 ppm

From To	Description	Amount	Units

(9) LOCATION OF WELL (legal description)

County MARION Twp 9.00 S N/S Range 2.00 W E/W WM

Sec 6 SE 1/4 of the SW 1/4 Tax Lot 300

Tax Map Number Lot

Lat ° ' " or 44.81070026 DMS or DD

Long ° ' " or -122.98205637 DMS or DD

☒ Street address of well ☐ Nearest address

3894 RIDGEWAY DR SE, TURNER, OR 97392

(10) STATIC WATER LEVEL

	Date	SWL (psi)	+	SWL (ft)
Existing Well / Pre-Alteration				
Completed Well	9/14/2026			1
Flowing Artesian? ☐ Dry Hole? ☐				

WATER BEARING ZONES

Depth water was first found 70.00

SWL Date	From	To	Est Flow	SWL (psi)	+	SWL (ft)
9/14/2026	70	163	15			1

(11) WELL LOG

Ground Elevation 346.99 FT

Material	From	To
Topsoil	0	2
Clay Brown	2	9
Clay Grey	9	16
Clay Tan	16	25
Basalt Grey and Brown Broken	25	40
Basalt Grey w/ Brown Fractures	40	60
Basalt Grey and Brown Broken and Caving	60	70
Basalt Grey	70	90
Basalt Grey w/ Large Brown Fractures	90	97
Basalt Grey w/ Green Fractures	97	110
Basalt Grey w/ Brown Fractures	110	118
Basalt Grey w/ Green Fractures	118	135
Basalt Grey w/ Brown Fractures	135	163
Basalt Grey w/ Green Fractures	163	204

Construction

Begin Date 9/10/2026 Begin Time 08 00 End Date 9/14/2026

(unbonded) Water Well Constructor Certification

I certify that the work I performed on the construction, deepening, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.

License Number 2090 Date 9/14/2026

Signed JACK BOLLER (E-filed)

(bonded) Water Well Constructor Certification

I accept responsibility for the construction, deepening, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

License Number 1394 Date 9/15/2026

Signed EUGENE MACK (E-filed)

Drilling Company: Mack Drilling Company Inc.

ORIGINAL - WATER RESOURCES DEPARTMENT

THIS REPORT MUST BE SUBMITTED TO THE WATER RESOURCES DEPARTMENT WITHIN 30 DAYS OF COMPLETION OF WORK Form Version:

New exempt use wells must be submitted with a map and recording fee.

WATER SUPPLY WELL REPORT - Map with location identified must be attached and shall include an approximate scale and north arrow

MARI 72289

9/16/2026

Map of Hole

STATE OF OREGON WELL LOCATION MAP

This map is supplemental to the WATER SUPPLY WELL REPORT

Oregon Water Resources Department

725 Summer St NE, Salem OR 97301
(503)986-0900



LOCATION OF WELL

Latitude: 44.81070026 Datum: WGS84

Longitude: -122.98205637

Township/Range/Section/Quarter-Quarter Section:
WM9.00S2.00W6SESW

Address of Well:

3894 RIDGEWAY DR SE, TURNER, OR 97392

Well Label: 162114

Printed: September 16, 2026

DISCLAIMER: This map is intended to represent the approximate location the well. It is not intended to be construed as survey accurate in any manner.

Provided by well constructor

